Harrison

Mill and Overlay approximately 3.8 miles of US Highway 90, from I-110 to the East Bridge abut. of Biloxi Bay Bridge, known as Maintenance Project No. MP-6090-24(025) / 302701, in the County of Harrison, State of Mississippi.

REF #	ITEM DESCRIPTION	ITEM QUANTITY	UNITS	MISSISSIPPI DEPARTMENT OF TRANSPORTATION	WARREN PAVING INC.	MALLETTE BROS. CONSTR. CO. INC.	HUEY STOCKSTILL INC.		
				1,197,559.30	1,172,275.50	1,238,278.00	1,315,263.00	0.00	0.00
					1	2	3	4	5
10	Removal of Guard Rail Including Post, Blockouts &	400.000	LF		6.5000	6.5000	9.0000	0.0000	0.0000
20	Removal of Pavement, All Types and Depths	50.000	SY		75.0000	100.0000	42.0000	0.0000	0.0000
30	Removal of Traffic Stripe	50,000.000	LF		1.0000	1.0000	1.0000	0.0000	0.0000
40	Hot Mix Asphalt, MT, 9.5-mm mixture	8,250.000	T		59.9500	58.0000	50.0000	0.0000	0.0000
50	Hot Mix Asphalt, MT, 9.5-mm mixture, Leveling	800.000	T		59.9500	65.0000	50.0000	0.0000	0.0000
60	Hot Mix Asphalt, MT, 19-mm mixture	50.000	T		65.0000	100.0000	150.0000	0.0000	0.0000
70	Cold Milling of Bituminous Pavement, All Depths	130,000.000	SY		0.6000	1.0000	2.0000	0.0000	0.0000
80	Sawing and Sealing Transverse Joints in Asphalt	35,000.000	LF		2.9000	3.0800	3.0000	0.0000	0.0000
90	Guard Rail, Class A, Type 1, 'W' Beam	300.000	LF		20.0000	20.0000	20.0000	0.0000	0.0000
100	Guard Rail, Bridge End Section, Type A	2.000	E		1,250.0000	1,250.0000	1,300.0000	0.0000	0.0000
110	Guard Rail, Terminal End Section	2.000	E		2,250.0000	2,250.0000	2,200.0000	0.0000	0.0000
120	Temporary Traffic Stripe, Continuous White	3.000	MI		200.0000	200.0000	200.0000	0.0000	0.0000
130	Temporary Traffic Stripe, Continuous Yellow	2.000	MI		200.0000	200.0000	200.0000	0.0000	0.0000
140	Temporary Traffic Stripe, Skip White	5.000	MI		1,000.0000	1,000.0000	1,000.0000	0.0000	0.0000
150	Temporary Traffic Stripe, Legend	11,128.000	LF		0.5000	0.5000	0.5000	0.0000	0.0000
160	6" Thermoplastic Edge Stripe, Continuous White	3.000	MI		3,000.0000	3,000.0000	3,000.0000	0.0000	0.0000
170	6" Thermoplastic Edge Stripe, Continuous Yellow	2.000	MI		3,000.0000	3,000.0000	1,000.0000	0.0000	0.0000
180	6" Thermoplastic Traffic Stripe, Skip White	5.000	MI		1,000.0000	1,000.0000	3,000.0000	0.0000	0.0000
190	Thermoplastic Detail Stripe, White	16,747.000	LF		1.2500	1.2500	1.5000	0.0000	0.0000
200	Thermoplastic Detail Stripe, Yellow	13,511.000	LF		1.2500	1.2500	1.5000	0.0000	0.0000
210	Thermoplastic Legend, White	4,003.000	SF		5.0000	5.0000	5.0000	0.0000	0.0000
220	Thermoplastic Legend, White	11,128.000	LF		1.5000	1.5000	1.5000	0.0000	0.0000
230	Red-Clear Reflective High Performance Raised Markers	934.000	E		4.5000	4.5000	5.0000	0.0000	0.0000
240	Two-Way Yellow Reflective High Performance Raised	351.000	E		4.5000	4.5000	5.0000	0.0000	0.0000
250	6" High Performance Cold Plastic Traffic Stripe,	3.000	MI		15,500.0000	15,500.0000	15,000.0000	0.0000	0.0000
260	6" High Performance Cold Plastic Traffic Stripe,	3.000	MI		15,500.0000	15,500.0000	3,400.0000	0.0000	0.0000
270	6" High Performance Cold Plastic Traffic Stripe, Skip	3.000	MI		3,500.0000	3,500.0000	15,000.0000	0.0000	0.0000
280	Delineators, Guard Rail, White	14.000	E		18.0000	18.0000	20.0000	0.0000	0.0000
290	Vehicle Loop Assemblies	7,500.000	LF		10.0000	10.5000	10.0000	0.0000	0.0000
300	Additional Construction Signs	0.000	SF		10.0000	10.0000	10.0000	0.0000	0.0000
310	Maintenance of Traffic	0.000	LS		87,000.0000	100,000.0000	120,000.0000	0.0000	0.0000