Jasper

Installation of a Traffic Signal at the intersection of Mississippi Highway 528 and Mississippi Highway 18, known as Federal Aid Project No. STP-0022-01(057) / 103032, in the County of Jasper, State of Mississippi

REF#	SM ITEM	ITEM DESCRIPTION	ITEM QUANTITY	UNITS	MISSISSIPPI DEPARTMENT OF TRANSPORTATION	LEWIS ELECTRIC INC	B & B ELECTRICAL & UTILITY CONTRACTORS	TOOMER ELECTRICAL COMPANY INC.		
					155,017.00	143,849.00	159,235.20	205,204.86	0.00	0.00
						1	2	3	4	5
10	202-B038	Removal of Curb, All Types	50.000	LF		22.0000	30.0000	15.0000	0.0000	0.0000
20	202-B076	Removal of Traffic Stripe	1,105.000	LF		2.0000	1.5000	3.0300	0.0000	0.0000
30	403-A015	Hot Mix Asphalt, ST, 9.5-mm mixture	1.000	T		2,500.0000	3,000.0000	363.0000	0.0000	0.0000
40	608-B001	Concrete Sidewalk, With Reinforcement	40.000	SY		110.0000	50.0000	97.0000	0.0000	0.0000
50	609-D002	Combination Concrete Curb and Gutter Type 2	51.000	LF		22.0000	30.0000	31.0000	0.0000	0.0000
60	616-A003	Concrete Median and/or Island Pavement, 10-inch	16.000	SY		66.0000	50.0000	121.0000	0.0000	0.0000
70	626-B001	6" Thermoplastic TrafficStripe, Continuous White	580.000	LF		1.2500	1.7000	0.4300	0.0000	0.0000
80	626-C001	6" Thermoplastic Edge Stripe, Continuous White	3,760.000	LF		1.2500	1.5000	0.3600	0.0000	0.0000
90	626-D001	6" Thermoplastic Traffic Stripe, Skip Yellow	602.000	LF		1.2500	1.5000	0.3100	0.0000	0.0000
100	626-E001	6" Thermoplastic Traffic Stripe, Continuous Yellow	3,958.000	LF		1.2500	1.4000	0.4300	0.0000	0.0000
110	626-G001	Thermoplastic Detail Stripe, White	905.000	LF		1.7500	2.0000	1.5200	0.0000	0.0000
120	626-H001	Thermoplastic Legend, White	192.000	SF		5.5000	7.5000	10.2900	0.0000	0.0000
130	626-H002	Thermoplastic Legend, White	1,678.000	LF		1.7500	2.0000	2.1800	0.0000	0.0000
140	627-K001	Red-Clear Reflective High Performance Raised Markers	32.000	E		5.5000	7.0000	48.4000	0.0000	0.0000
150	627-L001	Two-Way Yellow Reflective High Performance Raised	202.000	E		5.5000	6.7500	18.1500	0.0000	0.0000
160	635-A001	Vehicle Loop Assemblies	1,695.000	LF		10.0000	10.0000	21.7800	0.0000	0.0000
170	636-A002	Shielded Cable	2,033.000	LF		1.2500	1.2500	1.0100	0.0000	0.0000
180	638-A005	Loop Detector Amplifier, Card Rack Mounted, 4 Channel	4.000	E		450.0000	1,025.0000	397.1000	0.0000	0.0000
190	639-A052	Traffic Signal Equipment Pole, Type III, 17' Shaft, 45'	1.000	E		6,706.0000	8,200.0000	8,957.0000	0.0000	0.0000
200		Traffic Signal Equipment Pole, Type III, 17' Shaft, 50'	1.000	E		6,760.0000	8,646.0000	9,568.0000	0.0000	0.0000
210		Traffic Signal Equipment Pole, Type IV, 30' Shaft, 30'	2.000	E		7,370.0000	8,570.0000	9,467.0000	0.0000	0.0000
220	640-A016	Traffic Signal Heads, Type 1 LED	14.000	E		816.0000	875.0000	873.0000	0.0000	0.0000
230	640-A022	Traffic Signal Heads, Type 7 LED	2.000	E		1,300.0000	1,525.0000	1,300.0000	0.0000	0.0000
240	642-A008	Solid State Traffic Actuated Controllers, Type 8A	1.000	E		9,000.0000	9,800.0000	10,718.0000	0.0000	0.0000
250	644-A001	Optical Detector	8.000	E		490.0000	675.0000	522.0000	0.0000	0.0000
260	644-B001	Optical Detector Cable	2,516.000	LF		1.2500	1.2500	1.3200	0.0000	0.0000
270	644-C002	Phase Selector, 4 Channel	1.000	E		3,315.0000	3,375.0000	3,434.0000	0.0000	0.0000
280	647-A005	Pullbox, Type 2	8.000	E		300.0000	475.0000	291.0000	0.0000	0.0000
290		Electric Cable, Underground in Conduit, IMSA 26-3, AWG	100.000	LF		6.0000	10.0000	1.2100	0.0000	0.0000
300		Electric Cable, Underground in Conduit, IMSA 26-3, AWG	600.000	LF		3.0000	5.0000	1.2100	0.0000	0.0000
310	666-B015	Electric Cable, Underground in Conduit, IMSA 20-1, AWG	719.000	LF		2.0000	2.4500	1.0900	0.0000	0.0000
320	666-B016	Electric Cable, Underground in Conduit, IMSA 20-1, AWG	2,244.000	LF		2.5000	2.8000	1.5500	0.0000	0.0000
330	666-C007	Electric Cable, Aerial Supported, IMSA 20-1, AWG 14, 7	295.000	LF		3.0000	2.8000	1.5500	0.0000	0.0000

Jasper

Installation of a Traffic Signal at the intersection of Mississippi Highway 528 and Mississippi Highway 18, known as Federal Aid Project No. STP-0022-01(057) / 103032, in the County of Jasper, State of Mississippi

REF#	SM ITEM	ITEM DESCRIPTION	ITEM QUANTITY	UNITS	MISSISSIPPI DEPARTMENT OF TRANSPORTATION	LEWIS ELECTRIC INC	B & B ELECTRICAL & UTILITY CONTRACTORS	TOOMER ELECTRICAL COMPANY INC.		
					155,017.00	143,849.00	159,235.20	205,204.86	0.00	0.00
						1	2	3	4	5
340	668-A018	Traffic Signal Conduit, Underground, Type 4, 2"	367.000	LF		7.0000	4.0000	5.3100	0.0000	0.0000
350	668-A020	Traffic Signal Conduit, Underground, Type 4, 3"	10.000	LF		10.0000	20.0000	6.3000	0.0000	0.0000
360		Traffic Signal Conduit, Underground Drilled or Jacked,	379.000	LF		11.0000	12.0000	20.1500	0.0000	0.0000
370	618-A001	Maintenance of Traffic	0.000	LS		3,000.0000	5,000.0000	22,599.0000	0.0000	0.0000
380	620-A001	Mobilization	0.000	LS		8,000.5000	5,000.0000	23,000.0000	0.0000	0.0000