





Greene Work necessary to add an additional lane to Mississippi Highway 57, between Mississippi Highway 63 and Turkey Creek, known as Federal Aid Project No. NH-0002-02(061)PH3 / 102917, in the County of Greene, State of Mississippi.				MISSISSIPPI DEPARTMENT OF TRANSPORTATION	TANNER CONSTRUCTION COMPANY INC.	EUTAW CONSTRUCTION CO INC	W. G. YATES & SON CONSTR. CO.		
				11,402,080.09	10,774,310.73	12,940,371.58	15,519,123.23	0.00	0.00
REF#	SM	ITEM DESCRIPTION	ITEM QUANTITY UNITS		1	2	3	4	5
670		Standard Roadside Construction Signs (0.9 square meter	65.000 m2		200.0000	215.0000	115.0000	0.0000	0.0000
680		Barricades (Type III) (Double Faced)	7.000 m		100.0000	240.0000	65.0000	0.0000	0.0000
690		Barricades (Type III) (Single Faced) (Permanent)	212.000 m		75.0000	115.0000	105.0000	0.0000	0.0000
700		Warning Lights (Type "B")	12.000 E		245.0000	850.0000	505.0000	0.0000	0.0000
710		Field Laboratory	1.000 E		6,000.0000	10,000.0000	43,000.0000	0.0000	0.0000
720		Portland Cement Grout for Plugging Abandoned Wells	150.000 kg		50.0000	3.0000	12.0000	0.0000	0.0000
730		Loading Tests	18.000 E		5,000.0000	5,000.0000	5,000.0000	0.0000	0.0000
740		350-mm x 350-mm Prestressed Concrete Piling	2,467.000 m		90.0000	75.0000	125.0000	0.0000	0.0000
750		400-mm x 400-mm Prestressed Concrete Piling	3,267.000 m		100.0000	80.0000	109.0000	0.0000	0.0000
760		PDA Test Piles	18.000 E		3,500.0000	5,000.0000	9,500.0000	0.0000	0.0000
770		Bridge Concrete (Class AA)	2,810.000 m3		400.0000	510.0000	660.0000	0.0000	0.0000
780		Box Bridge Concrete (Class B)	1,050.000 m3		365.0000	360.0000	480.0000	0.0000	0.0000
790		9-m Prestressed Concrete Beams, Type I+50	88.000 m		150.0000	135.0000	175.0000	0.0000	0.0000
800		12-m Prestressed Concrete Beams, Type I+50	2,805.000 m		150.0000	140.0000	160.0000	0.0000	0.0000
810		18-m Prestressed Concrete Beams, Type III	179.000 m		225.0000	185.0000	215.0000	0.0000	0.0000
820		24-m Prestressed Concrete Beams, Type III	287.000 m		225.0000	200.0000	200.0000	0.0000	0.0000
830		Reinforcement	315,373.000 kg		1.5000	1.5000	2.0000	0.0000	0.0000
840		Concrete Railing	1,332.000 m		100.0000	130.0000	125.0000	0.0000	0.0000
850		Loose Riprap, (Size 136 kg)	2,619.000 mt		40.0000	49.5000	52.3900	0.0000	0.0000
860		Geotextile Fabric under Riprap	1,725.000 m2		1.2300	2.0000	1.8500	0.0000	0.0000
870		Sediment Control Stone	40.000 mt		40.0000	48.0000	45.1500	0.0000	0.0000
880		Maintenance of Traffic	0.000 LS		3,500.0000	25,000.0000	145,000.0000	0.0000	0.0000
890		Mobilization	0.000 LS		651,000.0000	892,000.0000	515,000.0000	0.0000	0.0000
900		Roadway Construction Stakes	0.000 LS		215,000.0000	150,000.0000	395,000.0000	0.0000	0.0000