

Scott Replacing one bridge on US Highway 80 at the railroad in Forest, known as Federal Aid Project No. BR-5525-00(005) / 100602, in the County of Scott, State of Mississippi.				MISSISSIPPI DEPARTMENT OF TRANSPORTATION	TANNER CONSTRUCTION COMPANY INC.	T. L. WALLACE .CONSTRUCTION CO. INC .	KEY CONSTRUCTORS INC.	JOE MCGEE CONSTRUCTION COMPANY INC.	
				3,301,528.19	3,345,593.03	3,895,076.81	3,911,439.52	4,166,378.81	0.00
REF#	SM ITEM	ITEM DESCRIPTION	ITEM QUANTITY	UNITS	1	2	3	4	5
330	234-A001	Temporary Silt Fence	4,125.000	LF	2.5000	3.5000	3.4500	3.2500	0.0000
340	235-A001	Temporary Erosion Checks	1,280.000	E	5.0000	10.0000	10.0000	5.0000	0.0000
350	236-A004	Silt Basin, Type D	2.000	E	1,650.0000	2,500.0000	2,120.0000	1,000.0000	0.0000
360	239-A001	Temporary Slope Drains	278.000	LF	5.0000	7.0000	3.0000	10.0000	0.0000
370	304-A023	Granular Material, LVM, Class 5, Group C	2,955.000	CY	22.5000	16.5000	16.0000	20.6500	0.0000
380	304-G001	3/4" and Down Crushed Stone Base, AEA	3,962.000	CY	48.0000	70.0000	65.0000	52.9200	0.0000
390	305-B001	Size I Stabilizer Aggregate, Coarse	1,000.000	CY	10.0000	45.0000	28.0000	42.3500	0.0000
400	403-A006	Hot Mix Asphalt, MT, 12.5-mm mixture	3,355.000	T	50.0000	54.0000	54.0000	55.5000	0.0000
410	403-A007	Hot Mix Asphalt, MT, 19-mm mixture	3,051.000	T	50.0000	52.0000	54.0000	55.5000	0.0000
420	406-A001	Cold Milling of Bituminous Pavement, All Depths	1,200.000	SY	4.0000	5.0000	4.0000	4.0000	0.0000
430	501-E001	Expansion Joints, Without Dowels	150.000	LF	6.0000	10.0000	7.0000	4.0000	0.0000
440	501-K001	Transverse Grooving	2,423.000	SY	3.0000	3.5000	3.0000	2.9000	0.0000
450	502-A001	Reinforced Cement Concrete Bridge End Pavement	430.000	SY	62.0000	85.0000	95.0000	85.0000	0.0000
460	503-C002	Saw Cut, 3-inch	135.000	LF	5.0000	5.0000	4.0000	3.3000	0.0000
470	601-A003	Class "B" Structural Concrete	37.000	CY	450.0000	500.0000	405.0000	560.0000	0.0000
480	601-B001	Class "B" Structural Concrete, Minor Structures	2.000	CY	800.0000	1,200.0000	1,515.0000	1,000.0000	0.0000
490	602-A001	Reinforcing Steel	7,303.000	LBS	0.7200	0.9000	1.0000	0.7000	0.0000
500	603-ALT001	18" Type A Alternate Pipe	1,404.000	LF	18.0000	20.0000	31.8000	16.7500	0.0000
510	603-CA002	18" Reinforced Concrete Pipe, Class III	84.000	LF	28.0000	35.0000	40.3000	30.3000	0.0000
520	603-CA003	24" Reinforced Concrete Pipe, Class III	88.000	LF	40.0000	50.0000	53.0000	42.8000	0.0000
530	603-CB002	24" Reinforced Concrete End Section	2.000	E	660.0000	1,500.0000	700.0000	807.0000	0.0000
540	606-B001	Guard Rail, Class A, Type 1	375.000	LF	16.5000	16.5000	16.5000	16.5000	0.0000
550	606-D012	Guard Rail, Bridge End Section, Type I	4.000	E	1,850.0000	1,850.0000	1,850.0000	1,850.0000	0.0000
560	606-E001	Guard Rail, Terminal End Section	4.000	E	2,000.0000	2,000.0000	2,000.0000	2,000.0000	0.0000
570	607-A001	31.5" Type"A" Woven Wire Fence, w/ Barbed Wire as Shown	1,028.000	LF	4.0000	4.2500	4.0000	3.0000	0.0000
580	607-P1020	Line Post, 7' x 4" Timber	54.000	E	60.0000	65.0000	60.0000	50.0000	0.0000
590	607-P1021	Line Post, 9' x 4" Timber	11.000	E	70.0000	75.0000	70.0000	60.0000	0.0000
600	607-P1002	Line Post, 10' x 4" Timber	7.000	E	80.0000	85.0000	80.0000	60.0000	0.0000
610	607-P2001	Brace Post, 8' x 6" Timber	11.000	E	175.0000	185.0000	175.0000	70.0000	0.0000
620	607-P2002	Brace Post, 10' x 6" Timber	2.000	E	190.0000	205.0000	195.0000	75.0000	0.0000
630	607-P2003	Brace Post, 12' x 6" Timber	1.000	E	200.0000	210.0000	200.0000	75.0000	0.0000
640	607-Z001	Concrete Anchors	20.000	E	30.0000	35.0000	30.0000	20.0000	0.0000
650	609-D002	Combination Concrete Curb and Gutter Type 2	490.000	LF	15.0000	14.3500	14.3500	18.0000	0.0000

