

Washington				MISSISSIPPI	AUSTIN BRIDGE &	HILL BROS.CONSTR.				
Work necessary to construct the Arkansas approach to the US Highway 82/Mississippi River Bridge, known as Federal Aid Project Nos. ACBR-9205-00(005)/100332 in Washington County, Mississippi & BRN-0009(26) in Chicot County, Arkansas.				DEPARTMENT OF	ROAD, LP	AND JENSEN				
				TRANSPORTATION		CONSTR.CO.				
				61,670,946.58	65,989,486.90	68,444,313.80	0.00	0.00	0.00	
REF#	SM	ITEM	ITEM DESCRIPTION	ITEM QUANTITY	UNITS	1	2	3	4	5
350			Temporary Erosion Checks	100.000	bale	30.0000	9.0000	0.0000	0.0000	0.0000
360	236-A004		Silt Basin (Type D)	1.000	E	3,100.0000	2,500.0000	0.0000	0.0000	0.0000
370	239-A001		Temporary Slope Drains	100.000	m	36.0000	35.0000	0.0000	0.0000	0.0000
380			Interlocking Flexible Block Erosion Control System	2,000.000	m2	65.0000	125.0000	0.0000	0.0000	0.0000
390	304-B025		Granular Material (Class 5, Group E)	5,170.000	mt	61.0000	25.0000	0.0000	0.0000	0.0000
400	304-B043		Granular Material (Class 9, Group C)	12,400.000	mt	55.0000	22.0000	0.0000	0.0000	0.0000
410	907-304-G00		20-mm and Down Crushed Stone (AEA)	1,600.000	m3	100.0000	75.0000	0.0000	0.0000	0.0000
420	907-306-A00		Asphalt Drainage Course	12,800.000	m2	20.0000	19.0000	0.0000	0.0000	0.0000
430	907-307-B00		150-mm Soil-Lime-Water Mixing (Class B)	12,300.000	m2	3.2000	2.8000	0.0000	0.0000	0.0000
440	907-307-D00		Lime	177.000	mt	172.0000	155.0000	0.0000	0.0000	0.0000
450	907-403-A01		Hot Mix Asphalt, HT, 12.5-mm mixture	2,400.000	mt	88.0000	85.0000	0.0000	0.0000	0.0000
460	907-403-A01		Hot Mix Asphalt, HT, 19-mm mixture	2,200.000	mt	86.0000	85.0000	0.0000	0.0000	0.0000
470	907-403-A01		Hot Mix Asphalt, HT, 25-mm mixture	6,000.000	mt	86.0000	84.0000	0.0000	0.0000	0.0000
480	907-403-C00		Hot Mix Asphalt, HT, 19-mm mixture, Trench Widening	263.000	mt	86.0000	90.0000	0.0000	0.0000	0.0000
490	907-403-D00		Hot Mix Asphalt, HT, 12.5-mm mixture, Polymer Modified	1,500.000	mt	92.0000	90.0000	0.0000	0.0000	0.0000
500	907-403-D00		Hot Mix Asphalt, HT, 19-mm mixture, Polymer Modified	1,120.000	mt	91.0000	90.0000	0.0000	0.0000	0.0000
510	907-403-E00		Hot Mix Asphalt, HT, 19-mm mixture, Polymer Modified,	1,370.000	mt	90.0000	90.0000	0.0000	0.0000	0.0000
520	406-A001		Cold Milling of Bituminous Pavement (All Depths)	7,310.000	m2	4.7000	4.7500	0.0000	0.0000	0.0000
530	408-A003		Asphalt for Prime Coat, Cut-Back MC-70 or Emulsified	10,500.000	l	2.1000	2.1000	0.0000	0.0000	0.0000
540	501-E001		Expansion Joints (Without Dowels)	28.000	m	70.0000	60.0000	0.0000	0.0000	0.0000
550	907-501-K00		Transverse Grooving	34,079.000	m2	2.8000	6.0000	0.0000	0.0000	0.0000
560	502-A001		Reinforced Cement Concrete Bridge End Pavement	165.000	m2	107.0000	125.0000	0.0000	0.0000	0.0000
570	907-503-C00		Saw Cut (Full Depth)	141.000	m	10.5000	35.0000	0.0000	0.0000	0.0000
580	601-B001		Class "B" Structural Concrete, Minor Structures	6.000	m3	1,200.0000	1,500.0000	0.0000	0.0000	0.0000
590	602-A001		Reinforcing Steel	134.000	kg	1.3000	5.0000	0.0000	0.0000	0.0000
600	907-603-ALT		450-mm Type A Alternate Pipe	32.000	m	293.0000	75.0000	0.0000	0.0000	0.0000
610	907-603-ALT		600-mm Type A Alternate Pipe	30.000	m	379.0000	100.0000	0.0000	0.0000	0.0000
620	603-C-A005		900-mm Reinforced Concrete Pipe, Class III	42.000	m	463.0000	750.0000	0.0000	0.0000	0.0000
630	603-C-B004		900-mm Reinforced Concrete End Section	3.000	E	2,100.0000	1,300.0000	0.0000	0.0000	0.0000
640	603-C-E001		560-mm x 345-mm Concrete Arch Pipe, Class A III	22.000	m	705.0000	175.0000	0.0000	0.0000	0.0000
650	603-C-E007		1650-mm x 1015-mm Concrete Arch Pipe, Class A III	21.000	m	806.0000	600.0000	0.0000	0.0000	0.0000
660	603-C-F001		560-mm x 345-mm Concrete Arch Pipe End Section	2.000	E	3,700.0000	800.0000	0.0000	0.0000	0.0000
670	603-C-F007		1650-mm x 1015-mm Concrete Arch Pipe End Section	2.000	E	4,500.0000	2,500.0000	0.0000	0.0000	0.0000

Washington				MISSISSIPPI	AUSTIN BRIDGE &	HILL BROS.CONSTR.				
Work necessary to construct the Arkansas approach to the US Highway 82/Mississippi River Bridge, known as Federal Aid Project Nos. ACBR-9205-00(005)/100332 in Washington County, Mississippi & BRN-0009(26) in Chicot County, Arkansas.				DEPARTMENT OF	ROAD, LP	AND JENSEN				
				TRANSPORTATION		CONSTR.CO.				
				61,670,946.58	65,989,486.90	68,444,313.80	0.00	0.00	0.00	
REF#	SM	ITEM	ITEM DESCRIPTION	ITEM QUANTITY	UNITS	1	2	3	4	5
680	907-605-FF0		Edge Drain, Complete-in-Place	1,010.000	m	54.0000	45.0000	0.0000	0.0000	0.0000
690	907-605-GG0		Edge Drain Outlets/Vents, Complete-in-Place	114.000	m	82.0000	33.0000	0.0000	0.0000	0.0000
700	907-605-HH0		Edge Drain & Edge Drain Outlet/Vent Inspection	562.000	m	67.0000	13.0000	0.0000	0.0000	0.0000
710	605-X002		Filter Material for Filter Beds, Type A	100.000	mt	35.0000	50.0000	0.0000	0.0000	0.0000
720	605-X005		Filter Material for Filter Beds, Type C	4,650.000	m3	76.0000	55.0000	0.0000	0.0000	0.0000
730	606-B001		Guard Rail (Class A, Type 1)	73.000	m	61.0000	60.0000	0.0000	0.0000	0.0000
740	606-C003		Guard Rail, Cable Anchor, Type 1	1.000	E	800.0000	775.0000	0.0000	0.0000	0.0000
750	606-D012		Guard Rail, Bridge End Section, Type I	2.000	E	2,000.0000	2,100.0000	0.0000	0.0000	0.0000
760	907-606-E00		Guard Rail, Terminal End Section	1.000	E	2,500.0000	2,650.0000	0.0000	0.0000	0.0000
770	907-610-A00		Drainage Wicks	19,100.000	m	2.1000	2.5000	0.0000	0.0000	0.0000
780	615-A009		Concrete Type I Cast-in-Place Median Barrier (1050 mm	18.000	m	240.0000	150.0000	0.0000	0.0000	0.0000
790	907-619-A10		Temporary Traffic Stripe (Continuous White)	4.000	km	1,100.0000	1,050.0000	0.0000	0.0000	0.0000
800	907-619-A20		Temporary Traffic Stripe (Continuous Yellow)	4.000	km	1,100.0000	1,050.0000	0.0000	0.0000	0.0000
810	907-619-A50		Temporary Traffic Stripe (Detail)	101.000	m	5.4000	5.2500	0.0000	0.0000	0.0000
820	907-619-A60		Temporary Traffic Stripe (Legend)	53.000	m	10.8000	10.5000	0.0000	0.0000	0.0000
830	907-619-A60		Temporary Traffic Stripe (Legend)	4.000	m2	54.0000	52.0000	0.0000	0.0000	0.0000
840	907-619-C60		Red-Clear Reflective High Performance Raised Marker	6.000	E	22.0000	21.0000	0.0000	0.0000	0.0000
850	907-619-C70		Two-Way Yellow Reflective High Performance Raised	99.000	E	22.0000	21.0000	0.0000	0.0000	0.0000
860	619-D1001		Standard Roadside Construction Signs (less than 0.9	4.000	m2	427.0000	250.0000	0.0000	0.0000	0.0000
870	619-D2001		Standard Roadside Construction Signs (0.9 square meter	37.000	m2	435.0000	250.0000	0.0000	0.0000	0.0000
880	619-D4001		Directional Signs	5.000	m2	469.0000	250.0000	0.0000	0.0000	0.0000
890	619-F1001		Concrete Median Barrier (Precast)	705.000	m	227.0000	110.0000	0.0000	0.0000	0.0000
900	619-F2001		Remove and Reset Concrete Median Barrier (Precast)	555.000	m	17.0000	15.0000	0.0000	0.0000	0.0000
910	619-G4005		Barricades (Type III) (Double Faced)	62.000	m	177.0000	150.0000	0.0000	0.0000	0.0000
920	619-G5001		Free Standing Plastic Drums	33.000	E	284.0000	250.0000	0.0000	0.0000	0.0000
930	619-G7001		Warning Lights (Type "B")	9.000	E	4,200.0000	4,000.0000	0.0000	0.0000	0.0000
940	621-A001		Field Laboratory	1.000	E	15,000.0000	16,000.0000	0.0000	0.0000	0.0000
950	907-622-A00		Engineer's Field Office Building (Type 3)	1.000	E	100,000.0000	23,000.0000	0.0000	0.0000	0.0000
960			150-mm Thermoplastic Traffic Stripe (Continuous White)	1.000	km	2,200.0000	2,100.0000	0.0000	0.0000	0.0000
970			150-mm Thermoplastic Traffic Stripe (Continuous Yellow)	1.000	km	2,200.0000	2,100.0000	0.0000	0.0000	0.0000
980	907-627-L00		Two-Way Yellow Reflective High Performance Raised	21.000	E	22.0000	21.0000	0.0000	0.0000	0.0000
990	629-A004		Vehicular Impact Attenuator (112 kph)	1.000	E	24,700.0000	25,000.0000	0.0000	0.0000	0.0000
1000	630-A001		Standard Roadside Signs (Sheet Aluminum, 2.03-mm	8.000	m2	143.0000	150.0000	0.0000	0.0000	0.0000

Washington				MISSISSIPPI	AUSTIN BRIDGE &	HILL BROS.CONSTR.			
Work necessary to construct the Arkansas approach to the US Highway 82/Mississippi River Bridge, known as Federal Aid Project Nos. ACBR-9205-00(005)/100332 in Washington County, Mississippi & BRN-0009(26) in Chicot County, Arkansas.				DEPARTMENT OF	ROAD, LP	AND JENSEN			
				TRANSPORTATION		CONSTR.CO.			
				61,670,946.58	65,989,486.90	68,444,313.80	0.00	0.00	0.00
REF#	SM ITEM	ITEM DESCRIPTION	ITEM QUANTITY	UNITS	1	2	3	4	5
1340	815-A007	Loose Riprap, (Size 136 kg)	760.000	mt	60.0000	50.0000	0.0000	0.0000	0.0000
1350	815-D001	Concrete Slope Paving	56.000	m3	408.0000	600.0000	0.0000	0.0000	0.0000
1360	907-815-F00	Sediment Control Stone	120.000	mt	52.0000	50.0000	0.0000	0.0000	0.0000
1370		Bridge Name Plate	2.000	E	1,396.0000	1,000.0000	0.0000	0.0000	0.0000
1380	907-308-A00	Portland Cement	153.000	mt	221.0000	195.0000	0.0000	0.0000	0.0000
1390	907-308-B00	Soil-Cement-Water Mixing, (Optional Mixers) (Base)	12,300.000	m2	2.8000	2.5000	0.0000	0.0000	0.0000
1400	907-311-A00	Processing Lime and Fly Ash Treated Course, 150 mm	12,300.000	m2	0.0000	0.0000	0.0000	0.0000	0.0000
1410	907-311-B00	Lime	133.000	mt	0.0000	0.0000	0.0000	0.0000	0.0000
1420		Fly Ash, Class C or F	528.000	mt	0.0000	0.0000	0.0000	0.0000	0.0000
1430	618-A001	Maintenance of Traffic	0.000	LS	166,000.0000	225,000.0000	0.0000	0.0000	0.0000
1440	620-A001	Mobilization	0.000	LS	6,500,000.0000	6,400,000.0000	0.0000	0.0000	0.0000
1450	907-699-A00	Roadway Construction Stakes	0.000	LS	500,000.0000	750,000.0000	0.0000	0.0000	0.0000