

Hinds & Madison				MISSISSIPPI	SUPERIOR ASPHALT					
Overlying approx. 8.4 miles of I-55 from Pearl St. to I-220, including frontage rds., connectors, streets, interchange loops, & ramps, known as Federal Aid Project No. IM-0055-02(186) / 104166, in the Counties of Hinds & Madison, State of Mississippi.				DEPARTMENT OF	INC. & APAC-MS					
				TRANSPORTATION	INC. AJV					
				29,900,989.03	31,326,888.27	0.00	0.00	0.00	0.00	
REF#	SM	ITEM	ITEM DESCRIPTION	ITEM QUANTITY	UNITS	1	2	3	4	5
10	201	A001	Clearing and Grubbing	0.000	LS	40,000.0000	0.0000	0.0000	0.0000	0.0000
20	202	B005	Removal of Asphalt Pavement, All Depths	2,000.000	SY	10.0000	0.0000	0.0000	0.0000	0.0000
21	202	B112	Removal of Concrete Pavement, Failed Areas	135.000	SY	228.7900	0.0000	0.0000	0.0000	0.0000
30	202	B076	Removal of Traffic Stripe	4,105.000	LF	2.0000	0.0000	0.0000	0.0000	0.0000
40	202	B087	Removal of Guard Rail, Including Rails, Posts and	2,162.000	LF	4.0000	0.0000	0.0000	0.0000	0.0000
50	202	B038	Removal of Curb, All Types	400.000	LF	10.0000	0.0000	0.0000	0.0000	0.0000
60	203	E045	Borrow Excavation, LVM, Class B15	13,000.000	CY	14.0000	0.0000	0.0000	0.0000	0.0000
70	203	G002	Excess Excavation, LVM	600.000	CY	11.0000	0.0000	0.0000	0.0000	0.0000
80	212	B001	Standard Ground Preparation	26,027.000	SY	0.0800	0.0000	0.0000	0.0000	0.0000
90	907-213	A00	Agricultural Limestone	10.000	T	85.0000	0.0000	0.0000	0.0000	0.0000
100	213	B001	Combination Fertilizer, 13-13-13	2.000	T	660.0000	0.0000	0.0000	0.0000	0.0000
120	214	A002	Seeding, Bermudagrass	70.000	LBS	9.7500	0.0000	0.0000	0.0000	0.0000
130	214	A003	Seeding, Tall Fescue	35.000	LBS	9.0000	0.0000	0.0000	0.0000	0.0000
140	214	A004	Seeding, Crimson Clover	35.000	LBS	9.0000	0.0000	0.0000	0.0000	0.0000
150	215	A001	Vegetative Materials for Mulch	8.000	T	350.0000	0.0000	0.0000	0.0000	0.0000
160	216	A001	Solid Sodding	2,000.000	SY	9.0000	0.0000	0.0000	0.0000	0.0000
170	219	A001	Watering	40.000	M/G	20.0000	0.0000	0.0000	0.0000	0.0000
180	220	A001	Insect Pest Control	4.000	A	30.0000	0.0000	0.0000	0.0000	0.0000
190	221	A001	Portland Cement Concrete Paved Ditch	17.000	CY	800.0000	0.0000	0.0000	0.0000	0.0000
200	234	A001	Temporary Silt Fence	600.000	LF	5.0000	0.0000	0.0000	0.0000	0.0000
210	235	A001	Temporary Erosion Checks	50.000	E	20.0000	0.0000	0.0000	0.0000	0.0000
220	304	A023	Granular Material, LVM, Class 5, Group C	5,000.000	CY	32.0000	0.0000	0.0000	0.0000	0.0000
230			Hot Mix Asphalt, HT, 9.5-mm mixture	1,488.000	T	54.0000	0.0000	0.0000	0.0000	0.0000
240			Hot Mix Asphalt, HT, 19-mm mixture	14,738.000	T	51.5000	0.0000	0.0000	0.0000	0.0000
250			Hot Mix Asphalt, HT, 12.5-mm mixture, Leveling	6,968.000	T	59.0000	0.0000	0.0000	0.0000	0.0000
260			Hot Mix Asphalt, HT, 9.5-mm mixture, Polymer Modified,	13,446.000	TON	62.5000	0.0000	0.0000	0.0000	0.0000
270			Hot Mix Asphalt, HT, 12.5-mm mixture, Polymer Modified	58,575.000	T	58.5000	0.0000	0.0000	0.0000	0.0000
280			Hot Mix Asphalt, HT, 12.5-mm mixture, Polymer Modified,	97,390.000	TON	57.0000	0.0000	0.0000	0.0000	0.0000
290			Hot Mix Asphalt, HT, 19-mm mixture, Polymer Modified	93,229.000	T	56.0000	0.0000	0.0000	0.0000	0.0000
300	406	A003	Cold Milling of Bituminous Pavement, All Depths	80,416.000	T	18.5000	0.0000	0.0000	0.0000	0.0000
310	406	B001	Cold Milling of Concrete Pavement, All Depths	43,929.000	SY	22.0000	0.0000	0.0000	0.0000	0.0000
320	413	C001	Cleaning and Sealing Cracks	5,280.000	LF	2.1300	0.0000	0.0000	0.0000	0.0000
330			Cleaning and Sealing Joints in PCC Pavement	21,120.000	LF	2.1300	0.0000	0.0000	0.0000	0.0000

