

Bolivar				MISSISSIPPI	TALBOT BROS.	T. L. WALLACE	ENDEVCO, INC.	HARPER	DOZER, INC.
Work necessary to replace the bridge on Mississippi Highway 444 west of the junction of US Highway 61, known as Federal Aid Project No. BR-0610-00(013) / 102508, in the County of Bolivar, State of Mississippi.				DEPARTMENT OF	CONTR./TALBOT	CONSTRUCTION		CONSTRUCTION,	
				TRANSPORTATION	BROS. GRAD. A	COMPANY, INC.		INC.	
				2,010,452.90	1,855,735.00	1,995,738.17	2,138,117.46	2,257,215.15	2,348,500.00
REF#	SM ITEM	ITEM DESCRIPTION	ITEM QUANTITY	UNITS	1	2	3	4	5
650	630-G002	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	4.000	E	75.0000	75.0000	80.0000	75.0000	75.0000
660	803-A001	Test Pile	2.000	E	7,400.0000	2,410.0000	7,000.0000	5,500.0000	6,700.0000
670	803-B001	Conventional Static Loading Test	2.000	E	5,000.0000	5,000.0000	5,000.0000	5,000.0000	5,000.0000
680	803-C002	14" x 14" Prestressed Concrete Piling	2,090.000	LF	35.0000	9.5500	35.0000	39.0000	33.0000
690	803-C003	16" x 16" Prestressed Concrete Piling	1,665.000	LF	45.0000	122.0000	45.0000	45.0000	42.0000
700	803-J001	Pile Restrike	2.000	E	800.0000	1,030.0000	750.0000	700.0000	750.0000
710		Bridge Concrete, Class AA	348.000	CY	599.0000	460.0000	600.0000	550.0000	600.0000
720		60' Prestressed Concrete Beam, Type II+2	717.000	LF	105.0000	95.0000	105.0000	95.0000	100.0000
730		80' Prestressed Concrete Beam, Type III	740.000	LF	133.0000	75.0000	115.0000	110.0000	113.0000
740	805-A001	Reinforcement	48,367.000	LBS	0.7600	0.7400	0.7400	0.9000	0.8200
750	813-A001	Concrete Railing	400.000	LF	31.0000	47.8000	62.5000	52.0000	50.0000
760	815-A009	Loose Riprap, Size 300	2,906.000	T	45.0000	4.2000	48.0000	47.0000	45.0000
770	815-E001	Geotextile under Riprap	3,236.000	SY	2.2000	2.1000	2.9000	3.5000	3.0000
780	618-A001	Maintenance of Traffic	0.000	LS	15,000.0000	6,900.0000	15,000.0000	32,000.0000	35,000.0000
790	620-A001	Mobilization	0.000	LS	75,000.0000	220,000.0000	175,000.0000	220,000.0000	130,617.1500
800	699-A001	Roadway Construction Stakes	0.000	LS	38,000.0000	75,000.0000	70,000.0000	116,000.0000	50,000.0000