

WASHINGTON (76)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	APAC-MISSISSIPPI, INC.	J. J. FERGUSON SAND & GRAVEL, INC.	
Construction necessary to widen and overlay SR 12 from SR 1 to Leroy Percy State Park, known as State Project No. MP-3012-76(010)/303221301, in the County of Washington, State of Mississippi.					\$2,019,481.50	\$2,304,835.30	\$2,350,959.40	
Ref#	SM Item	Item Description	Item Qty	Units		1	2	
0010	202-B005	Removal of Asphalt Pavement, All Depths	350.000	SY		10.00	9.30	
0020	202-B076	Removal of Traffic Stripe	100.000	LF		50.00	11.00	
0030	203-EX018	Borrow Excavation, AH, LVM, Class B9	3,000.000	CY		12.35	14.00	
0040	203-G001	Excess Excavation, FM	300.000	CY		13.30	9.40	
0050	234-A001	Temporary Silt Fence	500.000	LF		4.10	3.00	
0060	304-B025	Granular Material, Class 5, Group E	7,200.000	TON		28.90	23.50	
0070	406-A003	Cold Milling of Bituminous Pavement, All Depths	1,000.000	TON		25.00	13.50	
0080	423-A001	Rumble Strips, Ground In	14.000	MI		725.00	550.00	
0090	603-ALT001	18" Type A Alternate Pipe	40.000	LF		34.30	32.10	
0100	606-B001	Guard Rail, Class A, Type 1	950.000	LF		17.50	27.40	
0110	606-D014	Guard Rail, Bridge End Section, Type I, Metal Post	8.000	EA		1,050.00	1,650.00	
0120	606-E001	Guard Rail, Terminal End Section	8.000	EA		1,400.00	2,200.00	
0130	618-A001	Maintenance of Traffic	1.000	LS		35,000.00	51,300.00	
0140	619-A1002	Temporary Traffic Stripe, Continuous White	28.000	MI		800.00	900.00	
0150	619-A2002	Temporary Traffic Stripe, Continuous Yellow	14.000	MI		10.00	11.00	
0160	619-A4006	Temporary Traffic Stripe, Skip Yellow	14.000	MI		2,200.00	2,500.00	
0170	619-A5001	Temporary Traffic Stripe, Detail	2,400.000	LF		0.10	0.12	
0180	619-A6001	Temporary Traffic Stripe, Legend	600.000	LF		1.00	1.15	
0190	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	700.000	EA		7.00	7.75	
0200	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	186.000	SF		17.00	12.20	
0210	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	316.000	SF		14.50	12.20	
0220	619-G4005	Barricades, Type III, Double Faced	30.000	LF		31.45	24.00	
0230	619-G7001	Warning Lights, Type "B"	2.000	EA		695.50	337.00	
0240	620-A001	Mobilization	1.000	LS		35,000.00	223,000.00	
0250	626-C002	6" Thermoplastic Edge Stripe, Continuous White	14.000	MI		2,400.00	2,650.00	
0260	626-D002	6" Thermoplastic Traffic Stripe, Skip Yellow	7.000	MI		1,400.00	1,550.00	

WASHINGTON (76)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	APAC-MISSISSIPPI, INC.	J. J. FERGUSON SAND & GRAVEL, INC.	
Construction necessary to widen and overlay SR 12 from SR 1 to Leroy Percy State Park, known as State Project No. MP-3012-76(010)/303221301, in the County of Washington, State of Mississippi.					\$2,019,481.50	\$2,304,835.30	\$2,350,959.40	
Ref#	SM Item	Item Description	Item Qnty	Units		1	2	
0265	626-E002	6" Thermoplastic Traffic Stripe, Continuous Yellow	1.000	MI		2,000.00	2,200.00	
0270	626-G001	Thermoplastic Detail Stripe, White	1,500.000	LF		1.00	1.10	
0280	626-G002	Thermoplastic Detail Stripe, Yellow	900.000	LF		1.00	1.10	
0290	626-H002	Thermoplastic Legend, White	600.000	LF		4.00	4.50	
0300	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	700.000	EA		7.00	7.70	
0310	628-J002	6" High Performance Cold Plastic Traffic Stripe, Continuous	500.000	LF		5.00	5.50	
0320	628-L002	6" High Performance Cold Plastic Traffic Stripe, Skip Yellow	250.000	LF		5.00	5.50	
0330	630-F001	Delineators, Guard Rail, White	48.000	EA		12.60	20.00	
0340	630-G002	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	8.000	EA		52.50	85.00	
0350	699-A001	Roadway Construction Stakes	1.000	LS		2,000.00	18,300.00	
0360	907-213-A001	Agricultural Limestone	5.000	TON		100.00	110.00	
0370	907-225-A001	Grassing	2.000	ACRE		3,000.00	3,300.00	
0380	907-304-F003	3/4" and Down Crushed Stone Base	500.000	TON		40.20	43.50	
0390	907-403-A015	Hot Mix Asphalt, ST, 9.5-mm mixture	10,500.000	TON		80.89	73.50	
0400	907-403-B009	Hot Mix Asphalt, ST, 9.5-mm mixture, Leveling	11,200.000	TON		79.95	73.00	