

HARRISON (24)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Superior Asphalt, Inc.	Hemphill Construction Company, Inc.	TCB Construction Company, Inc.
Grading, Draining, Paving & Replacing traffic signals on US 90 between Rodenburg Ave. and Biloxi Bay, known as Federal Aid Project Nos. ER-NH-0003-01(108) / 104569306 & ER-NH-0003-01(108) / 104569308, in the County of Harrison, State of Mississippi.					\$15,774,070.95	\$19,115,389.25	IRREGULAR	IRREGULAR
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS		50,000.00		
0020	202-A001	Removal of Obstructions	1.000	LS		100,000.00		
0030	202-B024	Removal of Concrete Median & Island Pavement, All Depths	3,845.000	SY		16.50		
0040	202-B035	Removal of Concrete Sidewalk	12,373.000	SY		20.00		
0050	202-B038	Removal of Curb, All Types	78,324.000	LF		20.00		
0060	202-B047	Removal of Guard Rail Bridge End Section, Type H	1.000	EA		250.00		
0070	202-B051	Removal of Guard Rail, Double Faced Rail Including Hardware,	75.000	LF		6.00		
0080	202-B057	Removal of Inlets, All Sizes	2.000	EA		1,000.00		
0090	202-B078	Removal of Pavement, All Types and Depths	2,840.000	SY		22.00		
0100	202-B094	Removal of Curb &/or Curb and Gutter, All Types	93.000	LF		35.00		
0110	202-B102	Removal of Guard Rail	168.000	LF		5.00		
0120	202-B106	Removal of Pipe, All Sizes	4,268.000	LF		19.00		
0130	202-B137	Removal of Guard Rail Cable Anchor	1.000	EA		250.00		
0140	202-B174	Removal of Debris and Sand From Box Culvert, Less Than 6-foo	1,062.000	LF		10.00		
0150	202-B175	Removal of Debris and Sand From Inlet and Junction Box, All	267.000	EA		125.00		
0160	202-B176	Removal of Debris and Sand From Pipe, 18" to Less Than 36" D	16,098.000	LF		6.50		
0170	202-B177	Removal of Debris and Sand From Pipe, 36" to Less Than 54" D	2,616.000	LF		8.50		
0180	202-B179	Removal of Debris and Sand From Pipe, 51" x 31" Arch Pipe	150.000	LF		8.50		
0190	202-B181	Removal of Debris and Sand From Pipe, 65" x 40" Arch Pipe	736.000	LF		10.50		
0200	202-B182	Removal of Debris and Sand From Pipe, Less Than 18" Diameter	2,201.000	LF		6.25		
0210	202-B189	Removal of Impact Attenuator	1.000	EA		750.00		
0220	202-B218	Removal of Inlet Tops	7.000	EA		600.00		
0230	202-B219	Removal of and Replacement of SS-2 Inlet Top	279.000	EA		1,000.00		
0240	202-B220	Removal of Debris and Sand From Pipe, 58" x 36" Arch Pipe	326.000	LF		9.00		
0250	202-B221	Removal of Debris and Sand From Pipe, 72" x 51" Arch Pipe	106.000	LF		12.00		
0260	202-B222	Removal of Debris and Sand From Pipe, 15" Slotted Metal Pip	6,917.000	LF		5.75		

HARRISON (24)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Superior Asphalt, Inc.	Hemphill Construction Company, Inc.	TCB Construction Company, Inc.
Grading, Draining, Paving & Replacing traffic signals on US 90 between Rodenburg Ave. and Biloxi Bay, known as Federal Aid Project Nos. ER-NH-0003-01(108) / 104569306 & ER-NH-0003-01(108) / 104569308, in the County of Harrison, State of Mississippi.					\$15,774,070.95	\$19,115,389.25	IRREGULAR	IRREGULAR
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0270	203-A002	Unclassified Excavation, LVM	417.000	CY		50.00		
0280	203-EX006	Borrow Excavation, AH, LVM, Class B3	2,478.000	CY		31.50		
0290	203-H004	Surplus Excavation, LVM, AH	100.000	CY		85.00		
0300	206-A001	Structure Excavation	405.000	CY		10.00		
0310	213-C001	Superphosphate	17.000	TON		650.00		
0320	216-B004	Solid Sodding, Bermuda	5,000.000	SY		5.00		
0330	219-A001	Watering	100.000	KGAL		20.00		
0340	220-A001	Insect Pest Control	17.000	ACRE		30.00		
0350	234-A001	Temporary Silt Fence	49,300.000	LF		2.20		
0360	235-A001	Temporary Erosion Checks	200.000	BALE		35.00		
0370	406-A001	Cold Milling of Bituminous Pavement, All Depths	226,661.000	SY		2.50		
0380	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	41,360.000	LF		3.50		
0390	503-C007	Saw Cut, Full Depth	1,000.000	LF		12.00		
0400	601-B001	Class "B" Structural Concrete, Minor Structures	31.000	CY		1,800.00		
0410	602-A001	Reinforcing Steel	2,297.000	LBS		3.00		
0420	603-CA002	18" Reinforced Concrete Pipe, Class III	1,984.000	LF		80.00		
0430	603-CA003	24" Reinforced Concrete Pipe, Class III	1,064.000	LF		90.00		
0440	603-CA004	30" Reinforced Concrete Pipe, Class III	428.000	LF		100.00		
0450	603-CA005	36" Reinforced Concrete Pipe, Class III	880.000	LF		115.00		
0460	603-CA006	42" Reinforced Concrete Pipe, Class III	232.000	LF		165.00		
0470	603-CE006	58" x 36" Concrete Arch Pipe, Class A III	40.000	LF		250.00		
0480	603-CE007	65" x 40" Concrete Arch Pipe, Class A III	80.000	LF		275.00		
0490	604-A001	Castings	4,373.000	LBS		7.00		
0500	606-A002	Guard Post, Type II Modified	63.000	EA		75.00		
0510	606-B002	Guard Rail, Class A, Type 1, Double Faced	75.000	LF		35.00		
0520	606-B003	Guard Rail, Class A, Type 1, Wood Post	263.000	LF		25.00		

HARRISON (24)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Superior Asphalt, Inc.	Hemphill Construction Company, Inc.	TCB Construction Company, Inc.
Grading, Draining, Paving & Replacing traffic signals on US 90 between Rodenburg Ave. and Biloxi Bay, known as Federal Aid Project Nos. ER-NH-0003-01(108) / 104569306 & ER-NH-0003-01(108) / 104569308, in the County of Harrison, State of Mississippi.					\$15,774,070.95	\$19,115,389.25	IRREGULAR	IRREGULAR
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0530	606-C003	Guard Rail, Cable Anchor, Type 1	1.000	EA		850.00		
0540	606-D008	Guard Rail, Bridge End Section, Type H	1.000	EA		1,150.00		
0550	608-A001	Concrete Sidewalk, Without Reinforcement	17,013.000	SY		53.50		
0560	609-B001	Concrete Curb, Header	863.000	LF		20.00		
0570	609-B002	Concrete Curb, Doweled	442.000	LF		22.00		
0580	609-B008	Concrete Curb, Special Design Header, Type 1	59,888.000	LF		24.00		
0590	609-B009	Concrete Curb, Special Design Header, Type 2	17,969.000	LF		26.00		
0600	609-D002	Combination Concrete Curb and Gutter Type 2	685.000	LF		30.00		
0610	609-D016	Combination Concrete Curb and Gutter Type 3 Modified	93.000	LF		33.00		
0620	613-D007	Adjustment of Utility Appurtenance	2.000	EA		500.00		
0630	616-A001	Concrete Median and/or Island Pavement, 4-inch	4,885.000	SY		47.00		
0640	616-A003	Concrete Median and/or Island Pavement, 10-inch	766.000	SY		85.00		
0650	618-A001	Maintenance of Traffic	1.000	LS		750,000.00		
0660	619-A1004	Temporary Traffic Stripe, Continuous White, Paint	3.000	MI		1,000.00		
0670	619-A2004	Temporary Traffic Stripe, Continuous Yellow, Paint	3.000	MI		1,000.00		
0680	619-A3007	Temporary Traffic Stripe, Skip White, Paint	21.000	MI		1,000.00		
0690	619-A4002	Temporary Traffic Stripe, Skip Yellow, Paint	2,080.000	LF		0.25		
0700	619-A5002	Temporary Traffic Stripe, Detail, Paint	13,786.000	LF		0.25		
0710	619-A6003	Temporary Traffic Stripe, Legend, Paint	14,552.000	LF		0.25		
0720	619-A6004	Temporary Traffic Stripe, Legend, Paint	2,071.000	SF		1.00		
0730	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	32.000	SF		30.00		
0740	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	696.000	SF		30.00		
0750	619-G4005	Barricades, Type III, Double Faced	48.000	LF		30.00		
0760	620-A001	Mobilization	1.000	LS		1,900,000.00		
0770	626-A002	6" Thermoplastic Traffic Stripe, Skip White	11.000	MI		1,500.00		
0780	626-B002	6" Thermoplastic Traffic Stripe, Continuous White	2.000	MI		3,000.00		

HARRISON (24)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Superior Asphalt, Inc.	Hemphill Construction Company, Inc.	TCB Construction Company, Inc.
Grading, Draining, Paving & Replacing traffic signals on US 90 between Rodenburg Ave. and Biloxi Bay, known as Federal Aid Project Nos. ER-NH-0003-01(108) / 104569306 & ER-NH-0003-01(108) / 104569308, in the County of Harrison, State of Mississippi.					\$15,774,070.95	\$19,115,389.25	IRREGULAR	IRREGULAR
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0790	626-D001	6" Thermoplastic Traffic Stripe, Skip Yellow	1,040.000	LF		0.50		
0800	626-E002	6" Thermoplastic Traffic Stripe, Continuous Yellow	2.000	MI		3,000.00		
0810	626-G001	Thermoplastic Detail Stripe, White	33,426.000	LF		1.00		
0820	626-G002	Thermoplastic Detail Stripe, Yellow	16,582.000	LF		1.00		
0830	626-H001	Thermoplastic Legend, White	5,794.000	SF		5.00		
0840	626-H002	Thermoplastic Legend, White	22,644.000	LF		1.00		
0850	627-K001	Red-Clear Reflective High Performance Raised Markers	2,114.000	EA		4.00		
0860	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	312.000	EA		4.00		
0870	629-A001	Vehicular Impact Attenuator, 50 MPH	1.000	EA		20,000.00		
0880	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	1,121.000	SF		25.00		
0890	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	706.000	SF		27.50		
0900	630-B001	Interstate Directional Signs, Bolted Extruded Aluminum Panel	803.000	SF		30.00		
0910	630-C004	Steel U-Section Posts, 3.0 to 3.5 lb/ft	2,698.000	LF		9.50		
0920	630-D003	Structural Steel Beams, W6 x 9	282.000	LF		55.00		
0930	630-E001	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	174.000	LBS		3.50		
0940	630-E002	Structural Steel Angles & Bars, 3 1/2" x 3 1/2" x 1/4" Angle	58.000	LBS		3.50		
0950	630-E003	Structural Steel Angles & Bars, 4" x 4" x 5/16" Angles	328.000	LBS		3.50		
0960	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	180.000	LBS		3.50		
0980	630-K001	Welded & Seamless Steel Pipe Posts, 3"	103.000	LF		45.00		
0990	630-K003	Welded & Seamless Steel Pipe Posts, 4"	48.000	LF		65.00		
1000	631-A001	Flowable Fill	1,942.000	CY		115.00		
1010	635-A001	Vehicle Loop Assemblies	96.000	LF		24.00		
1020	636-A001	Shielded Cable, AWG #18, 4 Conductor	950.000	LF		1.50		
1030	638-A005	Loop Detector Amplifier, Card Rack Mounted, 4 Channel	2.000	EA		700.00		
1040	640-A016	Traffic Signal Heads, Type 1 LED	67.000	EA		850.00		
1050	640-A018	Traffic Signal Heads, Type 3 LED	6.000	EA		1,100.00		

HARRISON (24)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Superior Asphalt, Inc.	Hemphill Construction Company, Inc.	TCB Construction Company, Inc.
Grading, Draining, Paving & Replacing traffic signals on US 90 between Rodenburg Ave. and Biloxi Bay, known as Federal Aid Project Nos. ER-NH-0003-01(108) / 104569306 & ER-NH-0003-01(108) / 104569308, in the County of Harrison, State of Mississippi.					\$15,774,070.95	\$19,115,389.25	IRREGULAR	IRREGULAR
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
1060	640-A020	Traffic Signal Heads, Type 5R LED	1.000	EA		1,000.00		
1070	640-A022	Traffic Signal Heads, Type 7 LED	28.000	EA		1,500.00		
1080	640-A031	Traffic Signal Heads, Type 1A LED	3.000	EA		3,500.00		
1090	640-A034	Traffic Signal Heads, Type 6 LED Countdown	76.000	EA		1,000.00		
1100	640-A036	Traffic Signal Heads, Type 5L, LED	12.000	EA		1,100.00		
1110	640-A037	Traffic Signal Heads, Type 5LA, LED	2.000	EA		3,600.00		
1120	642-A008	Solid State Traffic Actuated Controllers, Type 8A	12.000	EA		15,000.00		
1130	643-A001	Closed Loop On-Street Master System	1.000	EA		30,000.00		
1140	644-A001	Optical Detector	45.000	EA		750.00		
1150	644-B001	Optical Detector Cable	8,010.000	LF		1.50		
1160	644-C002	Phase Selector, 4 Channel	12.000	EA		3,500.00		
1170	646-A001	Removal of Existing Traffic Signal Equipment	1.000	LS		35,000.00		
1180	647-A005	Pullbox, Type 2	63.000	EA		450.00		
1190	650-A002	On Street Video Equipment, Fixed Type	2.000	EA		2,600.00		
1200	650-A003	On Street Video Equipment, PTZ Type	1.000	EA		4,600.00		
1210	666-B004	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 10, 2	3,558.000	LF		3.50		
1220	666-B015	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 5	10,127.000	LF		3.00		
1230	666-B016	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 7	8,160.000	LF		3.25		
1240	668-A016	Traffic Signal Conduit, Underground, Type 4, 1"	905.000	LF		4.25		
1250	668-A018	Traffic Signal Conduit, Underground, Type 4, 2"	840.000	LF		5.50		
1260	668-A020	Traffic Signal Conduit, Underground, Type 4, 3"	335.000	LF		7.00		
1270	668-B024	Traffic Signal Conduit, Underground Drilled or Jacked, Rolle	1,955.000	LF		9.00		
1280	668-B025	Traffic Signal Conduit, Underground Drilled or Jacked, Rolle	2,225.000	LF		11.00		
1290	699-A001	Roadway Construction Stakes	1.000	LS		550,000.00		
1300	907-213-A001	Agricultural Limestone	68.000	TON		300.00		
1310	907-227-A001	Hydroseeding	34.000	ACRE		2,500.00		

HARRISON (24)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Superior Asphalt, Inc.	Hemphill Construction Company, Inc.	TCB Construction Company, Inc.
Grading, Draining, Paving & Replacing traffic signals on US 90 between Rodenburg Ave. and Biloxi Bay, known as Federal Aid Project Nos. ER-NH-0003-01(108) / 104569306 & ER-NH-0003-01(108) / 104569308, in the County of Harrison, State of Mississippi.					\$15,774,070.95	\$19,115,389.25	IRREGULAR	IRREGULAR
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
1320	907-403-B002	Hot Mix Asphalt, HT, 19-mm mixture, Leveling	3,474.000	TON		100.00		
1330	907-403-D004	Hot Mix Asphalt, HT, 9.5-mm mixture, Polymer Modified	17,196.000	TON		100.00		
1340	907-403-E004	Hot Mix Asphalt, HT, 9.5-mm mixture, Polymer Modified, Level	18,441.000	TON		100.00		
1350	907-603-V001	Video Pipe Inspection, All Sizes	43,148.000	LF		1.50		
1360	907-622-A001	Engineer's Field Office Building, Type 2	1.000	EA		80,000.00		
1370	907-626-C003	6" Thermoplastic Double Drop Edge Stripe, Continuous White	7.000	MI		3,000.00		
1380	907-626-F003	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	6.000	MI		3,000.00		
1390	907-626-G001	Thermoplastic Detail Stripe, Blue-ADA	784.000	LF		1.00		
1400	907-629-D001	Crash Cushion System	64.000	LF		2,000.00		
1405	907-630-I001	Metal Overhead Sign Supports, Assembly No. 1, Contractor Des	1.000	LS		150,000.00		
1410	907-639-A002	Traffic Signal Equipment Pole, Type II, 17' Shaft, 50' Arm	2.000	EA		10,000.00		
1420	907-639-A006	Traffic Signal Equipment Pole, Type II, 17' Shaft, 30' Arm	3.000	EA		8,000.00		
1430	907-639-A007	Traffic Signal Equipment Pole, Type II, 17' Shaft, 40' Arm	4.000	EA		10,000.00		
1440	907-639-A011	Traffic Signal Equipment Pole, Type II, 17' Shaft, 35' Arm	4.000	EA		8,500.00		
1450	907-639-A015	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 50' Arm	6.000	EA		15,000.00		
1460	907-639-A016	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 55' Arm	2.000	EA		15,500.00		
1470	907-639-A017	Traffic Signal Equipment Pole, Type II, 17' Shaft, 25' Arm	6.000	EA		7,000.00		
1480	907-639-A020	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 60' Arm	5.000	EA		15,500.00		
1490	907-639-A021	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 40' Arm	3.000	EA		13,000.00		
1500	907-639-A028	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 30' Arm	1.000	EA		10,000.00		
1510	907-639-A029	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 45' Arm	2.000	EA		12,000.00		
1520	907-639-A030	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 65' Arm	1.000	EA		17,000.00		
1530	907-639-A031	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 70' Arm	2.000	EA		18,000.00		
1540	907-639-A032	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 25' & 60'	1.000	EA		20,000.00		
1550	907-639-A033	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 35' & 35'	1.000	EA		16,000.00		
1560	907-639-A034	Traffic Signal Equipment Pole, Type VI, 8' Shaft	12.000	EA		2,000.00		

HARRISON (24)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Superior Asphalt, Inc.	Hemphill Construction Company, Inc.	TCB Construction Company, Inc.
Grading, Draining, Paving & Replacing traffic signals on US 90 between Rodenburg Ave. and Biloxi Bay, known as Federal Aid Project Nos. ER-NH-0003-01(108) / 104569306 & ER-NH-0003-01(108) / 104569308, in the County of Harrison, State of Mississippi.					\$15,774,070.95	\$19,115,389.25	IRREGULAR	IRREGULAR
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
1570	907-639-C002	Pole Foundations, 36" Diameter	152.000	CY		1,000.00		
1580	907-639-C003	Pole Foundations, 24" Diameter	7.000	CY		1,500.00		
1590	907-639-D001	Slip Casing, 36" Diameter	581.000	LF		65.00		
1600	907-648-C001	Radio Ethernet Interconnect, Local Intersection	12.000	EA		12,000.00		
1610	907-648-D001	Radio Ethernet Distribution Repeater Installation	6.000	EA		160,000.00		
1620	907-648-E001	Radio Ethernet Fixed Backbone Repeater Installation	5.000	EA		70,000.00		
1630	907-648-F001	Radio Interconnect Training, Testing and Installation	1.000	LS		20,000.00		
1640	907-649-A001	Video Detection System, 1 Sensor	43.000	EA		9,400.00		
1650	907-649-B001	Video Detection-Data Collection and Reporting Tool License	14.000	EA		1,500.00		
1660	907-649-D001	Video Detection-Digitized Video Encoder/Decoded	14.000	EA		1,900.00		
1670	907-649-E001	Video Detection Training	1.000	LS		25,000.00		
1680	907-687-A014	Loop, Sensor, Loop ATR Station	1.000	EA		35,000.00		