

HARRISON (24)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Bond Paving Company, Inc.		
Construction necessary to build a new median crossover on U.S. Highway 49 at the Lyman Project Office, known as Federal-Aid Project No. HSIP-0008-01(105) / 104923301, in the County of Harrison, State of Mississippi.					\$85,768.00	\$228,857.00		
Ref#	SM Item	Item Description	Item Qty	Units		1		
0010	202-B076	Removal of Traffic Stripe	1,200.000	LF		2.40		
0020	212-B001	Standard Ground Preparation	2,420.000	SY		1.20		
0030	213-B001	Combination Fertilizer, 13-13-13	1.000	TON		1,440.00		
0040	214-A001	Seeding, Bahiagrass	13.000	LBS		12.00		
0050	214-A002	Seeding, Bermudagrass	10.000	LBS		12.00		
0060	304-A043	Granular Material, LVM, Class 9, Group C	180.000	CY		20.00		
0070	406-A001	Cold Milling of Bituminous Pavement, All Depths	925.000	SY		17.00		
0080	618-A001	Maintenance of Traffic	1.000	LS		50,000.00		
0090	618-B001	Additional Construction Signs	1.000	SF		10.00		
0100	620-A001	Mobilization	1.000	LS		70,000.00		
0110	626-C001	6" Thermoplastic Edge Stripe, Continuous White	400.000	LF		4.80		
0120	626-F001	6" Thermoplastic Edge Stripe, Continuous Yellow	1,200.000	LF		4.80		
0130	626-G001	Thermoplastic Detail Stripe, White	250.000	LF		4.80		
0140	626-G002	Thermoplastic Detail Stripe, Yellow	150.000	LF		4.80		
0150	626-H002	Thermoplastic Legend, White	12.000	LF		6.00		
0160	627-K001	Red-Clear Reflective High Performance Raised Markers	20.000	EA		12.00		
0170	907-213-A001	Agricultural Limestone	1.000	TON		360.00		
0180	907-304-F001	Size 825 Crushed Stone Base	145.000	TON		50.00		
0190	907-403-A012	Hot Mix Asphalt, ST, 19-mm mixture	300.000	TON		125.00		
0200	907-403-A015	Hot Mix Asphalt, ST, 9.5-mm mixture	180.000	TON		150.00		