

HARRISON (24)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Superior Asphalt, Inc.	Tanner Construction Company, Inc.	Hemphill Construction Company, Inc.
Reconstruction of US 90 between Lewis Ave. and Debuys Rd. in Gulfport, known as Federal Aid Project No. ER-NH-0003-01(104) / 104569302 & 310, in the County of Harrison, State of Mississippi.					\$26,318,199.05	\$26,856,983.59	\$28,466,524.25	\$28,584,566.83
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS		150,000.00	150,000.00	75,000.00
0020	202-A001	Removal of Obstructions	1.000	LS		60,000.00	150,000.00	150,000.00
0030	202-B024	Removal of Concrete Median & Island Pavement, All Depths	13,612.000	SY		13.00	20.00	33.50
0040	202-B035	Removal of Concrete Sidewalk	13,375.000	SY		14.00	20.00	15.00
0050	202-B038	Removal of Curb, All Types	149,739.000	LF		10.00	20.00	15.00
0060	202-B078	Removal of Pavement, All Types and Depths	10,035.000	SY		19.00	20.00	35.00
0070	202-B093	Removal of Curb & Gutter, All Types	5,508.000	LF		6.00	20.00	15.00
0080	202-B106	Removal of Pipe, All Sizes	6,123.000	LF		13.00	20.00	20.00
0090	202-B172	Removal of Debris and Sand From Box Culvert, 10-foot and Gre	230.000	LF		12.50	40.00	50.00
0100	202-B173	Removal of Debris and Sand From Box Culvert, 6-foot to Less	992.000	LF		11.00	30.00	30.00
0110	202-B174	Removal of Debris and Sand From Box Culvert, Less Than 6-foo	730.000	LF		9.00	20.00	30.00
0120	202-B175	Removal of Debris and Sand From Inlet and Junction Box, All	430.000	EA		75.00	78.00	135.00
0130	202-B176	Removal of Debris and Sand From Pipe, 18" to Less Than 36" D	23,667.000	LF		3.50	3.65	6.00
0140	202-B177	Removal of Debris and Sand From Pipe, 36" to Less Than 54" D	2,674.000	LF		4.50	4.70	7.00
0150	202-B180	Removal of Debris and Sand From Pipe, 54" to Less Than 72" D	82.000	LF		10.00	10.40	12.00
0160	202-B181	Removal of Debris and Sand From Pipe, 65" x 40" Arch Pipe	72.000	LF		6.00	6.25	12.00
0170	202-B182	Removal of Debris and Sand From Pipe, Less Than 18" Diameter	3,996.000	LF		3.50	3.65	5.00
0180	202-B218	Removal of Inlet Tops	28.000	EA		300.00	2,500.00	585.00
0190	202-B223	Removal of and Replacement of	391.000	EA		1,900.00	5,000.00	2,929.00
0200	202-B224	Removal of Debris and Sand From Pipe, 36" x 23" Arch Pipe	160.000	LF		5.00	5.20	7.00
0210	202-B225	Removal of Top of Sea Wall	376.000	LF		40.00	40.00	22.00
0220	203-EX006	Borrow Excavation, AH, LVM, Class B3	4,000.000	CY		30.00	33.38	18.00
0230	203-H004	Surplus Excavation, LVM, AH	200.000	CY		80.00	20.87	16.00
0240	213-C001	Superphosphate	29.000	TON		500.00	425.00	500.00
0250	216-B004	Solid Sodding, Bermuda	10,000.000	SY		2.50	4.00	2.80
0260	219-A001	Watering	200.000	KGAL		20.00	20.00	20.00

HARRISON (24)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Superior Asphalt, Inc.	Tanner Construction Company, Inc.	Hemphill Construction Company, Inc.
Reconstruction of US 90 between Lewis Ave. and Debuys Rd. in Gulfport, known as Federal Aid Project No. ER-NH-0003-01(104) / 104569302 & 310, in the County of Harrison, State of Mississippi.					\$26,318,199.05	\$26,856,983.59	\$28,466,524.25	\$28,584,566.83
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0270	220-A001	Insect Pest Control	57.000	ACRE		30.00	30.00	30.00
0280	234-A001	Temporary Silt Fence	82,416.000	LF		2.25	1.00	2.25
0290	235-A001	Temporary Erosion Checks	400.000	BALE		20.00	10.00	15.00
0300	406-A001	Cold Milling of Bituminous Pavement, All Depths	340,044.000	SY		2.50	3.65	3.50
0310	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	67,822.000	LF		9.00	9.50	9.80
0320	503-C007	Saw Cut, Full Depth	2,000.000	LF		9.00	12.00	10.00
0330	601-B001	Class "B" Structural Concrete, Minor Structures	35.000	CY		1,800.00	2,000.00	1,650.00
0340	602-A001	Reinforcing Steel	5,031.000	LBS		1.25	1.00	1.50
0350	603-CA002	18" Reinforced Concrete Pipe, Class III	3,161.000	LF		75.00	114.00	128.50
0360	603-CA003	24" Reinforced Concrete Pipe, Class III	1,449.000	LF		95.00	126.00	141.00
0370	603-CA004	30" Reinforced Concrete Pipe, Class III	772.000	LF		110.00	141.00	162.00
0380	603-CA005	36" Reinforced Concrete Pipe, Class III	521.000	LF		130.00	161.00	180.00
0390	603-CA006	42" Reinforced Concrete Pipe, Class III	184.000	LF		180.00	176.00	195.00
0400	603-CA008	54" Reinforced Concrete Pipe, Class III	32.000	LF		280.00	222.00	230.00
0410	603-CE003	36" x 23" Concrete Arch Pipe, Class A III	32.000	LF		220.00	142.00	250.00
0420	603-CE007	65" x 40" Concrete Arch Pipe, Class A III	32.000	LF		300.00	232.00	250.00
0430	604-A001	Castings	1,580.000	LBS		11.00	2.00	3.00
0440	608-A001	Concrete Sidewalk, Without Reinforcement	23,776.000	SY		50.00	44.00	43.00
0450	609-B001	Concrete Curb, Header	4,759.000	LF		30.00	19.00	22.65
0460	609-B002	Concrete Curb, Doweled	1,240.000	LF		31.00	20.00	24.00
0470	609-B008	Concrete Curb, Special Design Header, Type 1	101,612.000	LF		32.00	21.00	25.00
0480	609-B009	Concrete Curb, Special Design Header, Type 2	42,087.000	LF		31.00	21.00	25.00
0490	609-D002	Combination Concrete Curb and Gutter Type 2	1,136.000	LF		35.00	20.00	23.80
0500	609-D009	Combination Concrete Curb and Gutter Type 3B	4,511.000	LF		40.00	20.00	23.80
0510	613-D007	Adjustment of Utility Appurtenance	89.000	EA		325.00	1,650.00	1,000.00
0520	616-A001	Concrete Median and/or Island Pavement, 4-inch	13,158.000	SY		50.00	38.00	46.70

HARRISON (24)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Superior Asphalt, Inc.	Tanner Construction Company, Inc.	Hemphill Construction Company, Inc.
Reconstruction of US 90 between Lewis Ave. and Debuys Rd. in Gulfport, known as Federal Aid Project No. ER-NH-0003-01(104) / 104569302 & 310, in the County of Harrison, State of Mississippi.					\$26,318,199.05	\$26,856,983.59	\$28,466,524.25	\$28,584,566.83
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0530	616-A003	Concrete Median and/or Island Pavement, 10-inch	244.000	SY		70.00	80.00	94.00
0540	618-A001	Maintenance of Traffic	1.000	LS		1,500,000.00	1,000,000.00	1,785,000.00
0550	619-A1004	Temporary Traffic Stripe, Continuous White, Paint	7.000	MI		500.00	500.00	560.00
0560	619-A2003	Temporary Traffic Stripe, Continuous Yellow, Paint	6,172.000	LF		0.10	0.10	0.11
0570	619-A3007	Temporary Traffic Stripe, Skip White, Paint	34.000	MI		1,000.00	1,000.00	1,125.00
0580	619-A5002	Temporary Traffic Stripe, Detail, Paint	26,642.000	LF		0.20	0.20	0.22
0590	619-A6003	Temporary Traffic Stripe, Legend, Paint	19,652.000	LF		0.20	0.20	0.22
0600	619-A6004	Temporary Traffic Stripe, Legend, Paint	3,886.000	SF		1.00	1.00	1.15
0610	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	32.000	SF		25.00	20.00	20.00
0620	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	1,064.000	SF		25.00	20.00	20.00
0630	619-G4005	Barricades, Type III, Double Faced	48.000	LF		35.00	30.00	30.00
0640	620-A001	Mobilization	1.000	LS		2,500,000.00	2,910,000.00	1,900,000.00
0650	626-A002	6" Thermoplastic Traffic Stripe, Skip White	18.000	MI		1,500.00	1,500.00	1,590.00
0660	626-B002	6" Thermoplastic Traffic Stripe, Continuous White	4.000	MI		3,000.00	3,000.00	3,200.00
0670	626-E001	6" Thermoplastic Traffic Stripe, Continuous Yellow	3,086.000	LF		0.50	0.50	0.53
0680	626-G001	Thermoplastic Detail Stripe, White	44,361.000	LF		1.00	1.00	1.10
0690	626-G002	Thermoplastic Detail Stripe, Yellow	22,809.000	LF		1.00	1.00	1.10
0700	626-H001	Thermoplastic Legend, White	5,396.000	SF		5.00	5.00	5.30
0710	626-H002	Thermoplastic Legend, White	23,528.000	LF		1.00	1.00	1.10
0720	627-K001	Red-Clear Reflective High Performance Raised Markers	3,525.000	EA		4.00	4.00	4.25
0730	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	216.000	EA		4.00	4.00	4.25
0740	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	1,011.000	SF		22.00	22.00	23.50
0750	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	1,055.000	SF		25.00	25.00	26.50
0760	630-B001	Interstate Directional Signs, Bolted Extruded Aluminum Panel	561.000	SF		28.00	28.00	30.00
0770	630-C004	Steel U-Section Posts, 3.0 to 3.5 lb/ft	3,916.000	LF		8.00	8.00	8.50
0780	630-D003	Structural Steel Beams, W6 x 9	313.000	LF		55.00	55.00	60.00

HARRISON (24)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Superior Asphalt, Inc.	Tanner Construction Company, Inc.	Hemphill Construction Company, Inc.
Reconstruction of US 90 between Lewis Ave. and Debuys Rd. in Gulfport, known as Federal Aid Project No. ER-NH-0003-01(104) / 104569302 & 310, in the County of Harrison, State of Mississippi.					\$26,318,199.05	\$26,856,983.59	\$28,466,524.25	\$28,584,566.83
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0790	630-E001	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	375.000	LBS		5.50	5.50	5.85
0800	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	112.000	LBS		7.12	5.50	5.85
0810	630-K001	Welded & Seamless Steel Pipe Posts, 3"	89.000	LF		45.00	45.00	50.00
0820	631-A001	Flowable Fill	3,448.000	CY		110.00	120.00	95.00
0830	635-A001	Vehicle Loop Assemblies	1,056.000	LF		19.00	20.00	21.00
0840	636-A001	Shielded Cable, AWG #18, 4 Conductor	11,371.000	LF		1.40	1.50	1.55
0850	638-A005	Loop Detector Amplifier, Card Rack Mounted, 4 Channel	20.000	EA		725.00	750.00	800.00
0860	640-A016	Traffic Signal Heads, Type 1 LED	65.000	EA		840.00	875.00	925.00
0870	640-A018	Traffic Signal Heads, Type 3 LED	8.000	EA		1,150.00	1,200.00	1,265.00
0880	640-A022	Traffic Signal Heads, Type 7 LED	8.000	EA		1,455.00	1,500.00	1,600.00
0890	640-A031	Traffic Signal Heads, Type 1A LED	4.000	EA		3,700.00	3,850.00	4,100.00
0900	640-A034	Traffic Signal Heads, Type 6 LED Countdown	56.000	EA		945.00	1,000.00	1,040.00
0910	640-A036	Traffic Signal Heads, Type 5L, LED	20.000	EA		1,025.00	1,100.00	1,130.00
0915	640-A038	Traffic Signal Heads, Type 8A LED, 8" Amber	2.000	EA		2,000.00	2,000.00	2,200.00
0920	642-A008	Solid State Traffic Actuated Controllers, Type 8A	10.000	EA		15,500.00	16,000.00	17,000.00
0930	643-A001	Closed Loop On-Street Master System	1.000	EA		27,075.00	28,000.00	30,000.00
0940	644-A001	Optical Detector	37.000	EA		705.00	735.00	775.00
0950	644-B001	Optical Detector Cable	6,909.000	LF		1.50	1.50	1.65
0960	644-C002	Phase Selector, 4 Channel	10.000	EA		3,275.00	3,400.00	3,600.00
0970	646-A001	Removal of Existing Traffic Signal Equipment	1.000	LS		45,000.00	46,800.00	50,000.00
0980	647-A005	Pullbox, Type 2	83.000	EA		550.00	570.00	640.00
0990	650-A003	On Street Video Equipment, PTZ Type	3.000	EA		5,600.00	5,800.00	6,500.00
1000	666-B004	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 10, 2	2,707.000	LF		2.95	3.00	3.50
1010	666-B015	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 5	7,980.000	LF		2.75	3.00	3.25
1020	666-B016	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 7	8,109.000	LF		2.90	3.00	3.50
1030	668-A018	Traffic Signal Conduit, Underground, Type 4, 2"	552.000	LF		13.00	13.50	15.00

HARRISON (24)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Superior Asphalt, Inc.	Tanner Construction Company, Inc.	Hemphill Construction Company, Inc.
Reconstruction of US 90 between Lewis Ave. and Debuys Rd. in Gulfport, known as Federal Aid Project No. ER-NH-0003-01(104) / 104569302 & 310, in the County of Harrison, State of Mississippi.					\$26,318,199.05	\$26,856,983.59	\$28,466,524.25	\$28,584,566.83
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
1040	668-A020	Traffic Signal Conduit, Underground, Type 4, 3"	212.000	LF		14.00	14.50	16.50
1050	668-B024	Traffic Signal Conduit, Underground Drilled or Jacked, Rolle	7,639.000	LF		14.25	15.00	16.75
1060	668-B025	Traffic Signal Conduit, Underground Drilled or Jacked, Rolle	3,636.000	LF		16.00	16.50	19.00
1070	699-A001	Roadway Construction Stakes	1.000	LS		725,000.00	500,000.00	760,000.00
1080	907-213-A001	Agricultural Limestone	171.000	TON		60.00	120.00	65.00
1090	907-227-A001	Hydroseeding	57.000	ACRE		2,000.00	2,450.00	2,100.00
1100	907-403-B002	Hot Mix Asphalt, HT, 19-mm mixture, Leveling	5,519.000	TON		80.00	100.00	105.00
1110	907-403-D004	Hot Mix Asphalt, HT, 9.5-mm mixture, Polymer Modified	25,715.000	TON		100.00	100.00	109.00
1120	907-403-E004	Hot Mix Asphalt, HT, 9.5-mm mixture, Polymer Modified, Level	26,909.000	TON		100.00	100.00	109.00
1130	907-603-V001	Video Pipe Inspection, All Sizes	65,115.000	LF		1.20	1.04	1.65
1140	907-622-A002	Engineer's Field Office Building, Type 3	1.000	EA		100,000.00	50,000.00	75,000.00
1150	907-626-C003	6" Thermoplastic Double Drop Edge Stripe, Continuous White	14.000	MI		3,000.00	3,000.00	3,200.00
1160	907-626-F003	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	13.000	MI		3,000.00	3,000.00	3,200.00
1170	907-626-G001	Thermoplastic Detail Stripe, Blue-ADA	1,738.000	LF		5.00	5.00	5.30
1180	907-639-A002	Traffic Signal Equipment Pole, Type II, 17' Shaft, 50' Arm	2.000	EA		10,980.00	11,400.00	12,100.00
1190	907-639-A006	Traffic Signal Equipment Pole, Type II, 17' Shaft, 30' Arm	1.000	EA		7,675.00	8,000.00	8,500.00
1200	907-639-A007	Traffic Signal Equipment Pole, Type II, 17' Shaft, 40' Arm	1.000	EA		8,650.00	9,000.00	9,500.00
1205	907-639-A008	Traffic Signal Equipment Pole, Type II, 17' Shaft, 55' Arm	2.000	EA		11,590.00	12,000.00	12,750.00
1210	907-639-A009	Traffic Signal Equipment Pole, Type II, 17' Shaft, 60' Arm	3.000	EA		13,325.00	14,000.00	14,650.00
1215	907-639-A012	Traffic Signal Equipment Pole, Type II, 17' Shaft, 45' Arm	1.000	EA		10,975.00	11,500.00	12,100.00
1220	907-639-A015	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 50' Arm	3.000	EA		13,500.00	14,000.00	14,850.00
1230	907-639-A020	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 60' Arm	3.000	EA		14,800.00	15,400.00	16,275.00
1240	907-639-A021	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 40' Arm	5.000	EA		11,260.00	11,700.00	12,375.00
1250	907-639-A028	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 30' Arm	3.000	EA		8,460.00	8,800.00	9,300.00
1260	907-639-A034	Traffic Signal Equipment Pole, Type VI, 8' Shaft	16.000	EA		1,200.00	1,250.00	1,320.00
1270	907-639-A035	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 30' & 30'	1.000	EA		14,850.00	15,500.00	16,320.00

HARRISON (24)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Superior Asphalt, Inc.	Tanner Construction Company, Inc.	Hemphill Construction Company, Inc.
Reconstruction of US 90 between Lewis Ave. and Debuys Rd. in Gulfport, known as Federal Aid Project No. ER-NH-0003-01(104) / 104569302 & 310, in the County of Harrison, State of Mississippi.					\$26,318,199.05	\$26,856,983.59	\$28,466,524.25	\$28,584,566.83
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
1275	907-639-A040	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 30' & 45'	2.000	EA		15,390.00	16,000.00	16,950.00
1280	907-639-A036	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 40' & 40'	3.000	EA		14,875.00	14,500.00	16,350.00
1290	907-639-A038	Traffic Signal Equipment Pole, Type IV, 30' Shaft, 40' & 50'	1.000	EA		17,100.00	18,000.00	18,800.00
1295	907-639-A043	Traffic Signal Equipment Pole, Type VI-A, 15' Shaft	2.000	EA		2,000.00	2,000.00	2,200.00
1300	907-639-C002	Pole Foundations, 36" Diameter	96.000	CY		1,500.00	1,600.00	2,000.00
1310	907-639-C003	Pole Foundations, 24" Diameter	9.000	CY		1,150.00	1,200.00	1,500.00
1320	907-639-D001	Slip Casing, 36" Diameter	375.000	LF		100.00	100.00	120.00
1330	907-648-C001	Radio Ethernet Interconnect, Local Intersection	9.000	EA		10,150.00	10,000.00	11,200.00
1340	907-648-D001	Radio Ethernet Distribution Repeater Installation	2.000	EA		140,000.00	131,000.00	140,000.00
1350	907-648-E001	Radio Ethernet Fixed Backbone Repeater Installation	6.000	EA		60,000.00	57,500.00	60,500.00
1360	907-648-F001	Radio Interconnect Training, Testing and Installation	1.000	LS		20,000.00	17,500.00	18,700.00
1370	907-649-A001	Video Detection System, 1 Sensor	31.000	EA		7,350.00	7,650.00	8,100.00
1380	907-649-B001	Video Detection-Data Collection and Reporting Tool License	10.000	EA		1,250.00	1,300.00	1,375.00
1390	907-649-D001	Video Detection-Digitized Video Encoder/Decoded	10.000	EA		1,550.00	1,600.00	1,710.00
1400	907-649-E001	Video Detection Training	1.000	LS		21,000.00	21,850.00	23,000.00
1410	907-687-A014	Loop, Sensor, Loop ATR Station	1.000	EA		40,000.00	32,250.00	35,000.00
1420	907-813-J001	Cleaning and Coating Existing Railing	6,593.000	LF		19.00	10.00	8.50