

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) further propose to execute the attached contract agreement (Section 902) as soon as the work is awarded to me (us), and to begin and complete the work within the time limit(s) provided for in the Specifications and Advertisement. I (We) also propose to execute the attached contract bond (Section 903) in an amount not less than one hundred (100) percent of the total of my (our) part, but also to guarantee the excellence of both workmanship and materials until the work is finally accepted.

I (We) enclose a certified check, cashier's check or bid bond for **five percent (5%) of total bid** and hereby agree that in case of my (our) failure to execute the contract and furnish bond within Ten (10) days after notice of award, the amount of this check (bid bond) will be forfeited to the State of Mississippi as liquidated damages arising out of my (our) failure to execute the contract as proposed. It is understood that in case I am (we are) not awarded the work, the check will be returned as provided in the Specifications.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. 1 DATED 10/16/2007 ADDENDUM NO. DATED
ADDENDUM NO. DATED ADDENDUM NO. DATED

Number	Description
1	Revised Table of Contents; Added Notice to Bidders #1747; Revised Diskette Required.

TOTAL ADDENDA: 1
(Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

Contractor

BY _____
Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

_____ President	_____ Address
_____ Secretary	_____ Address
_____ Treasurer	_____ Address

The following is my (our) itemized proposal.

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

TABLE OF CONTENTS

PROJECT: BR-0034-01(007) / 103323301 – Yalobusha County

RE-ADVERTISEMENT – NOTICE TO BIDDERS # 1731

901--Advertisement

904--Notice to Bidders: Governing Specs. - # 1
 Status of ROW, Utility Adjustments and Underground Storage
 Tanks, W/Attachments - # 2
 Final Cleanup - #3
 Federal Bridge Formula - # 12
 Submission of Form OCR-485 - # 13
 Storm Water Discharge Associated W/Construction Activities
 (≥1 and <5 Acres) - #14
 Changes in Submittal of DBE Forms - #16
 Fiber Reinforced Concrete - #640
 Disadvantage Business Enterprise W/Supplement - # 696
 On-The-Job Training Program - # 777
 DBE Participation and Payment - # 882
 Payroll Requirements - # 883
 Use of Precast Drainage Units - #1321
 Errata & Modifications to 2004 Standard Specifications - #1405
 Contract Time - #1696
 Specialty Items – 1697
 Minimum Wage Rate - #1699
 Advance Notice of Closure - #1708
 Petroleum Products Base Price - # 1722
 Road Closure - #1733
 Box Culvert Construction - #1747

906: Required Federal Contract Provisions -- FHWA-1273, W/Supplement

907-104-1: Partnering Process
907-105-3: Cooperation By Contractors
907-107-1: Liability Insurance, W/Supplement
907-107-3: Contractor's Protection Plan
907-107-6: Legal Relations & Responsibility to Public
907-108-11: Prosecution and Progress

-CONTINUED ON NEXT PAGE-

- 907-108-12: Additional Construction Provisions, W/Supplement
- 907-109-3: Partial Payment, W/Supplement
- 907-213-1: Agricultural Limestone
- 907-225-1: Grassing
- 907-226-1: Temporary Grassing
- 907-304-9: Crushed Aggregate Courses
- 907-401-2: Hot Mix Asphalt (HMA), W/Supplement
- 907-403-4: Hot Mix Asphalt (HMA), W/Supplement
- 907-617-2: Right-of-Way Markers
- 907-618-4: Placement of Temporary Traffic Stripe
- 907-701-2: Portland Cement
- 907-708-4: Non-Metal Drainage Structures
- 907-711-3: Synthetic Structural Fiber Reinforcement
- 907-714-2: Miscellaneous Materials
- 907-715-2: Roadside Development Materials
- 907-804-2: Concrete Bridges and Structures W/Supplement

- 906-3: MDOT On-the-Job Training Program
- 906-6: MDOT On-the-Job Training Program - Alternate Program

SECTION 905 - PROPOSAL, PROPOSAL SHEET NOS. 2-1 THRU 2-9
COMBINATION BID PROPOSAL,
CERTIFICATE OF PERFORMANCE - PRIOR FEDERAL-AID CONTRACTS,
NON-COLLUSION CERTIFICATE,
SECTION 902 - CONTRACT FORM, AND SECTION 903 - CONTRACT BOND FORM,
OCR-485,
HAUL PERMIT FOR BRIDGES WITH POSTED WEIGHT LIMITS.
(REVISIONS TO THE ABOVE WILL BE INDICATED ON THE SECOND SHEET
OF SECTION 905 AS ADDENDA)

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904 -NOTICE TO BIDDERS NO. 1747

CODE: (SP)

DATE: 10/16/2007

SUBJECT: Box Culvert Construction

PROJECT: BR-0034-01 (007) / 103323 Yalobusha County

Bidders are hereby advised of the following box culvert requirements:

Site 1:

On the estimated quantities for box bridge, box culvert, and drainage structures, working sheet number EQ-4, the standard drawings listed on the sheet are for information purposes only and may or may not be used or applicable to the construction of the precast box culverts.

The two 12' x 8' box culverts shall be placed 4" to 12" apart. Pay item 631-A Flowable Fill shall be used to fill the void between the box culverts before fill material shall be place over the box.

The two 12' x 8' box culverts will have approximately 17 feet of fill material above the box culverts. The contractor is responsible for placing precast units that are designed for this approximate cover height.

Wing walls, aprons and parapets shall be cast-in-place for the double 12' x 8' precast box culvert.

Site 2:

Wing walls, aprons and parapets shall be cast-in-place for the 12' x 6' precast box culvert.