

WAYNE (77)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Magco, Inc.	Key, LLC
Replacing the bridge south of Clara at Turkey Creek, known as Federal Aid Project No. BR-1132-00(007) / 102412301, in Wayne County, State of Mississippi.					\$2,021,595.09	\$1,541,150.33	\$1,762,590.37	\$1,831,043.26
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS		34,000.00	96,102.05	28,000.00
0020	201-B001	Clearing and Grubbing	1.000	ACRE		1,000.00	2,730.00	1,700.00
0030	202-A001	Removal of Obstructions	1.000	LS		10,000.00	20,150.00	7,500.00
0040	202-B076	Removal of Traffic Stripe	400.000	LF		2.00	2.00	2.00
0050	202-B078	Removal of Pavement, All Types and Depths	4,548.000	SY		4.00	5.00	2.00
0060	202-B102	Removal of Guard Rail	200.000	LF		2.50	6.82	5.00
0070	202-B106	Removal of Pipe, All Sizes	133.000	LF		4.00	5.00	17.00
0080	203-A001	Unclassified Excavation, FM	7,517.000	CY		2.74	4.68	4.70
0090	203-EX013	Borrow Excavation, AH, FME, Class B7	11,265.000	CY		6.62	7.00	13.70
0100	203-EX039	Borrow Excavation, AH, LVM, Class B7-6	1,380.000	CY		10.07	7.00	12.70
0110	206-A001	Structure Excavation	153.000	CY		7.00	5.20	12.70
0120	209-A004	Geotextile Stabilization, Type V, Non-Woven	5,360.000	SY		1.00	1.43	3.20
0130	211-A001	Topsoil for Slope Treatment, From Right-of-Way	48,324.000	SY		0.08	0.94	0.25
0140	212-A001	Light Ground Preparation	24,162.000	SY		0.06	0.06	0.06
0150	212-B001	Standard Ground Preparation	48,324.000	SY		0.06	0.06	0.06
0160	213-B001	Combination Fertilizer, 13-13-13	6.000	TON		500.00	750.00	500.00
0170	213-C001	Superphosphate	5.000	TON		500.00	500.00	500.00
0180	214-A001	Seeding, Bahiagrass	250.000	LBS		4.00	5.00	4.00
0190	214-A002	Seeding, Bermudagrass	200.000	LBS		6.00	7.00	6.00
0200	214-A003	Seeding, Tall Fescue	75.000	LBS		3.25	4.00	3.25
0210	214-A004	Seeding, Crimson Clover	100.000	LBS		3.25	4.00	3.25
0220	214-A014	Seeding, Browntop Millet	100.000	LBS		1.50	3.00	1.50
0230	214-A015	Seeding, Oats	449.000	LBS		1.50	2.00	1.50
0240	214-A017	Seeding, Rye Grass	125.000	LBS		1.50	2.50	1.50
0250	215-A001	Vegetative Materials for Mulch	25.000	TON		185.00	200.00	185.00
0260	216-A001	Solid Sodding	68.000	SY		10.00	8.00	10.00

WAYNE (77)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Magco, Inc.	Key, LLC
Replacing the bridge south of Clara at Turkey Creek, known as Federal Aid Project No. BR-1132-00(007) / 102412301, in Wayne County, State of Mississippi.					\$2,021,595.09	\$1,541,150.33	\$1,762,590.37	\$1,831,043.26
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0270	217-A001	Ditch Liner	679.000	SY		1.50	2.00	1.50
0280	219-A001	Watering	2.000	KGAL		20.00	20.00	20.00
0290	220-A001	Insect Pest Control	5.000	ACRE		30.00	30.00	30.00
0300	221-A001	Portland Cement Concrete Paved Ditch	9.000	CY		700.00	371.80	400.00
0310	223-A001	Mowing	1.000	ACRE		40.00	40.00	40.00
0320	224-A001	Soil Reinforcing Mat	265.000	SY		5.00	5.00	5.00
0330	234-A001	Temporary Silt Fence	2,494.000	LF		3.25	6.00	4.70
0340	235-A001	Temporary Erosion Checks	337.000	BALE		8.00	8.00	10.00
0350	236-A004	Silt Basin, Type D	1.000	EA		2,000.00	2,860.00	1,250.00
0360	239-A001	Temporary Slope Drains	121.000	LF		7.00	48.43	10.00
0370	406-A001	Cold Milling of Bituminous Pavement, All Depths	734.000	SY		10.00	10.00	11.00
0380	408-A003	Asphalt for Prime Coat, Cut-Back MC-70 or Emulsified EA-1	783.000	GAL		3.00	2.00	1.00
0390	423-A001	Rumble Strips, Ground In	2.000	MI		1,000.00	1,250.00	1,250.00
0400	501-E001	Expansion Joints, Without Dowels	94.000	LF		5.00	8.45	7.00
0410	501-K001	Transverse Grooving	196.000	SY		3.20	2.60	3.00
0420	502-A001	Reinforced Cement Concrete Bridge End Pavement	202.000	SY		85.00	85.00	125.00
0430	603-ALT001	18" Type A Alternate Pipe	480.000	LF		23.00	30.03	25.00
0440	603-CA089	24" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	24.000	LF		50.00	61.10	65.00
0450	603-CA091	36" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	84.000	LF		88.00	111.80	110.00
0460	603-CA121	36" Reinforced Concrete Pipe, Class V, Jacked or Bored	60.000	LF		400.00	603.10	850.00
0470	603-CB002	24" Reinforced Concrete End Section	2.000	EA		700.00	817.70	1,000.00
0480	603-CB004	36" Reinforced Concrete End Section	4.000	EA		1,300.00	1,433.90	1,650.00
0490	605-AA004	Geotextile for Subsurface Drainage, Type V	759.000	SY		1.00	1.69	2.60
0500	605-O003	6" Perforated Sewer Pipe for Underdrains, SDR 23.5	1,000.000	LF		1.00	18.20	10.00
0510	605-P003	6" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	200.000	LF		1.00	18.20	10.00
0520	605-W001	Filter Material for Combination Storm Drain and/or Underdrai	64.000	CY		1.00	65.00	28.00

WAYNE (77)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Magco, Inc.	Key, LLC
Replacing the bridge south of Clara at Turkey Creek, known as Federal Aid Project No. BR-1132-00(007) / 102412301, in Wayne County, State of Mississippi.					\$2,021,595.09	\$1,541,150.33	\$1,762,590.37	\$1,831,043.26
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0530	605-W002	Filter Material for Combination Storm Drain and/or Underdrai	69.000	CY		1.00	65.00	42.00
0540	606-B001	Guard Rail, Class A, Type 1	300.000	LF		21.50	21.50	21.50
0550	606-D012	Guard Rail, Bridge End Section, Type I	4.000	EA		2,250.00	2,250.00	2,250.00
0560	606-E001	Guard Rail, Terminal End Section	4.000	EA		2,500.00	2,500.00	2,500.00
0570	609-D002	Combination Concrete Curb and Gutter Type 2	129.000	LF		20.00	28.00	25.00
0580	615-A015	Concrete Bridge End Barrier, 32"	40.000	LF		50.00	57.55	125.00
0590	618-A001	Maintenance of Traffic	1.000	LS		6,000.00	24,000.00	30,000.00
0600	619-A1004	Temporary Traffic Stripe, Continuous White, Paint	1.000	MI		1,000.00	1,000.00	1,000.00
0610	619-A1007	Temporary Traffic Stripe, Continuous White, Type 1 Tape	2,946.000	LF		2.00	2.00	2.00
0620	619-A2004	Temporary Traffic Stripe, Continuous Yellow, Paint	1.000	MI		1,000.00	1,000.00	1,000.00
0630	619-A2007	Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape	2,946.000	LF		2.00	2.00	2.00
0640	619-A5001	Temporary Traffic Stripe, Detail	158.000	LF		1.00	1.00	1.00
0650	619-A6001	Temporary Traffic Stripe, Legend	108.000	LF		1.00	1.00	1.00
0660	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	36.000	SF		12.00	15.00	11.55
0670	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	244.000	SF		12.00	15.00	11.55
0680	619-G4001	Barricades, Type III, Single Faced	48.000	LF		24.00	20.00	20.95
0690	619-G4005	Barricades, Type III, Double Faced	24.000	LF		30.00	30.00	30.50
0700	619-G5001	Free Standing Plastic Drums	45.000	EA		30.00	85.00	63.10
0710	619-G7001	Warning Lights, Type "B"	6.000	EA		200.00	250.00	500.00
0720	620-A001	Mobilization	1.000	LS		152,000.00	97,550.00	180,000.00
0730	626-E002	6" Thermoplastic Traffic Stripe, Continuous Yellow	2.000	MI		3,000.00	3,000.00	3,000.00
0740	626-G001	Thermoplastic Detail Stripe, White	343.000	LF		2.00	2.00	2.00
0750	626-H002	Thermoplastic Legend, White	128.000	LF		2.00	2.00	2.00
0760	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	72.000	EA		5.00	5.00	5.00
0770	628-J002	6" High Performance Cold Plastic Traffic Stripe, Continuous	547.000	LF		5.00	5.00	5.00
0780	628-M002	6" High Performance Cold Plastic Traffic Stripe, Continuous	564.000	LF		5.00	5.00	5.00

WAYNE (77)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Magco, Inc.	Key, LLC
Replacing the bridge south of Clara at Turkey Creek, known as Federal Aid Project No. BR-1132-00(007) / 102412301, in Wayne County, State of Mississippi.					\$2,021,595.09	\$1,541,150.33	\$1,762,590.37	\$1,831,043.26
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0790	628-O002	High Performance Cold Plastic Detail Stripe, Yellow	16.000	LF		5.00	5.00	5.00
0800	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	18.000	SF		25.00	25.00	25.00
0810	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	35.000	SF		30.00	30.00	30.00
0820	630-C004	Steel U-Section Posts, 3.0 to 3.5 lb/ft	130.000	LF		9.50	9.50	9.50
0830	630-F001	Delineators, Guard Rail, White	19.000	EA		18.00	18.00	18.00
0840	699-A001	Roadway Construction Stakes	1.000	LS		20,000.00	26,500.00	30,000.00
0850	815-A009	Loose Riprap, Size 300	489.000	TON		57.00	59.61	65.00
0860	815-E001	Geotextile under Riprap	1,111.000	SY		1.00	1.47	3.70
0870	815-F001	Sediment Control Stone	2.000	CY		250.00	55.90	175.00
0880	907-213-A001	Agricultural Limestone	30.000	TON		100.00	70.00	75.00
0890	907-304-F001	Size 825 Crushed Stone Base	2,418.000	TON		47.00	44.00	44.00
0900	907-403-A011	Hot Mix Asphalt, ST, 12.5-mm mixture	1,149.000	TON		80.00	79.00	79.00
0910	907-403-A012	Hot Mix Asphalt, ST, 19-mm mixture	956.000	TON		80.00	74.00	74.00
0920	907-403-A015	Hot Mix Asphalt, ST, 9.5-mm mixture	862.000	TON		80.00	85.00	85.00
0930	907-403-C005	Hot Mix Asphalt, ST, 19-mm mixture, Trench Widening	394.000	TON		80.00	100.00	100.00
0940	907-601-B003	Class "B" Structural Concrete, Minor Structures	2.000	CY		1,400.00	1,189.50	1,000.00
0950	907-617-A001	Right-of-Way Marker	17.000	EA		200.00	130.00	125.00
0960	907-626-C003	6" Thermoplastic Double Drop Edge Stripe, Continuous White	2.000	MI		3,000.00	3,000.00	3,000.00
0970	501-K001	Transverse Grooving	1,067.000	SY		3.20	3.50	2.75
0980	803-B001	Conventional Static Loading Test	2.000	EA		5,000.00	5,000.00	5,000.00
0990	803-D002	HP 12 x 53 Steel Piling	760.000	LF		48.00	52.65	50.00
1000	803-D003	HP 14 x 73 Steel Piling	1,290.000	LF		60.00	66.95	65.00
1010	803-I001	PDA Test Pile	3.000	EA		5,000.00	5,980.00	5,500.00
1020	803-J001	Pile Restrike	2.000	EA		1,000.00	2,405.00	500.00
1030	805-A001	Reinforcement	80,781.000	LBS		0.82	0.83	1.00
1040	813-A001	Concrete Railing	483.000	LF		50.00	57.55	58.00

WAYNE (77)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Magco, Inc.	Key, LLC
Replacing the bridge south of Clara at Turkey Creek, known as Federal Aid Project No. BR-1132-00(007) / 102412301, in Wayne County, State of Mississippi.					\$2,021,595.09	\$1,541,150.33	\$1,762,590.37	\$1,831,043.26
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
1050	815-A009	Loose Riprap, Size 300	655.000	TON		57.00	59.61	65.00
1060	815-E001	Geotextile under Riprap	333.000	SY		1.00	1.47	3.70
1070	907-804-A001	Bridge Concrete, Class AA	447.000	CY		450.00	495.30	470.00
1080	907-804-C016	40' Prestressed Concrete Beam, Type I+2	1,417.000	LF		61.00	65.00	72.00

WAYNE (77)					Dozer, LLC			
Replacing the bridge south of Clara at Turkey Creek, known as Federal Aid Project No. BR-1132-00(007) / 102412301, in Wayne County, State of Mississippi.					\$1,983,429.19			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0010	201-A001	Clearing and Grubbing	1.000	LS	125,000.00			
0020	201-B001	Clearing and Grubbing	1.000	ACRE	5,000.00			
0030	202-A001	Removal of Obstructions	1.000	LS	20,000.00			
0040	202-B076	Removal of Traffic Stripe	400.000	LF	2.00			
0050	202-B078	Removal of Pavement, All Types and Depths	4,548.000	SY	5.00			
0060	202-B102	Removal of Guard Rail	200.000	LF	5.00			
0070	202-B106	Removal of Pipe, All Sizes	133.000	LF	20.00			
0080	203-A001	Unclassified Excavation, FM	7,517.000	CY	4.00			
0090	203-EX013	Borrow Excavation, AH, FME, Class B7	11,265.000	CY	9.80			
0100	203-EX039	Borrow Excavation, AH, LVM, Class B7-6	1,380.000	CY	7.00			
0110	206-A001	Structure Excavation	153.000	CY	7.00			
0120	209-A004	Geotextile Stabilization, Type V, Non-Woven	5,360.000	SY	3.00			
0130	211-A001	Topsoil for Slope Treatment, From Right-of-Way	48,324.000	SY	1.65			
0140	212-A001	Light Ground Preparation	24,162.000	SY	0.06			
0150	212-B001	Standard Ground Preparation	48,324.000	SY	0.08			
0160	213-B001	Combination Fertilizer, 13-13-13	6.000	TON	500.00			
0170	213-C001	Superphosphate	5.000	TON	500.00			
0180	214-A001	Seeding, Bahiagrass	250.000	LBS	4.00			
0190	214-A002	Seeding, Bermudagrass	200.000	LBS	8.00			
0200	214-A003	Seeding, Tall Fescue	75.000	LBS	3.25			
0210	214-A004	Seeding, Crimson Clover	100.000	LBS	3.25			
0220	214-A014	Seeding, Browntop Millet	100.000	LBS	1.50			
0230	214-A015	Seeding, Oats	449.000	LBS	1.50			
0240	214-A017	Seeding, Rye Grass	125.000	LBS	1.50			
0250	215-A001	Vegetative Materials for Mulch	25.000	TON	185.00			
0260	216-A001	Solid Sodding	68.000	SY	10.00			

WAYNE (77)					Dozer, LLC			
Replacing the bridge south of Clara at Turkey Creek, known as Federal Aid Project No. BR-1132-00(007) / 102412301, in Wayne County, State of Mississippi.					\$1,983,429.19			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0270	217-A001	Ditch Liner	679.000	SY	1.50			
0280	219-A001	Watering	2.000	KGAL	20.00			
0290	220-A001	Insect Pest Control	5.000	ACRE	30.00			
0300	221-A001	Portland Cement Concrete Paved Ditch	9.000	CY	350.00			
0310	223-A001	Mowing	1.000	ACRE	40.00			
0320	224-A001	Soil Reinforcing Mat	265.000	SY	5.00			
0330	234-A001	Temporary Silt Fence	2,494.000	LF	3.25			
0340	235-A001	Temporary Erosion Checks	337.000	BALE	8.00			
0350	236-A004	Silt Basin, Type D	1.000	EA	2,500.00			
0360	239-A001	Temporary Slope Drains	121.000	LF	10.00			
0370	406-A001	Cold Milling of Bituminous Pavement, All Depths	734.000	SY	15.00			
0380	408-A003	Asphalt for Prime Coat, Cut-Back MC-70 or Emulsified EA-1	783.000	GAL	2.00			
0390	423-A001	Rumble Strips, Ground In	2.000	MI	1,350.00			
0400	501-E001	Expansion Joints, Without Dowels	94.000	LF	15.00			
0410	501-K001	Transverse Grooving	196.000	SY	4.10			
0420	502-A001	Reinforced Cement Concrete Bridge End Pavement	202.000	SY	125.00			
0430	603-ALT001	18" Type A Alternate Pipe	480.000	LF	18.00			
0440	603-CA089	24" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	24.000	LF	50.00			
0450	603-CA091	36" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	84.000	LF	89.00			
0460	603-CA121	36" Reinforced Concrete Pipe, Class V, Jacked or Bored	60.000	LF	912.00			
0470	603-CB002	24" Reinforced Concrete End Section	2.000	EA	738.00			
0480	603-CB004	36" Reinforced Concrete End Section	4.000	EA	1,312.00			
0490	605-AA004	Geotextile for Subsurface Drainage, Type V	759.000	SY	3.00			
0500	605-O003	6" Perforated Sewer Pipe for Underdrains, SDR 23.5	1,000.000	LF	15.00			
0510	605-P003	6" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	200.000	LF	15.00			
0520	605-W001	Filter Material for Combination Storm Drain and/or Underdrai	64.000	CY	25.00			

WAYNE (77)					Dozer, LLC			
Replacing the bridge south of Clara at Turkey Creek, known as Federal Aid Project No. BR-1132-00(007) / 102412301, in Wayne County, State of Mississippi.					\$1,983,429.19			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0530	605-W002	Filter Material for Combination Storm Drain and/or Underdrai	69.000	CY	25.00			
0540	606-B001	Guard Rail, Class A, Type 1	300.000	LF	21.60			
0550	606-D012	Guard Rail, Bridge End Section, Type I	4.000	EA	2,250.00			
0560	606-E001	Guard Rail, Terminal End Section	4.000	EA	2,500.00			
0570	609-D002	Combination Concrete Curb and Gutter Type 2	129.000	LF	25.00			
0580	615-A015	Concrete Bridge End Barrier, 32"	40.000	LF	150.00			
0590	618-A001	Maintenance of Traffic	1.000	LS	28,000.00			
0600	619-A1004	Temporary Traffic Stripe, Continuous White, Paint	1.000	MI	1,000.00			
0610	619-A1007	Temporary Traffic Stripe, Continuous White, Type 1 Tape	2,946.000	LF	2.00			
0620	619-A2004	Temporary Traffic Stripe, Continuous Yellow, Paint	1.000	MI	1,000.00			
0630	619-A2007	Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape	2,946.000	LF	2.00			
0640	619-A5001	Temporary Traffic Stripe, Detail	158.000	LF	1.00			
0650	619-A6001	Temporary Traffic Stripe, Legend	108.000	LF	1.00			
0660	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	36.000	SF	12.00			
0670	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	244.000	SF	12.00			
0680	619-G4001	Barricades, Type III, Single Faced	48.000	LF	21.00			
0690	619-G4005	Barricades, Type III, Double Faced	24.000	LF	31.00			
0700	619-G5001	Free Standing Plastic Drums	45.000	EA	75.00			
0710	619-G7001	Warning Lights, Type "B"	6.000	EA	600.00			
0720	620-A001	Mobilization	1.000	LS	189,000.00			
0730	626-E002	6" Thermoplastic Traffic Stripe, Continuous Yellow	2.000	MI	3,000.00			
0740	626-G001	Thermoplastic Detail Stripe, White	343.000	LF	2.00			
0750	626-H002	Thermoplastic Legend, White	128.000	LF	2.00			
0760	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	72.000	EA	5.00			
0770	628-J002	6" High Performance Cold Plastic Traffic Stripe, Continuous	547.000	LF	5.00			
0780	628-M002	6" High Performance Cold Plastic Traffic Stripe, Continuous	564.000	LF	5.00			

WAYNE (77)					Dozer, LLC			
Replacing the bridge south of Clara at Turkey Creek, known as Federal Aid Project No. BR-1132-00(007) / 102412301, in Wayne County, State of Mississippi.					\$1,983,429.19			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0790	628-O002	High Performance Cold Plastic Detail Stripe, Yellow	16.000	LF	5.00			
0800	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	18.000	SF	25.00			
0810	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	35.000	SF	30.00			
0820	630-C004	Steel U-Section Posts, 3.0 to 3.5 lb/ft	130.000	LF	9.50			
0830	630-F001	Delineators, Guard Rail, White	19.000	EA	18.00			
0840	699-A001	Roadway Construction Stakes	1.000	LS	30,000.00			
0850	815-A009	Loose Riprap, Size 300	489.000	TON	50.00			
0860	815-E001	Geotextile under Riprap	1,111.000	SY	3.00			
0870	815-F001	Sediment Control Stone	2.000	CY	100.00			
0880	907-213-A001	Agricultural Limestone	30.000	TON	500.00			
0890	907-304-F001	Size 825 Crushed Stone Base	2,418.000	TON	44.00			
0900	907-403-A011	Hot Mix Asphalt, ST, 12.5-mm mixture	1,149.000	TON	79.00			
0910	907-403-A012	Hot Mix Asphalt, ST, 19-mm mixture	956.000	TON	74.00			
0920	907-403-A015	Hot Mix Asphalt, ST, 9.5-mm mixture	862.000	TON	85.00			
0930	907-403-C005	Hot Mix Asphalt, ST, 19-mm mixture, Trench Widening	394.000	TON	100.00			
0940	907-601-B003	Class "B" Structural Concrete, Minor Structures	2.000	CY	2,500.00			
0950	907-617-A001	Right-of-Way Marker	17.000	EA	250.00			
0960	907-626-C003	6" Thermoplastic Double Drop Edge Stripe, Continuous White	2.000	MI	3,000.00			
0970	501-K001	Transverse Grooving	1,067.000	SY	4.10			
0980	803-B001	Conventional Static Loading Test	2.000	EA	5,000.00			
0990	803-D002	HP 12 x 53 Steel Piling	760.000	LF	47.00			
1000	803-D003	HP 14 x 73 Steel Piling	1,290.000	LF	62.00			
1010	803-I001	PDA Test Pile	3.000	EA	5,000.00			
1020	803-J001	Pile Restrike	2.000	EA	1,000.00			
1030	805-A001	Reinforcement	80,781.000	LBS	0.90			
1040	813-A001	Concrete Railing	483.000	LF	68.00			

WAYNE (77)					Dozer, LLC			
Replacing the bridge south of Clara at Turkey Creek, known as Federal Aid Project No. BR-1132-00(007) / 102412301, in Wayne County, State of Mississippi.					\$1,983,429.19			
Ref#	SM Item	Item Description	Item Qty	Units	4			
1050	815-A009	Loose Riprap, Size 300	655.000	TON	50.00			
1060	815-E001	Geotextile under Riprap	333.000	SY	3.00			
1070	907-804-A001	Bridge Concrete, Class AA	447.000	CY	520.00			
1080	907-804-C016	40' Prestressed Concrete Beam, Type I+2	1,417.000	LF	65.00			