

HANCOCK (23)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Malouf Construction, LLC	T. L. Wallace Construction Company, Inc.	Kenneth R. Thompson, Jr., Builder, Inc.
Construction necessary to build a new Administration Building, Inspection Barn, install a new Static / Weigh-In-Motion Scale System, and make other improvements to the Weigh-In-Motion Truck Scale Facilities on I-10 (Eastbound) Near NASA, known as Federal Aid Project No. IM-0010-01(122)N / 104808301, in the County of Hancock, State of Mississippi.					\$13,072,042.50	\$13,055,704.95	\$13,098,272.93	\$14,573,183.54
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS		27,250.00	500,000.00	187,200.00
0020	202-B005	Removal of Asphalt Pavement, All Depths	19,605.000	SY		7.25	3.10	6.00
0030	202-B030	Removal of Concrete Pavement, All Depths	4,154.000	SY		11.80	8.20	18.00
0040	202-B038	Removal of Curb, All Types	2,865.000	LF		8.00	2.10	5.25
0050	202-B041	Removal of Fence, All Types	654.000	LF		2.90	3.12	3.20
0060	202-B042	Removal of Flared End Section, All Sizes	6.000	EA		345.00	105.00	374.40
0070	202-B057	Removal of Inlets, All Sizes	9.000	EA		161.00	525.00	600.00
0080	202-B064	Removal of Pipe, 8" And Above	1,388.000	LF		19.50	8.50	15.00
0090	202-B076	Removal of Traffic Stripe	11,250.000	LF		1.10	1.00	1.28
0100	202-B079	Removal of Headwall	3.000	EA		1,350.00	2,000.00	1,050.00
0110	202-B102	Removal of Guard Rail	696.000	LF		6.95	6.00	7.70
0120	202-B107	Removal of Sign, Ground Mounted with Posts	16.000	EA		150.00	200.00	200.00
0130	202-B142	Removal of Junction Box	2.000	EA		500.00	270.00	675.00
0140	203-A002	Unclassified Excavation, LVM	12,538.000	CY		5.65	10.00	5.25
0150	203-D002	Muck Excavation, LVM	500.000	CY		14.00	23.00	13.50
0160	203-EX017	Borrow Excavation, AH, FME, Class B9	55,086.000	CY		15.00	20.00	16.51
0170	203-EX038	Borrow Excavation, AH, FME, Class B7-6	15,888.000	CY		16.50	20.00	17.28
0180	206-A001	Structure Excavation	1,341.000	CY		12.00	15.00	9.00
0190	206-B001	Select Material for Undercuts, Contractor Furnished, FM	1,000.000	CY		60.00	75.00	18.00
0200	209-A004	Geotextile Stabilization, Type V, Non-Woven	68,320.000	SY		2.50	1.75	2.11
0210	211-A001	Topsoil for Slope Treatment, From Right-of-Way	95,826.000	SY		1.45	0.75	1.28
0220	212-B001	Standard Ground Preparation	3,866.000	SY		0.30	0.25	0.32
0230	213-B001	Combination Fertilizer, 13-13-13	1.000	TON		1,100.00	1,000.00	1,280.00
0240	216-B001	Solid Sodding, Centipede	3,866.000	SY		4.45	4.00	5.12
0250	219-A001	Watering	2.000	KGAL		20.00	20.00	20.00

HANCOCK (23)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Malouf Construction, LLC	T. L. Wallace Construction Company, Inc.	Kenneth R. Thompson, Jr., Builder, Inc.
Construction necessary to build a new Administration Building, Inspection Barn, install a new Static / Weigh-In-Motion Scale System, and make other improvements to the Weigh-In-Motion Truck Scale Facilities on I-10 (Eastbound) Near NASA, known as Federal Aid Project No. IM-0010-01(122)N / 104808301, in the County of Hancock, State of Mississippi.					\$13,072,042.50	\$13,055,704.95	\$13,098,272.93	\$14,573,183.54
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0260	220-A001	Insect Pest Control	20.000	ACRE		30.00	30.00	30.00
0270	221-A001	Portland Cement Concrete Paved Ditch	14.000	CY		400.00	350.00	512.00
0280	223-A001	Mowing	19.000	ACRE		40.00	40.00	40.00
0290	234-A001	Temporary Silt Fence	10,964.000	LF		3.05	3.00	3.52
0300	235-A001	Temporary Erosion Checks	553.000	BALE		9.00	8.00	10.25
0305	501-D001	Expansion Joints, With Dowels	100.000	LF		14.00	32.00	45.00
0307	501-E001	Expansion Joints, Without Dowels	1,000.000	LF		11.50	17.00	23.00
0310	423-A001	Rumble Strips, Ground In	1.000	MI		3,980.00	500.00	3,200.00
0320	602-A001	Reinforcing Steel	54,856.000	LBS		1.20	0.95	0.95
0330	603-A033	6" Steel Pipe, Wall Thickness 0.250"	120.000	LF		45.00	29.00	25.00
0340	603-A034	8" Steel Pipe, Wall Thickness 0.250"	50.000	LF		75.00	45.00	48.00
0350	603-CA002	18" Reinforced Concrete Pipe, Class III	1,381.000	LF		38.00	42.00	47.36
0360	603-CA003	24" Reinforced Concrete Pipe, Class III	955.000	LF		60.00	60.00	79.36
0370	603-CB001	18" Reinforced Concrete End Section	3.000	EA		1,000.00	800.00	1,123.20
0380	603-CB002	24" Reinforced Concrete End Section	4.000	EA		1,100.00	950.00	1,200.00
0390	603-CE001	22" x 13" Concrete Arch Pipe, Class A III	252.000	LF		71.50	65.00	87.05
0400	603-CE004	44" x 27" Concrete Arch Pipe, Class A III	128.000	LF		101.00	120.00	174.08
0410	603-CF001	22" x 13" Concrete Arch Pipe End Section	6.000	EA		1,030.00	800.00	1,123.00
0420	603-CF004	44" x 27" Concrete Arch Pipe End Section	1.000	EA		2,100.00	1,550.00	2,097.00
0430	604-B001	Gratings	5,990.000	LBS		2.70	3.30	6.40
0440	605-AA003	Geotextile for Subsurface Drainage, Type III	164.000	SY		2.50	3.30	6.00
0450	605-Q002	6" Perforated Corrugated Polyethylene Drainage Tubing for Un	204.000	LF		13.00	18.00	15.00
0460	605-R002	6" Non-perforated Corrugated Polyethylene Drainage Tubing fo	16.000	LF		10.25	18.00	15.00
0470	605-X001	Filter Material for Filter Beds, Type A	20.000	CY		150.00	60.00	120.00
0480	605-X003	Filter Material for Filter Beds, Type B	60.000	CY		55.00	75.00	30.75

HANCOCK (23)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Malouf Construction, LLC	T. L. Wallace Construction Company, Inc.	Kenneth R. Thompson, Jr., Builder, Inc.
Construction necessary to build a new Administration Building, Inspection Barn, install a new Static / Weigh-In-Motion Scale System, and make other improvements to the Weigh-In-Motion Truck Scale Facilities on I-10 (Eastbound) Near NASA, known as Federal Aid Project No. IM-0010-01(122)N / 104808301, in the County of Hancock, State of Mississippi.					\$13,072,042.50	\$13,055,704.95	\$13,098,272.93	\$14,573,183.54
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0490	606-B001	Guard Rail, Class A, Type 1	450.000	LF		25.50	23.00	29.45
0500	606-C003	Guard Rail, Cable Anchor, Type 1	1.000	EA		1,275.00	1,150.00	1,472.00
0510	606-E001	Guard Rail, Terminal End Section	1.000	EA		2,950.00	2,650.00	3,392.00
0520	607-A001	31.5" Type"A" Woven Wire Fence, w/ Barbed Wire as Shown	764.000	LF		4.00	10.00	6.65
0530	607-P1002	Line Post, 10' x 4" Timber	45.000	EA		46.00	135.00	51.10
0540	607-P2002	Brace Post, 10' x 6" Timber	14.000	EA		58.00	135.00	63.90
0550	607-Z001	Concrete Anchors	14.000	EA		17.00	150.00	18.70
0560	608-A001	Concrete Sidewalk, Without Reinforcement	365.000	SY		44.50	32.00	44.00
0570	609-D009	Combination Concrete Curb and Gutter Type 3B	4,004.000	LF		14.45	12.25	20.00
0580	616-A001	Concrete Median and/or Island Pavement, 4-inch	958.000	SY		47.50	29.00	37.00
0590	616-A003	Concrete Median and/or Island Pavement, 10-inch	48.000	SY		81.00	85.00	70.00
0600	618-A001	Maintenance of Traffic	1.000	LS		42,400.00	150,000.00	105,664.00
0610	619-A1007	Temporary Traffic Stripe, Continuous White, Type 1 Tape	4,820.000	LF		2.20	2.00	2.56
0620	619-A2007	Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape	4,820.000	LF		2.20	2.00	2.56
0630	619-A3004	Temporary Traffic Stripe, Skip White, Type 1 Tape	4,820.000	LF		2.20	2.00	2.56
0640	619-C6001	Red-Clear Reflective High Performance Raised Marker	184.000	EA		4.40	4.00	5.12
0650	619-C9001	One-Way Yellow Reflective High Performance Raised Marker	124.000	EA		4.40	4.00	5.12
0660	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	43.000	SF		18.70	17.00	21.75
0670	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	250.000	SF		18.70	17.00	21.75
0680	619-F1001	Concrete Median Barrier, Precast	2,720.000	LF		55.00	60.00	49.25
0690	619-F2001	Remove and Reset Concrete Median Barrier, Precast	1,750.000	LF		6.00	10.00	8.50
0700	619-G4001	Barricades, Type III, Single Faced	22.000	LF		30.80	28.00	36.00
0710	619-G7001	Warning Lights, Type "B"	4.000	EA		275.00	250.00	320.00
0720	620-A001	Mobilization	1.000	LS		845,930.00	1,000,000.00	700,000.00
0730	626-A001	6" Thermoplastic Traffic Stripe, Skip White	6,255.000	LF		1.10	1.00	1.28

HANCOCK (23)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Malouf Construction, LLC	T. L. Wallace Construction Company, Inc.	Kenneth R. Thompson, Jr., Builder, Inc.
Construction necessary to build a new Administration Building, Inspection Barn, install a new Static / Weigh-In-Motion Scale System, and make other improvements to the Weigh-In-Motion Truck Scale Facilities on I-10 (Eastbound) Near NASA, known as Federal Aid Project No. IM-0010-01(122)N / 104808301, in the County of Hancock, State of Mississippi.					\$13,072,042.50	\$13,055,704.95	\$13,098,272.93	\$14,573,183.54
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0740	626-G001	Thermoplastic Detail Stripe, White	1,435.000	LF		1.10	1.00	1.28
0750	627-K001	Red-Clear Reflective High Performance Raised Markers	500.000	EA		4.40	4.00	5.12
0760	628-I002	6" High Performance Cold Plastic Traffic Stripe, Skip White	680.000	LF		5.50	5.00	6.40
0770	628-J002	6" High Performance Cold Plastic Traffic Stripe, Continuous	19,260.000	LF		5.50	5.00	6.40
0780	628-M002	6" High Performance Cold Plastic Traffic Stripe, Continuous	9,742.000	LF		5.50	5.00	6.40
0790	628-O001	High Performance Cold Plastic Detail Stripe, White	16,889.000	LF		5.50	5.00	6.40
0800	628-O002	High Performance Cold Plastic Detail Stripe, Yellow	67.000	LF		5.50	5.00	6.40
0810	628-P001	High Performance Cold Plastic Legend, White	48.000	SF		27.50	25.00	32.00
0820	628-P002	High Performance Cold Plastic Legend, White	196.000	LF		5.50	5.00	6.40
0830	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	81.000	SF		24.00	21.50	27.52
0840	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	531.000	SF		27.00	24.50	31.40
0850	630-B001	Interstate Directional Signs, Bolted Extruded Aluminum Panel	516.000	SF		30.50	27.50	35.20
0860	630-C004	Steel U-Section Posts, 3.0 to 3.5 lb/ft	126.000	LF		9.50	8.50	10.90
0870	630-D003	Structural Steel Beams, W6 x 9	33.000	LF		50.00	45.00	57.60
0880	630-D004	Structural Steel Beams, W6 x 12	101.000	LF		55.50	50.00	64.00
0890	630-D005	Structural Steel Beams, W6 x 15	42.000	LF		61.00	55.00	70.50
0900	630-D006	Structural Steel Beams, W8 x 18	40.000	LF		66.50	60.00	77.00
0910	630-D007	Structural Steel Beams, W8 x 21	45.000	LF		72.00	65.00	83.20
0920	630-D009	Structural Steel Beams, W10 x 26	51.000	LF		78.00	70.00	89.60
0930	630-E001	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	135.000	LBS		3.90	3.50	4.50
0940	630-E002	Structural Steel Angles & Bars, 3 1/2" x 3 1/2" x 1/4" Angle	134.000	LBS		3.90	3.50	4.50
0950	630-E003	Structural Steel Angles & Bars, 4" x 4" x 5/16" Angles	66.000	LBS		3.90	3.50	4.50
0960	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	710.000	LBS		3.90	3.50	4.50
0970	630-F001	Delineators, Guard Rail, White	24.000	EA		20.00	18.00	23.04
0980	630-K002	Welded & Seamless Steel Pipe Posts, 3 1/2"	257.000	LF		50.00	45.00	57.60

HANCOCK (23)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Malouf Construction, LLC	T. L. Wallace Construction Company, Inc.	Kenneth R. Thompson, Jr., Builder, Inc.
Construction necessary to build a new Administration Building, Inspection Barn, install a new Static / Weigh-In-Motion Scale System, and make other improvements to the Weigh-In-Motion Truck Scale Facilities on I-10 (Eastbound) Near NASA, known as Federal Aid Project No. IM-0010-01(122)N / 104808301, in the County of Hancock, State of Mississippi.					\$13,072,042.50	\$13,055,704.95	\$13,098,272.93	\$14,573,183.54
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0990	630-K003	Welded & Seamless Steel Pipe Posts, 4"	310.000	LF		55.50	50.00	64.00
1000	682-A021	Underground Branch Circuit, AWG 3, 3 Conductor	12,285.000	LF		9.85	8.60	11.00
1010	682-A031	Underground Branch Circuit, AWG 6, 3 Conductor	4,605.000	LF		7.25	6.35	8.15
1020	682-B022	Underground Branch Circuit, Jacked or Bored, AWG 3, 3 Conduc	40.000	LF		32.50	28.30	38.00
1030	682-B031	Underground Branch Circuit, Jacked or Bored, AWG 6, 3 Conduc	40.000	LF		27.80	24.25	38.00
1040	682-D001	Underground Pull Box	7.000	EA		1,805.00	1,575.00	2,020.00
1050	683-A114	Lighting Assembly, High Mast, Type 60-4-S	1.000	EA		22,700.00	19,806.00	25,500.00
1060	683-A116	Lighting Assembly, High Mast, Type 60-2-A	2.000	EA		21,000.00	18,302.00	23,500.00
1070	683-B050	Lighting Assembly, Low Mast, Type 40-1-10-250	61.000	EA		2,230.00	1,945.00	2,500.00
1080	683-D001	Portable Electric Power Units	1.000	EA		3,900.00	3,401.00	4,400.00
1090	684-A003	Pole Foundation, 24" Diameter	67.000	CY		1,245.00	1,084.00	1,400.00
1100	684-A004	Pole Foundation, 36" Diameter	17.000	CY		855.00	746.00	975.00
1110	684-B003	Slip Casing, 24" Diameter	10.000	LF		86.00	75.00	100.00
1120	684-B004	Slip Casing, 36" Diameter	20.000	LF		85.00	74.00	100.00
1130	699-A001	Roadway Construction Stakes	1.000	LS		118,600.00	175,000.00	105,000.00
1140	907-213-A001	Agricultural Limestone	60.000	TON		72.00	65.00	83.20
1150	907-225-A001	Grassing	19.000	ACRE		1,275.00	1,150.00	1,472.00
1160	907-230-B066	Tree Planting, Magnolia, From Right-Of-Way	25.000	EA		150.00	100.00	150.00
1170	907-242-A006	Construction of	1.000	LS		591,000.00	625,000.00	558,000.00
1180	907-242-B006	Construction of	1.000	LS		566,000.00	475,000.00	600,500.00
1190	907-242-C001	Construction of	1.000	LS		1,017,500.00	846,793.00	1,085,000.00
1200	907-242-PP003	Construction of	1.000	LS		52,700.00	60,000.00	193,632.00
1210	907-258-E001	Trash Receptacle	2.000	EA		835.00	1,500.00	1,020.00
1220	907-259-C001	Lighting Assembly, Flag Pole Lighting	2.000	EA		670.00	580.00	800.00
1230	907-290-A001	Flagpole	2.000	EA		3,000.00	3,500.00	1,925.00

HANCOCK (23)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Malouf Construction, LLC	T. L. Wallace Construction Company, Inc.	Kenneth R. Thompson, Jr., Builder, Inc.
Construction necessary to build a new Administration Building, Inspection Barn, install a new Static / Weigh-In-Motion Scale System, and make other improvements to the Weigh-In-Motion Truck Scale Facilities on I-10 (Eastbound) Near NASA, known as Federal Aid Project No. IM-0010-01(122)N / 104808301, in the County of Hancock, State of Mississippi.					\$13,072,042.50	\$13,055,704.95	\$13,098,272.93	\$14,573,183.54
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
1240	907-304-F001	Size 825 Crushed Stone Base	23,866.000	TON		42.20	43.00	47.80
1250	907-307-C003	6" Soil-Lime-Water Mixing, Class C	30,940.000	SY		2.50	2.00	2.56
1260	907-307-D001	Lime	490.000	TON		200.00	180.00	230.40
1270	907-403-A012	Hot Mix Asphalt, ST, 19-mm mixture	10,965.000	TON		110.50	90.00	115.00
1280	907-501-B004	14" Plain Cement Concrete Pavement, Tine Finish	57,576.000	SY		61.25	56.00	72.00
1290	907-601-A001	Class "B" Structural Concrete	446.000	CY		680.00	550.00	1,088.00
1300	907-601-B001	Class "B" Structural Concrete, Minor Structures, Per Plans	31.000	CY		1,120.00	1,200.00	2,200.00
1310	907-622-A001	Engineer's Field Office Building, Type 2	1.000	EA		23,500.00	50,000.00	24,000.00
1320	907-626-C007	6" Thermoplastic Double Drop Edge Stripe, Continuous White	2,520.000	LF		1.15	1.00	1.28
1330	907-626-F005	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	5,000.000	LF		1.15	1.00	1.28
1340	907-628-G001	6" Cold Plastic Detail Stripe, Blue-ADA	100.000	LF		11.50	10.00	12.80
1350	907-628-H002	Cold Plastic Legend, Blue-ADA Handicap Symbol	1.000	EA		350.00	300.00	384.00
1360	907-308-A001	Portland Cement	262.000	TON		166.50	150.00	192.00
1370	907-308-B001	Soil-Cement-Water Mixing, Optional Mixers, Base	30,940.000	SY		2.50	2.00	2.56
1380	907-311-A003	Processing Lime and Fly Ash Treated Course, 6" Thick	30,940.000	SY				
1390	907-311-B001	Lime	245.000	TON				
1400	907-311-C001	Fly Ash, Class C	978.000	TON				

HANCOCK (23)					Colom Construction Company, Inc.			
Construction necessary to build a new Administration Building, Inspection Barn, install a new Static / Weigh-In-Motion Scale System, and make other improvements to the Weigh-In-Motion Truck Scale Facilities on I-10 (Eastbound) Near NASA, known as Federal Aid Project No. IM-0010-01(122)N / 104808301, in the County of Hancock, State of Mississippi.					\$15,015,582.30			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0010	201-A001	Clearing and Grubbing	1.000	LS	750,000.00			
0020	202-B005	Removal of Asphalt Pavement, All Depths	19,605.000	SY	3.00			
0030	202-B030	Removal of Concrete Pavement, All Depths	4,154.000	SY	10.00			
0040	202-B038	Removal of Curb, All Types	2,865.000	LF	10.00			
0050	202-B041	Removal of Fence, All Types	654.000	LF	3.00			
0060	202-B042	Removal of Flared End Section, All Sizes	6.000	EA	1,000.00			
0070	202-B057	Removal of Inlets, All Sizes	9.000	EA	1,500.00			
0080	202-B064	Removal of Pipe, 8" And Above	1,388.000	LF	15.00			
0090	202-B076	Removal of Traffic Stripe	11,250.000	LF	1.00			
0100	202-B079	Removal of Headwall	3.000	EA	2,000.00			
0110	202-B102	Removal of Guard Rail	696.000	LF	6.50			
0120	202-B107	Removal of Sign, Ground Mounted with Posts	16.000	EA	2,500.00			
0130	202-B142	Removal of Junction Box	2.000	EA	1,500.00			
0140	203-A002	Unclassified Excavation, LVM	12,538.000	CY	7.50			
0150	203-D002	Muck Excavation, LVM	500.000	CY	15.00			
0160	203-EX017	Borrow Excavation, AH, FME, Class B9	55,086.000	CY	19.00			
0170	203-EX038	Borrow Excavation, AH, FME, Class B7-6	15,888.000	CY	19.00			
0180	206-A001	Structure Excavation	1,341.000	CY	20.00			
0190	206-B001	Select Material for Undercuts, Contractor Furnished, FM	1,000.000	CY	55.00			
0200	209-A004	Geotextile Stabilization, Type V, Non-Woven	68,320.000	SY	2.50			
0210	211-A001	Topsoil for Slope Treatment, From Right-of-Way	95,826.000	SY	3.50			
0220	212-B001	Standard Ground Preparation	3,866.000	SY	2.20			
0230	213-B001	Combination Fertilizer, 13-13-13	1.000	TON	820.00			
0240	216-B001	Solid Sodding, Centipede	3,866.000	SY	6.00			
0250	219-A001	Watering	2.000	KGAL	20.00			

HANCOCK (23)					Colom Construction Company, Inc.			
Construction necessary to build a new Administration Building, Inspection Barn, install a new Static / Weigh-In-Motion Scale System, and make other improvements to the Weigh-In-Motion Truck Scale Facilities on I-10 (Eastbound) Near NASA, known as Federal Aid Project No. IM-0010-01(122)N / 104808301, in the County of Hancock, State of Mississippi.					\$15,015,582.30			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0260	220-A001	Insect Pest Control	20.000	ACRE	30.00			
0270	221-A001	Portland Cement Concrete Paved Ditch	14.000	CY	500.00			
0280	223-A001	Mowing	19.000	ACRE	40.00			
0290	234-A001	Temporary Silt Fence	10,964.000	LF	4.00			
0300	235-A001	Temporary Erosion Checks	553.000	BALE	25.00			
0305	501-D001	Expansion Joints, With Dowels	100.000	LF	50.00			
0307	501-E001	Expansion Joints, Without Dowels	1,000.000	LF	25.00			
0310	423-A001	Rumble Strips, Ground In	1.000	MI	3,000.00			
0320	602-A001	Reinforcing Steel	54,856.000	LBS	1.10			
0330	603-A033	6" Steel Pipe, Wall Thickness 0.250"	120.000	LF	35.00			
0340	603-A034	8" Steel Pipe, Wall Thickness 0.250"	50.000	LF	45.00			
0350	603-CA002	18" Reinforced Concrete Pipe, Class III	1,381.000	LF	40.00			
0360	603-CA003	24" Reinforced Concrete Pipe, Class III	955.000	LF	55.00			
0370	603-CB001	18" Reinforced Concrete End Section	3.000	EA	750.00			
0380	603-CB002	24" Reinforced Concrete End Section	4.000	EA	1,000.00			
0390	603-CE001	22" x 13" Concrete Arch Pipe, Class A III	252.000	LF	60.00			
0400	603-CE004	44" x 27" Concrete Arch Pipe, Class A III	128.000	LF	110.00			
0410	603-CF001	22" x 13" Concrete Arch Pipe End Section	6.000	EA	1,000.00			
0420	603-CF004	44" x 27" Concrete Arch Pipe End Section	1.000	EA	2,000.00			
0430	604-B001	Gratings	5,990.000	LBS	6.00			
0440	605-AA003	Geotextile for Subsurface Drainage, Type III	164.000	SY	4.00			
0450	605-Q002	6" Perforated Corrugated Polyethylene Drainage Tubing for Un	204.000	LF	20.00			
0460	605-R002	6" Non-perforated Corrugated Polyethylene Drainage Tubing fo	16.000	LF	20.00			
0470	605-X001	Filter Material for Filter Beds, Type A	20.000	CY	100.00			
0480	605-X003	Filter Material for Filter Beds, Type B	60.000	CY	100.00			



HANCOCK (23)					Colom Construction Company, Inc.			
Construction necessary to build a new Administration Building, Inspection Barn, install a new Static / Weigh-In-Motion Scale System, and make other improvements to the Weigh-In-Motion Truck Scale Facilities on I-10 (Eastbound) Near NASA, known as Federal Aid Project No. IM-0010-01(122)N / 104808301, in the County of Hancock, State of Mississippi.					\$15,015,582.30			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0490	606-B001	Guard Rail, Class A, Type 1	450.000	LF	24.00			
0500	606-C003	Guard Rail, Cable Anchor, Type 1	1.000	EA	1,200.00			
0510	606-E001	Guard Rail, Terminal End Section	1.000	EA	2,800.00			
0520	607-A001	31.5" Type"A" Woven Wire Fence, w/ Barbed Wire as Shown	764.000	LF	5.50			
0530	607-P1002	Line Post, 10' x 4" Timber	45.000	EA	45.00			
0540	607-P2002	Brace Post, 10' x 6" Timber	14.000	EA	55.00			
0550	607-Z001	Concrete Anchors	14.000	EA	20.00			
0560	608-A001	Concrete Sidewalk, Without Reinforcement	365.000	SY	22.00			
0570	609-D009	Combination Concrete Curb and Gutter Type 3B	4,004.000	LF	14.00			
0580	616-A001	Concrete Median and/or Island Pavement, 4-inch	958.000	SY	25.00			
0590	616-A003	Concrete Median and/or Island Pavement, 10-inch	48.000	SY	55.00			
0600	618-A001	Maintenance of Traffic	1.000	LS	125,000.00			
0610	619-A1007	Temporary Traffic Stripe, Continuous White, Type 1 Tape	4,820.000	LF	2.10			
0620	619-A2007	Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape	4,820.000	LF	2.10			
0630	619-A3004	Temporary Traffic Stripe, Skip White, Type 1 Tape	4,820.000	LF	2.10			
0640	619-C6001	Red-Clear Reflective High Performance Raised Marker	184.000	EA	4.25			
0650	619-C9001	One-Way Yellow Reflective High Performance Raised Marker	124.000	EA	4.25			
0660	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	43.000	SF	18.00			
0670	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	250.000	SF	18.00			
0680	619-F1001	Concrete Median Barrier, Precast	2,720.000	LF	50.00			
0690	619-F2001	Remove and Reset Concrete Median Barrier, Precast	1,750.000	LF	15.00			
0700	619-G4001	Barricades, Type III, Single Faced	22.000	LF	30.00			
0710	619-G7001	Warning Lights, Type "B"	4.000	EA	275.00			
0720	620-A001	Mobilization	1.000	LS	1,000,000.00			
0730	626-A001	6" Thermoplastic Traffic Stripe, Skip White	6,255.000	LF	1.05			

HANCOCK (23)					Colom Construction Company, Inc.			
Construction necessary to build a new Administration Building, Inspection Barn, install a new Static / Weigh-In-Motion Scale System, and make other improvements to the Weigh-In-Motion Truck Scale Facilities on I-10 (Eastbound) Near NASA, known as Federal Aid Project No. IM-0010-01(122)N / 104808301, in the County of Hancock, State of Mississippi.					\$15,015,582.30			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0740	626-G001	Thermoplastic Detail Stripe, White	1,435.000	LF	1.05			
0750	627-K001	Red-Clear Reflective High Performance Raised Markers	500.000	EA	4.25			
0760	628-I002	6" High Performance Cold Plastic Traffic Stripe, Skip White	680.000	LF	5.25			
0770	628-J002	6" High Performance Cold Plastic Traffic Stripe, Continuous	19,260.000	LF	5.25			
0780	628-M002	6" High Performance Cold Plastic Traffic Stripe, Continuous	9,742.000	LF	5.25			
0790	628-O001	High Performance Cold Plastic Detail Stripe, White	16,889.000	LF	5.25			
0800	628-O002	High Performance Cold Plastic Detail Stripe, Yellow	67.000	LF	5.25			
0810	628-P001	High Performance Cold Plastic Legend, White	48.000	SF	25.00			
0820	628-P002	High Performance Cold Plastic Legend, White	196.000	LF	5.25			
0830	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	81.000	SF	23.00			
0840	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	531.000	SF	25.00			
0850	630-B001	Interstate Directional Signs, Bolted Extruded Aluminum Panel	516.000	SF	29.00			
0860	630-C004	Steel U-Section Posts, 3.0 to 3.5 lb/ft	126.000	LF	9.00			
0870	630-D003	Structural Steel Beams, W6 x 9	33.000	LF	47.00			
0880	630-D004	Structural Steel Beams, W6 x 12	101.000	LF	52.00			
0890	630-D005	Structural Steel Beams, W6 x 15	42.000	LF	58.00			
0900	630-D006	Structural Steel Beams, W8 x 18	40.000	LF	64.00			
0910	630-D007	Structural Steel Beams, W8 x 21	45.000	LF	68.00			
0920	630-D009	Structural Steel Beams, W10 x 26	51.000	LF	74.00			
0930	630-E001	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	135.000	LBS	3.50			
0940	630-E002	Structural Steel Angles & Bars, 3 1/2" x 3 1/2" x 1/4" Angle	134.000	LBS	3.50			
0950	630-E003	Structural Steel Angles & Bars, 4" x 4" x 5/16" Angles	66.000	LBS	3.50			
0960	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	710.000	LBS	3.50			
0970	630-F001	Delineators, Guard Rail, White	24.000	EA	19.00			
0980	630-K002	Welded & Seamless Steel Pipe Posts, 3 1/2"	257.000	LF	47.00			

HANCOCK (23)					Colom Construction Company, Inc.			
Construction necessary to build a new Administration Building, Inspection Barn, install a new Static / Weigh-In-Motion Scale System, and make other improvements to the Weigh-In-Motion Truck Scale Facilities on I-10 (Eastbound) Near NASA, known as Federal Aid Project No. IM-0010-01(122)N / 104808301, in the County of Hancock, State of Mississippi.					\$15,015,582.30			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0990	630-K003	Welded & Seamless Steel Pipe Posts, 4"	310.000	LF	52.00			
1000	682-A021	Underground Branch Circuit, AWG 3, 3 Conductor	12,285.000	LF	9.00			
1010	682-A031	Underground Branch Circuit, AWG 6, 3 Conductor	4,605.000	LF	7.00			
1020	682-B022	Underground Branch Circuit, Jacked or Bored, AWG 3, 3 Conduc	40.000	LF	30.00			
1030	682-B031	Underground Branch Circuit, Jacked or Bored, AWG 6, 3 Conduc	40.000	LF	26.00			
1040	682-D001	Underground Pull Box	7.000	EA	1,730.00			
1050	683-A114	Lighting Assembly, High Mast, Type 60-4-S	1.000	EA	21,000.00			
1060	683-A116	Lighting Assembly, High Mast, Type 60-2-A	2.000	EA	20,000.00			
1070	683-B050	Lighting Assembly, Low Mast, Type 40-1-10-250	61.000	EA	2,100.00			
1080	683-D001	Portable Electric Power Units	1.000	EA	3,700.00			
1090	684-A003	Pole Foundation, 24" Diameter	67.000	CY	1,150.00			
1100	684-A004	Pole Foundation, 36" Diameter	17.000	CY	800.00			
1110	684-B003	Slip Casing, 24" Diameter	10.000	LF	80.00			
1120	684-B004	Slip Casing, 36" Diameter	20.000	LF	80.00			
1130	699-A001	Roadway Construction Stakes	1.000	LS	350,000.00			
1140	907-213-A001	Agricultural Limestone	60.000	TON	800.00			
1150	907-225-A001	Grassing	19.000	ACRE	1,200.00			
1160	907-230-B066	Tree Planting, Magnolia, From Right-Of-Way	25.000	EA	330.00			
1170	907-242-A006	Construction of	1.000	LS	1,361,865.00			
1180	907-242-B006	Construction of	1.000	LS	604,000.00			
1190	907-242-C001	Construction of	1.000	LS	900,000.00			
1200	907-242-PP003	Construction of	1.000	LS	25,000.00			
1210	907-258-E001	Trash Receptacle	2.000	EA	1,200.00			
1220	907-259-C001	Lighting Assembly, Flag Pole Lighting	2.000	EA	750.00			
1230	907-290-A001	Flagpole	2.000	EA	1,500.00			

HANCOCK (23)					Colom Construction Company, Inc.			
Construction necessary to build a new Administration Building, Inspection Barn, install a new Static / Weigh-In-Motion Scale System, and make other improvements to the Weigh-In-Motion Truck Scale Facilities on I-10 (Eastbound) Near NASA, known as Federal Aid Project No. IM-0010-01(122)N / 104808301, in the County of Hancock, State of Mississippi.					\$15,015,582.30			
Ref#	SM Item	Item Description	Item Qty	Units	4			
1240	907-304-F001	Size 825 Crushed Stone Base	23,866.000	TON	40.00			
1250	907-307-C003	6" Soil-Lime-Water Mixing, Class C	30,940.000	SY	2.10			
1260	907-307-D001	Lime	490.000	TON	185.00			
1270	907-403-A012	Hot Mix Asphalt, ST, 19-mm mixture	10,965.000	TON	100.00			
1280	907-501-B004	14" Plain Cement Concrete Pavement, Tine Finish	57,576.000	SY	59.00			
1290	907-601-A001	Class "B" Structural Concrete	446.000	CY	600.00			
1300	907-601-B001	Class "B" Structural Concrete, Minor Structures, Per Plans	31.000	CY	1,250.00			
1310	907-622-A001	Engineer's Field Office Building, Type 2	1.000	EA	20,000.00			
1320	907-626-C007	6" Thermoplastic Double Drop Edge Stripe, Continuous White	2,520.000	LF	1.05			
1330	907-626-F005	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	5,000.000	LF	1.05			
1340	907-628-G001	6" Cold Plastic Detail Stripe, Blue-ADA	100.000	LF	10.00			
1350	907-628-H002	Cold Plastic Legend, Blue-ADA Handicap Symbol	1.000	EA	300.00			
1360	907-308-A001	Portland Cement	262.000	TON	155.00			
1370	907-308-B001	Soil-Cement-Water Mixing, Optional Mixers, Base	30,940.000	SY	2.10			
1380	907-311-A003	Processing Lime and Fly Ash Treated Course, 6" Thick	30,940.000	SY				
1390	907-311-B001	Lime	245.000	TON				
1400	907-311-C001	Fly Ash, Class C	978.000	TON				