

ITAWAMBA (29)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Bonds Company, Inc.	APAC - Mississippi, Inc.	
Overlaying SR 23 in Treemont at SR 178, known as State Project No. MP-1023-29(005) / 303381301, in the County of Itawamba, State of Mississippi.					\$1,481,353.50	\$1,598,802.00	\$1,631,449.55	
Ref#	SM Item	Item Description	Item Qty	Units		1	2	
0010	202-B005	Removal of Asphalt Pavement, All Depths	840.000	SY		6.00	20.00	
0020	202-B038	Removal of Curb, All Types	450.000	LF		8.00	10.70	
0030	202-B076	Removal of Traffic Stripe	640.000	LF		1.75	1.80	
0040	202-B102	Removal of Guard Rail	194.000	LF		5.50	5.70	
0050	203-G003	Excess Excavation, FM, AH	110.000	CY		20.00	38.00	
0060	304-A013	Granular Material, LVM, Class 3, Group C	2,450.000	CY		20.00	10.00	
0070	406-A001	Cold Milling of Bituminous Pavement, All Depths	50,500.000	SY		1.80	1.50	
0080	606-B001	Guard Rail, Class A, Type 1	44.000	LF		25.00	27.75	
0090	606-E002	Guard Rail, Terminal End Section, Flared	4.000	EA		2,400.00	2,472.00	
0100	609-B001	Concrete Curb, Header	733.000	LF		24.00	25.65	
0110	616-A001	Concrete Median and/or Island Pavement, 4-inch	151.000	SY		37.00	39.50	
0120	618-A001	Maintenance of Traffic	1.000	LS		100,000.00	39,500.00	
0130	618-B001	Additional Construction Signs	1.000	SF		10.00	10.00	
0140	619-A1002	Temporary Traffic Stripe, Continuous White	32.000	MI		800.00	825.00	
0150	619-A2002	Temporary Traffic Stripe, Continuous Yellow	10.000	MI		1,000.00	1,030.00	
0160	619-A3006	Temporary Traffic Stripe, Skip White	5.000	MI		1,000.00	1,030.00	
0170	619-A4006	Temporary Traffic Stripe, Skip Yellow	12.000	MI		1,000.00	1,030.00	
0180	619-A5001	Temporary Traffic Stripe, Detail	91,000.000	LF		0.35	0.36	
0190	619-A6001	Temporary Traffic Stripe, Legend	3,200.000	LF		0.50	0.52	
0200	619-G5001	Free Standing Plastic Drums	15.000	EA		100.00	103.00	
0210	627-K001	Red-Clear Reflective High Performance Raised Markers	370.000	EA		5.25	5.41	
0220	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	900.000	EA		5.25	5.41	
0230	628-J002	6" High Performance Cold Plastic Traffic Stripe, Continuous	320.000	LF		6.00	6.20	
0240	628-M002	6" High Performance Cold Plastic Traffic Stripe, Continuous	320.000	LF		6.00	6.20	
0250	630-F001	Delineators, Guard Rail, White	12.000	EA		18.00	18.55	
0260	907-403-A015	Hot Mix Asphalt, ST, 9.5-mm mixture	14,700.000	TON		77.00	84.50	

ITAWAMBA (29)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Bonds Company, Inc.	APAC - Mississippi, Inc.	
Overlaying SR 23 in Treemont at SR 178, known as State Project No. MP-1023-29(005) / 303381301, in the County of Itawamba, State of Mississippi.								
Ref#	SM Item	Item Description	Item Qty	Units		1	2	
0270	907-606-PP001	Remove and Replace Guard Rail Blockouts	56.000	EA		25.00	25.75	
0280	907-626-A003	6" Thermoplastic Traffic Stripe, Skip White	2.000	MI		1,000.00	1,030.00	
0290	907-626-C004	6" Thermoplastic Edge Stripe, Continuous White	9.000	MI		1,800.00	1,855.00	
0300	907-626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	3.000	MI		1,000.00	1,030.00	
0310	907-626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	3.000	MI		2,300.00	2,370.00	
0320	907-626-F004	6" Thermoplastic Edge Stripe, Continuous Yellow	2.000	MI		1,800.00	1,855.00	
0330	907-626-G004	Thermoplastic Detail Stripe, White	13,350.000	LF		1.25	1.29	
0340	907-626-G005	Thermoplastic Detail Stripe, Yellow	22,900.000	LF		1.25	1.29	
0350	907-626-H004	Thermoplastic Legend, White	1,700.000	LF		2.00	2.06	