

CLARKE (12)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Dunn Roadbuilders, LLC	Joe McGee Construction Company, Inc.	APAC - Mississippi, Inc.
Reconstruction of SR 513 at the junction of SR 513 and SR 145 in Quitman, known as Federal Aid Project No. HSIP-0002-02(043) / 101614301, in the County of Clarke, State of Mississippi.					\$1,394,286.71	\$1,269,797.96	\$1,327,090.96	\$1,360,206.71
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS		20,000.00	108,650.00	18,650.00
0020	202-B005	Removal of Asphalt Pavement, All Depths	1,416.000	SY		4.75	7.50	8.00
0030	202-B064	Removal of Pipe, 8" And Above	188.000	LF		14.20	10.00	18.00
0040	202-B076	Removal of Traffic Stripe	6,872.000	LF		2.00	1.40	2.00
0050	203-A003	Unclassified Excavation, FM, AH	9,314.000	CY		7.85	4.50	9.50
0060	203-EX038	Borrow Excavation, AH, FME, Class B7-6	4,800.000	CY		14.00	7.00	18.00
0070	203-G003	Excess Excavation, FM, AH	6,912.000	CY		7.60	4.50	12.60
0080	206-A001	Structure Excavation	39.000	CY		11.50	27.00	16.00
0090	209-A004	Geotextile Stabilization, Type V, Non-Woven	5,078.000	SY		1.95	2.00	1.70
0100	211-A001	Topsoil for Slope Treatment, From Right-of-Way	34,145.000	SY		0.35	0.70	0.90
0110	212-A001	Light Ground Preparation	17,073.000	SY		0.02	0.02	0.02
0120	212-B001	Standard Ground Preparation	34,145.000	SY		0.07	0.07	0.07
0130	213-B001	Combination Fertilizer, 13-13-13	4.000	TON		750.00	750.00	750.00
0140	213-C001	Superphosphate	4.000	TON		800.00	800.00	800.00
0150	214-A001	Seeding, Bahiagrass	167.000	LBS		5.00	5.00	5.00
0160	214-A002	Seeding, Bermudagrass	134.000	LBS		8.00	8.00	8.00
0170	214-A003	Seeding, Tall Fescue	50.000	LBS		3.00	3.00	3.00
0180	214-A004	Seeding, Crimson Clover	67.000	LBS		3.00	3.00	3.00
0190	214-A014	Seeding, Browntop Millet	67.000	LBS		2.00	2.00	2.00
0200	214-A015	Seeding, Oats	300.000	LBS		2.00	2.00	2.00
0210	214-A017	Seeding, Rye Grass	83.000	LBS		2.00	2.00	2.00
0220	215-A001	Vegetative Materials for Mulch	17.000	TON		185.00	185.00	185.00
0230	216-A001	Solid Sodding	5,000.000	SY		4.00	4.00	4.00
0240	217-A001	Ditch Liner	353.000	SY		1.75	1.75	1.75
0250	219-A001	Watering	100.000	KGAL		20.00	20.00	20.00
0260	220-A001	Insect Pest Control	4.000	ACRE		30.00	30.00	30.00

CLARKE (12)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Dunn Roadbuilders, LLC	Joe McGee Construction Company, Inc.	APAC - Mississippi, Inc.
Reconstruction of SR 513 at the junction of SR 513 and SR 145 in Quitman, known as Federal Aid Project No. HSIP-0002-02(043) / 101614301, in the County of Clarke, State of Mississippi.					\$1,394,286.71	\$1,269,797.96	\$1,327,090.96	\$1,360,206.71
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0270	221-A001	Portland Cement Concrete Paved Ditch	20.000	CY		350.00	350.00	410.00
0280	223-A001	Mowing	1.000	ACRE		40.00	40.00	40.00
0290	304-A029	Granular Material, LVM, Class 6, Group D	3,297.000	CY		18.35	16.35	27.35
0300	408-A003	Asphalt for Prime Coat, Cut-Back MC-70 or Emulsified EA-1	397.000	GAL		2.80	5.00	6.50
0310	602-A001	Reinforcing Steel	372.000	LBS		1.75	4.75	2.00
0320	603-CA002	18" Reinforced Concrete Pipe, Class III	96.000	LF		45.20	32.80	55.00
0330	603-CA003	24" Reinforced Concrete Pipe, Class III	168.000	LF		59.85	46.00	83.00
0340	603-CB001	18" Reinforced Concrete End Section	1.000	EA		1,008.00	736.60	1,000.00
0350	603-CB002	24" Reinforced Concrete End Section	4.000	EA		1,100.00	846.80	1,225.00
0360	604-A001	Castings	79.000	LBS		5.00	7.00	3.00
0370	609-D002	Combination Concrete Curb and Gutter Type 2	2,056.000	LF		14.50	14.50	14.50
0380	616-A001	Concrete Median and/or Island Pavement, 4-inch	222.000	SY		28.50	28.50	28.50
0390	616-A003	Concrete Median and/or Island Pavement, 10-inch	25.000	SY		85.00	85.00	85.00
0400	618-A001	Maintenance of Traffic	1.000	LS		50,000.00	57,750.00	22,000.00
0410	619-A1007	Temporary Traffic Stripe, Continuous White, Type 1 Tape	5,106.000	LF		1.00	2.50	1.00
0420	619-A2007	Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape	5,106.000	LF		1.00	2.50	1.00
0430	619-A4001	Temporary Traffic Stripe, Skip Yellow	1,400.000	LF		1.00	2.50	1.00
0440	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	224.000	SF		37.00	8.00	8.00
0450	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	268.000	SF		23.00	9.00	9.00
0460	619-G4001	Barricades, Type III, Single Faced	368.000	LF		28.00	16.00	16.00
0470	619-G4005	Barricades, Type III, Double Faced	36.000	LF		78.00	20.00	20.00
0480	619-G5001	Free Standing Plastic Drums	288.000	EA		73.00	70.00	70.00
0490	620-A001	Mobilization	1.000	LS		50,000.00	59,500.00	72,750.00
0500	627-K001	Red-Clear Reflective High Performance Raised Markers	16.000	EA		5.00	12.00	5.00
0510	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	233.000	EA		5.00	12.00	5.00
0520	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	182.000	SF		22.50	22.50	22.50

CLARKE (12)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Dunn Roadbuilders, LLC	Joe McGee Construction Company, Inc.	APAC - Mississippi, Inc.
Reconstruction of SR 513 at the junction of SR 513 and SR 145 in Quitman, known as Federal Aid Project No. HSIP-0002-02(043) / 101614301, in the County of Clarke, State of Mississippi.					\$1,394,286.71	\$1,269,797.96	\$1,327,090.96	\$1,360,206.71
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0530	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	64.000	SF		24.00	24.00	24.00
0540	630-B001	Interstate Directional Signs, Bolted Extruded Aluminum Panel	90.000	SF		27.50	27.50	27.50
0550	630-C004	Steel U-Section Posts, 3.0 to 3.5 lb/ft	333.000	LF		10.50	10.50	10.50
0560	630-D003	Structural Steel Beams, W6 x 9	95.000	LF		45.00	45.00	45.00
0570	630-E001	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	106.000	LBS		4.50	4.50	4.50
0580	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	77.000	LBS		4.50	4.50	4.50
0590	630-K003	Welded & Seamless Steel Pipe Posts, 4"	61.000	LF		55.00	55.00	55.00
0600	699-A001	Roadway Construction Stakes	1.000	LS		58,000.00	57,076.00	60,000.00
0610	815-A009	Loose Riprap, Size 300	1,188.000	TON		48.00	54.00	63.70
0620	815-E001	Geotextile under Riprap	1,467.000	SY		3.25	3.50	1.00
0630	907-213-A001	Agricultural Limestone	20.000	TON		81.00	75.00	75.00
0640	907-304-H001	Size 825 Crushed Stone Base, LVM	1,727.000	CY		66.75	66.75	55.00
0650	907-403-A006	Hot Mix Asphalt, MT, 12.5-mm mixture	1,405.000	TON		88.00	88.00	88.00
0660	907-403-A007	Hot Mix Asphalt, MT, 19-mm mixture	2,447.000	TON		80.00	80.00	75.50
0670	907-403-A010	Hot Mix Asphalt, MT, 9.5-mm mixture	702.000	TON		97.00	97.00	92.50
0680	907-601-B003	Class "B" Structural Concrete, Minor Structures	7.000	CY		1,400.00	900.00	1,700.00
0690	907-603-ALT01	18" Type A Alternate Pipe	156.000	LF		40.00	21.00	80.00
0700	907-617-A001	Right-of-Way Marker	25.000	EA		330.00	175.00	81.50
0710	907-626-B003	6" Thermoplastic Traffic Stripe, Continuous White	322.000	LF		1.00	4.00	1.00
0720	907-626-C007	6" Thermoplastic Double Drop Edge Stripe, Continuous White	3,279.000	LF		1.00	4.00	1.00
0730	907-626-E003	6" Thermoplastic Traffic Stripe, Continuous Yellow	5,416.000	LF		1.00	2.50	1.00
0740	907-626-G004	Thermoplastic Detail Stripe, White	3,993.000	LF		1.00	4.00	1.00
0750	907-626-G005	Thermoplastic Detail Stripe, Yellow	1,908.000	LF		1.00	4.00	1.00
0760	907-626-H004	Thermoplastic Legend, White	303.000	LF		1.00	4.00	1.00
0770	907-626-H005	Thermoplastic Legend, White	116.000	SF		5.00	4.00	5.00

CLARKE (12)					Bush Construction Company, Inc.			
Reconstruction of SR 513 at the junction of SR 513 and SR 145 in Quitman, known as Federal Aid Project No. HSIP-0002-02(043) / 101614301, in the County of Clarke, State of Mississippi.					\$1,420,301.44			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0010	201-A001	Clearing and Grubbing	1.000	LS	26,304.31			
0020	202-B005	Removal of Asphalt Pavement, All Depths	1,416.000	SY	5.25			
0030	202-B064	Removal of Pipe, 8" And Above	188.000	LF	4.72			
0040	202-B076	Removal of Traffic Stripe	6,872.000	LF	2.26			
0050	203-A003	Unclassified Excavation, FM, AH	9,314.000	CY	4.16			
0060	203-EX038	Borrow Excavation, AH, FME, Class B7-6	4,800.000	CY	9.89			
0070	203-G003	Excess Excavation, FM, AH	6,912.000	CY	7.41			
0080	206-A001	Structure Excavation	39.000	CY	9.51			
0090	209-A004	Geotextile Stabilization, Type V, Non-Woven	5,078.000	SY	1.88			
0100	211-A001	Topsoil for Slope Treatment, From Right-of-Way	34,145.000	SY	0.62			
0110	212-A001	Light Ground Preparation	17,073.000	SY	0.07			
0120	212-B001	Standard Ground Preparation	34,145.000	SY	0.17			
0130	213-B001	Combination Fertilizer, 13-13-13	4.000	TON	1,129.77			
0140	213-C001	Superphosphate	4.000	TON	903.81			
0150	214-A001	Seeding, Bahiagrass	167.000	LBS	11.30			
0160	214-A002	Seeding, Bermudagrass	134.000	LBS	11.30			
0170	214-A003	Seeding, Tall Fescue	50.000	LBS	5.65			
0180	214-A004	Seeding, Crimson Clover	67.000	LBS	5.65			
0190	214-A014	Seeding, Browntop Millet	67.000	LBS	4.52			
0200	214-A015	Seeding, Oats	300.000	LBS	4.52			
0210	214-A017	Seeding, Rye Grass	83.000	LBS	4.52			
0220	215-A001	Vegetative Materials for Mulch	17.000	TON	282.44			
0230	216-A001	Solid Sodding	5,000.000	SY	6.78			
0240	217-A001	Ditch Liner	353.000	SY	2.26			
0250	219-A001	Watering	100.000	KGAL	20.00			
0260	220-A001	Insect Pest Control	4.000	ACRE	30.00			

CLARKE (12)					Bush Construction Company, Inc.			
Reconstruction of SR 513 at the junction of SR 513 and SR 145 in Quitman, known as Federal Aid Project No. HSIP-0002-02(043) / 101614301, in the County of Clarke, State of Mississippi.					\$1,420,301.44			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0270	221-A001	Portland Cement Concrete Paved Ditch	20.000	CY	553.78			
0280	223-A001	Mowing	1.000	ACRE	40.00			
0290	304-A029	Granular Material, LVM, Class 6, Group D	3,297.000	CY	13.50			
0300	408-A003	Asphalt for Prime Coat, Cut-Back MC-70 or Emulsified EA-1	397.000	GAL	4.80			
0310	602-A001	Reinforcing Steel	372.000	LBS	2.27			
0320	603-CA002	18" Reinforced Concrete Pipe, Class III	96.000	LF	49.03			
0330	603-CA003	24" Reinforced Concrete Pipe, Class III	168.000	LF	61.03			
0340	603-CB001	18" Reinforced Concrete End Section	1.000	EA	759.10			
0350	603-CB002	24" Reinforced Concrete End Section	4.000	EA	817.89			
0360	604-A001	Castings	79.000	LBS	2.86			
0370	609-D002	Combination Concrete Curb and Gutter Type 2	2,056.000	LF	16.27			
0380	616-A001	Concrete Median and/or Island Pavement, 4-inch	222.000	SY	36.15			
0390	616-A003	Concrete Median and/or Island Pavement, 10-inch	25.000	SY	74.56			
0400	618-A001	Maintenance of Traffic	1.000	LS	24,621.75			
0410	619-A1007	Temporary Traffic Stripe, Continuous White, Type 1 Tape	5,106.000	LF	1.13			
0420	619-A2007	Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape	5,106.000	LF	1.13			
0430	619-A4001	Temporary Traffic Stripe, Skip Yellow	1,400.000	LF	1.13			
0440	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	224.000	SF	18.02			
0450	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	268.000	SF	18.11			
0460	619-G4001	Barricades, Type III, Single Faced	368.000	LF	27.52			
0470	619-G4005	Barricades, Type III, Double Faced	36.000	LF	32.47			
0480	619-G5001	Free Standing Plastic Drums	288.000	EA	112.52			
0490	620-A001	Mobilization	1.000	LS	90,550.00			
0500	627-K001	Red-Clear Reflective High Performance Raised Markers	16.000	EA	5.65			
0510	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	233.000	EA	5.65			
0520	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	182.000	SF	25.42			

CLARKE (12)					Bush Construction Company, Inc.			
Reconstruction of SR 513 at the junction of SR 513 and SR 145 in Quitman, known as Federal Aid Project No. HSIP-0002-02(043) / 101614301, in the County of Clarke, State of Mississippi.					\$1,420,301.44			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0530	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	64.000	SF	27.11			
0540	630-B001	Interstate Directional Signs, Bolted Extruded Aluminum Panel	90.000	SF	31.07			
0550	630-C004	Steel U-Section Posts, 3.0 to 3.5 lb/ft	333.000	LF	11.86			
0560	630-D003	Structural Steel Beams, W6 x 9	95.000	LF	50.84			
0570	630-E001	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	106.000	LBS	5.08			
0580	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	77.000	LBS	5.08			
0590	630-K003	Welded & Seamless Steel Pipe Posts, 4"	61.000	LF	62.14			
0600	699-A001	Roadway Construction Stakes	1.000	LS	52,534.10			
0610	815-A009	Loose Riprap, Size 300	1,188.000	TON	53.05			
0620	815-E001	Geotextile under Riprap	1,467.000	SY	2.86			
0630	907-213-A001	Agricultural Limestone	20.000	TON	90.38			
0640	907-304-H001	Size 825 Crushed Stone Base, LVM	1,727.000	CY	88.78			
0650	907-403-A006	Hot Mix Asphalt, MT, 12.5-mm mixture	1,405.000	TON	108.46			
0660	907-403-A007	Hot Mix Asphalt, MT, 19-mm mixture	2,447.000	TON	108.40			
0670	907-403-A010	Hot Mix Asphalt, MT, 9.5-mm mixture	702.000	TON	118.91			
0680	907-601-B003	Class "B" Structural Concrete, Minor Structures	7.000	CY	1,515.39			
0690	907-603-ALT01	18" Type A Alternate Pipe	156.000	LF	28.84			
0700	907-617-A001	Right-of-Way Marker	25.000	EA	163.57			
0710	907-626-B003	6" Thermoplastic Traffic Stripe, Continuous White	322.000	LF	2.26			
0720	907-626-C007	6" Thermoplastic Double Drop Edge Stripe, Continuous White	3,279.000	LF	1.13			
0730	907-626-E003	6" Thermoplastic Traffic Stripe, Continuous Yellow	5,416.000	LF	1.13			
0740	907-626-G004	Thermoplastic Detail Stripe, White	3,993.000	LF	1.13			
0750	907-626-G005	Thermoplastic Detail Stripe, Yellow	1,908.000	LF	1.13			
0760	907-626-H004	Thermoplastic Legend, White	303.000	LF	1.13			
0770	907-626-H005	Thermoplastic Legend, White	116.000	SF	1.13			