

| NESHOPA (50) | | | | | MISSISSIPPI DEPARTMENT OF TRANSPORTATION | N. L. Carson Construction Company, Inc. | Joe McGee Construction Company, Inc. | Key, LLC |
|---|-----------|---|------------|-------|--|---|--|----------------|
| Construction necessary to replace the bridge on SR 15, between SR 19 and the Winston County Line, known as Federal Aid Project No. BR-0022-02(049) / 104632301, in the County of Neshoba, State of Mississippi. | | | | | \$3,079,252.17 | \$2,382,981.36 | \$2,677,024.84 | \$2,718,448.60 |
| Ref# | SM Item | Item Description | Item Qty | Units | | 1 | 2 | 3 |
| 0010 | 201-A001 | Clearing and Grubbing | 1.000 | LS | | 50,000.00 | 202,500.00 | 50,000.00 |
| 0020 | 202-B005 | Removal of Asphalt Pavement, All Depths | 7,580.000 | SY | | 2.50 | 4.40 | 3.50 |
| 0030 | 202-B008 | Removal of Box Culvert | 1.000 | EA | | 1,000.00 | 2,250.00 | 3,000.00 |
| 0040 | 202-B009 | Removal of Bridge | 1.000 | EA | | 10,000.00 | 25,000.00 | 6,500.00 |
| 0050 | 202-B076 | Removal of Traffic Stripe | 1,675.000 | LF | | 1.75 | 1.75 | 1.75 |
| 0060 | 202-B093 | Removal of Curb & Gutter, All Types | 83.000 | LF | | 3.00 | 3.25 | 14.00 |
| 0070 | 203-A003 | Unclassified Excavation, FM, AH | 4,260.000 | CY | | 3.00 | 3.25 | 2.00 |
| 0080 | 203-D001 | Muck Excavation, FM | 1,000.000 | CY | | 2.00 | 7.00 | 10.00 |
| 0090 | 203-EX035 | Borrow Excavation, AH, FME, Class B9-6 | 88,648.000 | CY | | 5.00 | 5.50 | 5.00 |
| 0100 | 203-G003 | Excess Excavation, FM, AH | 3,911.000 | CY | | 3.00 | 3.50 | 3.00 |
| 0110 | 206-A001 | Structure Excavation | 72.000 | CY | | 4.00 | 7.00 | 25.00 |
| 0120 | 212-A001 | Light Ground Preparation | 27,712.000 | SY | | 0.01 | 0.02 | 0.01 |
| 0130 | 212-B001 | Standard Ground Preparation | 55,424.000 | SY | | 0.07 | 0.05 | 0.07 |
| 0140 | 213-B001 | Combination Fertilizer, 13-13-13 | 7.000 | TON | | 1,000.00 | 750.00 | 1,000.00 |
| 0150 | 213-C001 | Superphosphate | 6.000 | TON | | 800.00 | 500.00 | 800.00 |
| 0160 | 214-A002 | Seeding, Bermudagrass | 229.000 | LBS | | 12.00 | 6.00 | 12.00 |
| 0170 | 214-A003 | Seeding, Tall Fescue | 115.000 | LBS | | 7.00 | 2.00 | 7.00 |
| 0180 | 214-A004 | Seeding, Crimson Clover | 115.000 | LBS | | 4.00 | 4.00 | 4.00 |
| 0190 | 214-A014 | Seeding, Browntop Millet | 115.000 | LBS | | 1.00 | 2.00 | 1.00 |
| 0200 | 214-A015 | Seeding, Oats | 515.000 | LBS | | 1.00 | 2.00 | 1.00 |
| 0210 | 214-A017 | Seeding, Rye Grass | 143.000 | LBS | | 1.00 | 2.00 | 1.00 |
| 0220 | 215-A001 | Vegetative Materials for Mulch | 29.000 | TON | | 210.00 | 185.00 | 210.00 |
| 0230 | 216-A001 | Solid Sodding | 45.000 | SY | | 7.00 | 10.00 | 7.00 |
| 0240 | 219-A001 | Watering | 1.000 | KGAL | | 20.00 | 20.00 | 20.00 |
| 0250 | 220-A001 | Insect Pest Control | 6.000 | ACRE | | 30.00 | 30.00 | 30.00 |
| 0260 | 221-A001 | Portland Cement Concrete Paved Ditch | 5.000 | CY | | 325.00 | 500.00 | 650.00 |

| NESHOPA (50) | | | | | MISSISSIPPI DEPARTMENT OF TRANSPORTATION | N. L. Carson Construction Company, Inc. | Joe McGee Construction Company, Inc. | Key, LLC |
|---|-----------|--|------------|-------|--|---|--|----------------|
| Construction necessary to replace the bridge on SR 15, between SR 19 and the Winston County Line, known as Federal Aid Project No. BR-0022-02(049) / 104632301, in the County of Neshoba, State of Mississippi. | | | | | \$3,079,252.17 | \$2,382,981.36 | \$2,677,024.84 | \$2,718,448.60 |
| Ref# | SM Item | Item Description | Item Qty | Units | | 1 | 2 | 3 |
| 0270 | 223-A001 | Mowing | 1.000 | ACRE | | 40.00 | 40.00 | 40.00 |
| 0280 | 234-A001 | Temporary Silt Fence | 6,144.000 | LF | | 3.00 | 3.75 | 4.50 |
| 0290 | 235-A001 | Temporary Erosion Checks | 34.000 | BALE | | 5.00 | 10.00 | 10.00 |
| 0300 | 236-A004 | Silt Basin, Type D | 1.000 | EA | | 1,200.00 | 1,000.00 | 5,000.00 |
| 0310 | 239-A001 | Temporary Slope Drains | 36.000 | LF | | 6.00 | 5.00 | 13.00 |
| 0320 | 406-A001 | Cold Milling of Bituminous Pavement, All Depths | 1,500.000 | SY | | 6.59 | 9.85 | 4.50 |
| 0330 | 501-E001 | Expansion Joints, Without Dowels | 66.000 | LF | | 9.00 | 8.00 | 9.00 |
| 0340 | 501-K001 | Transverse Grooving | 99.000 | SY | | 2.74 | 2.50 | 2.50 |
| 0350 | 502-A001 | Reinforced Cement Concrete Bridge End Pavement | 105.000 | SY | | 85.00 | 96.00 | 155.00 |
| 0360 | 603-CA005 | 36" Reinforced Concrete Pipe, Class III | 188.000 | LF | | 67.59 | 84.00 | 90.00 |
| 0370 | 603-CB004 | 36" Reinforced Concrete End Section | 4.000 | EA | | 1,044.30 | 1,465.00 | 1,700.00 |
| 0380 | 606-B001 | Guard Rail, Class A, Type 1 | 500.000 | LF | | 21.00 | 21.00 | 21.00 |
| 0390 | 606-D012 | Guard Rail, Bridge End Section, Type I | 4.000 | EA | | 2,250.00 | 2,250.00 | 2,250.00 |
| 0400 | 606-E001 | Guard Rail, Terminal End Section | 4.000 | EA | | 2,100.00 | 2,100.00 | 2,100.00 |
| 0410 | 609-D002 | Combination Concrete Curb and Gutter Type 2 | 599.000 | LF | | 16.00 | 15.85 | 16.80 |
| 0420 | 616-A001 | Concrete Median and/or Island Pavement, 4-inch | 125.000 | SY | | 21.00 | 29.00 | 23.50 |
| 0430 | 616-A003 | Concrete Median and/or Island Pavement, 10-inch | 5.000 | SY | | 62.00 | 110.00 | 63.75 |
| 0440 | 618-A001 | Maintenance of Traffic | 1.000 | LS | | 12,000.00 | 20,000.00 | 40,000.00 |
| 0450 | 619-A1001 | Temporary Traffic Stripe, Continuous White | 12,925.000 | LF | | 0.30 | 0.30 | 0.30 |
| 0460 | 619-A2001 | Temporary Traffic Stripe, Continuous Yellow | 11,540.000 | LF | | 0.30 | 0.30 | 0.30 |
| 0470 | 619-A4001 | Temporary Traffic Stripe, Skip Yellow | 330.000 | LF | | 1.00 | 1.00 | 1.00 |
| 0480 | 619-A6001 | Temporary Traffic Stripe, Legend | 34.000 | LF | | 5.00 | 5.00 | 5.00 |
| 0490 | 619-D1001 | Standard Roadside Construction Signs, Less than 10 Square Fe | 116.000 | SF | | 8.50 | 8.50 | 7.00 |
| 0500 | 619-D2001 | Standard Roadside Construction Signs, 10 Square Feet or More | 148.000 | SF | | 8.50 | 8.50 | 7.00 |
| 0510 | 619-G4001 | Barricades, Type III, Single Faced | 200.000 | LF | | 22.00 | 22.00 | 13.00 |
| 0520 | 619-G4005 | Barricades, Type III, Double Faced | 48.000 | LF | | 22.00 | 22.00 | 16.00 |

| NESHOPA (50) | | | | | MISSISSIPPI DEPARTMENT OF TRANSPORTATION | N. L. Carson Construction Company, Inc. | Joe McGee Construction Company, Inc. | Key, LLC |
|---|---------------|---|------------|-------|--|---|--|----------------|
| Construction necessary to replace the bridge on SR 15, between SR 19 and the Winston County Line, known as Federal Aid Project No. BR-0022-02(049) / 104632301, in the County of Neshoba, State of Mississippi. | | | | | \$3,079,252.17 | \$2,382,981.36 | \$2,677,024.84 | \$2,718,448.60 |
| Ref# | SM Item | Item Description | Item Qty | Units | | 1 | 2 | 3 |
| 0530 | 619-G5001 | Free Standing Plastic Drums | 172.000 | EA | | 48.50 | 48.50 | 30.00 |
| 0540 | 620-A001 | Mobilization | 1.000 | LS | | 108,500.00 | 76,500.00 | 120,000.00 |
| 0550 | 627-K001 | Red-Clear Reflective High Performance Raised Markers | 31.000 | EA | | 10.00 | 10.00 | 10.00 |
| 0560 | 627-L001 | Two-Way Yellow Reflective High Performance Raised Markers | 858.000 | EA | | 6.00 | 6.00 | 6.00 |
| 0570 | 628-B001 | 6" Cold Plastic Traffic Stripe, Continuous White | 230.000 | LF | | 6.00 | 6.00 | 8.00 |
| 0580 | 628-D001 | 6" Cold Plastic Traffic Stripe, Skip Yellow | 230.000 | LF | | 8.00 | 8.00 | 6.00 |
| 0590 | 628-E002 | 6" Cold Plastic Traffic Stripe, Continuous Yellow | 230.000 | LF | | 6.00 | 6.00 | 6.00 |
| 0600 | 630-A001 | Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness | 36.000 | SF | | 35.00 | 35.00 | 35.00 |
| 0610 | 630-A002 | Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness | 48.000 | SF | | 35.00 | 35.00 | 35.00 |
| 0620 | 630-C003 | Steel U-Section Posts, 3.0 lb/ft | 79.000 | LF | | 11.00 | 11.00 | 11.00 |
| 0630 | 630-E004 | Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar | 41.000 | LBS | | 5.50 | 5.50 | 5.50 |
| 0640 | 630-F001 | Delineators, Guard Rail, White | 14.000 | EA | | 18.00 | 18.00 | 18.00 |
| 0650 | 630-F002 | Delineators, Guard Rail, Yellow | 14.000 | EA | | 18.00 | 18.00 | 18.00 |
| 0660 | 630-K003 | Welded & Seamless Steel Pipe Posts, 4" | 31.000 | LF | | 65.00 | 65.00 | 65.00 |
| 0670 | 699-A001 | Roadway Construction Stakes | 1.000 | LS | | 48,168.75 | 42,322.50 | 60,000.00 |
| 0680 | 815-A009 | Loose Riprap, Size 300 | 200.000 | TON | | 51.60 | 45.00 | 65.00 |
| 0690 | 815-F002 | Sediment Control Stone | 5.000 | TON | | 71.70 | 120.00 | 300.00 |
| 0700 | 907-213-A001 | Agricultural Limestone | 23.000 | TON | | 75.00 | 65.00 | 75.00 |
| 0710 | 907-304-B001 | Granular Material, Class 5, Group C | 4,257.000 | TON | | 21.50 | 22.50 | 35.00 |
| 0720 | 907-304-C005 | Granular Material, AEA, Class 9, Group C | 4,430.000 | CY | | 5.75 | 11.50 | 12.00 |
| 0730 | 907-307-A002 | 6" Soil-Lime-Water Mixing, Class A | 12,747.000 | SY | | 2.00 | 2.00 | 2.00 |
| 0740 | 907-307-D001 | Lime | 173.000 | TON | | 155.00 | 155.00 | 155.00 |
| 0750 | 907-403-A006 | Hot Mix Asphalt, MT, 12.5-mm mixture | 1,910.000 | TON | | 90.00 | 90.00 | 90.00 |
| 0760 | 907-403-A007 | Hot Mix Asphalt, MT, 19-mm mixture | 4,765.000 | TON | | 76.14 | 76.14 | 76.00 |
| 0770 | 907-601-B003 | Class "B" Structural Concrete, Minor Structures | 1.000 | CY | | 750.00 | 1,500.00 | 2,300.00 |
| 0780 | 907-603-ALT01 | 18" Type A Alternate Pipe | 44.000 | LF | | 21.15 | 16.15 | 30.00 |

| NESHOPA (50) | | | | | MISSISSIPPI DEPARTMENT OF TRANSPORTATION | N. L. Carson Construction Company, Inc. | Joe McGee Construction Company, Inc. | Key, LLC |
|---|--------------|--|------------|-------|--|---|--|----------------|
| Construction necessary to replace the bridge on SR 15, between SR 19 and the Winston County Line, known as Federal Aid Project No. BR-0022-02(049) / 104632301, in the County of Neshoba, State of Mississippi. | | | | | \$3,079,252.17 | \$2,382,981.36 | \$2,677,024.84 | \$2,718,448.60 |
| Ref# | SM Item | Item Description | Item Qty | Units | | 1 | 2 | 3 |
| 0790 | 907-617-A001 | Right-of-Way Marker | 15.000 | EA | | 117.00 | 237.00 | 150.00 |
| 0800 | 907-626-B003 | 6" Thermoplastic Traffic Stripe, Continuous White | 620.000 | LF | | 0.50 | 0.50 | 0.50 |
| 0810 | 907-626-C007 | 6" Thermoplastic Double Drop Edge Stripe, Continuous White | 7,620.000 | LF | | 0.75 | 0.75 | 0.75 |
| 0820 | 907-626-E003 | 6" Thermoplastic Traffic Stripe, Continuous Yellow | 3,560.000 | LF | | 0.60 | 0.60 | 0.60 |
| 0830 | 907-626-G004 | Thermoplastic Detail Stripe, White | 1,650.000 | LF | | 1.00 | 1.00 | 1.00 |
| 0840 | 907-626-G005 | Thermoplastic Detail Stripe, Yellow | 7,300.000 | LF | | 0.75 | 0.75 | 0.75 |
| 0850 | 907-626-H004 | Thermoplastic Legend, White | 24.000 | LF | | 2.00 | 2.00 | 2.00 |
| 0860 | 907-626-H005 | Thermoplastic Legend, White | 192.000 | SF | | 6.00 | 6.00 | 6.00 |
| 0870 | 907-308-A001 | Portland Cement | 165.000 | TON | | 145.00 | 145.00 | 145.00 |
| 0880 | 907-308-B001 | Soil-Cement-Water Mixing, Optional Mixers, Base | 14,164.000 | SY | | 2.00 | 2.00 | 2.00 |
| 0890 | 907-311-A003 | Processing Lime and Fly Ash Treated Course, 6" Thick | 14,164.000 | SY | | | | |
| 0900 | 907-311-B001 | Lime | 119.000 | TON | | | | |
| 0910 | 907-311-C002 | Fly Ash, Class C or F | 475.000 | TON | | | | |
| 0920 | 501-K001 | Transverse Grooving | 1,022.000 | SY | | 2.74 | 2.50 | 2.50 |
| 0930 | 803-B001 | Conventional Static Loading Test | 1.000 | EA | | 5,000.00 | 5,000.00 | 5,000.00 |
| 0940 | 803-D002 | HP 12 x 53 Steel Piling | 1,320.000 | LF | | 33.17 | 37.00 | 40.00 |
| 0950 | 803-D003 | HP 14 x 73 Steel Piling | 1,625.000 | LF | | 41.18 | 47.75 | 55.00 |
| 0960 | 803-F009 | 20" Pre-Formed Pile Hole | 1,180.000 | LF | | 15.00 | 0.10 | 9.00 |
| 0970 | 803-I001 | PDA Test Pile | 2.000 | EA | | 5,300.00 | 6,000.00 | 9,000.00 |
| 0980 | 803-J001 | Pile Restrike | 2.000 | EA | | 500.00 | 725.00 | 500.00 |
| 0990 | 805-A001 | Reinforcement | 79,032.000 | LBS | | 0.64 | 0.65 | 0.85 |
| 1000 | 813-A001 | Concrete Railing | 464.000 | LF | | 43.65 | 46.50 | 42.50 |
| 1010 | 815-A009 | Loose Riprap, Size 300 | 367.000 | TON | | 51.60 | 45.00 | 65.00 |
| 1020 | 815-E001 | Geotextile under Riprap | 302.000 | SY | | 2.30 | 3.00 | 2.70 |
| 1030 | 907-804-A001 | Bridge Concrete, Class AA | 248.000 | CY | | 475.00 | 500.00 | 550.00 |
| 1040 | 907-804-A012 | Bridge Concrete, Class BD | 265.000 | CY | | 660.00 | 850.00 | 950.00 |

| | | | | | | | | |
|---|--------------|--|----------|-------|--|---|--|----------------|
| NESHOPA (50) | | | | | MISSISSIPPI DEPARTMENT OF TRANSPORTATION | N. L. Carson Construction Company, Inc. | Joe McGee Construction Company, Inc. | Key, LLC |
| Construction necessary to replace the bridge on SR 15, between SR 19 and the Winston County Line, known as Federal Aid Project No. BR-0022-02(049) / 104632301, in the County of Neshoba, State of Mississippi. | | | | | \$3,079,252.17 | \$2,382,981.36 | \$2,677,024.84 | \$2,718,448.60 |
| Ref# | SM Item | Item Description | Item Qty | Units | | 1 | 2 | 3 |
| 1050 | 907-804-C019 | 60' Prestressed Concrete Beam, Type II+2 | 717.000 | LF | | 105.00 | 75.00 | 100.00 |
| 1060 | 907-804-C150 | 110' Prestressed Concrete Beam, Type IV | 768.000 | LF | | 129.94 | 145.00 | 150.00 |