

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) further propose to execute the attached contract agreement (Section 902) as soon as the work is awarded to me (us), and to begin and complete the work within the time limit(s) provided for in the Specifications and Advertisement. I (We) also propose to execute the attached contract bond (Section 903) in an amount not less than one hundred (100) percent of the total of my (our) part, but also to guarantee the excellence of both workmanship and materials until the work is finally accepted.

I (We) enclose a certified check, cashier's check or bid bond for **five percent (5%) of total bid** and hereby agree that in case of my (our) failure to execute the contract and furnish bond within Ten (10) days after notice of award, the amount of this check (bid bond) will be forfeited to the State of Mississippi as liquidated damages arising out of my (our) failure to execute the contract as proposed. It is understood that in case I am (we are) not awarded the work, the check will be returned as provided in the Specifications.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. 1 DATED 5/15/2009 ADDENDUM NO. DATED
 ADDENDUM NO. DATED ADDENDUM NO. DATED

Number	Description
1	Bidsheets, replace same; Plan Sheets Revised or Added, 2, 5, 11, 14, 22, 481, & 508; Amendment EBS Download Required.

TOTAL ADDENDA: 1
 (Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

 Contractor

BY _____
 Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

_____ President	_____ Address
_____ Secretary	_____ Address
_____ Treasurer	_____ Address

The following is my (our) itemized proposal.

Revised 09/21/2005

BR-0031-01(018) / 103318302

DeSoto County(ies)

Replacing 4 bridges on MS Hwy. 305, known as Federal Aid Project No. BR-0031-01(018) / 103318302, in the County of DeSoto, State of Mississippi.

I (We) agree to complete the entire project within the specified contract time.

***** SPECIAL NOTICE TO BIDDERS *****

**BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED.
 BIDS WILL NOT BE CONSIDERED UNLESS THE BID CERTIFICATION LOCATED AT THE END OF THE BID SHEETS IS SIGNED**

*****BID SCHEDULE*****

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Item Amount	
						Dollar	Ct	Dollar	Ct
Roadway Items									
0010	201-A001		1	Lump Sum	Clearing and Grubbing	XXXXXXXX	XXX		
0020	201-B001		1	Acre	Clearing and Grubbing				
0030	202-A001		1	Lump Sum	Removal of Obstructions	XXXXXXXX	XXX		
0040	202-B005		20,311	Square Yard	Removal of Asphalt Pavement, All Depths				
0050	202-B064		98	Linear Feet	Removal of Pipe, 8" And Above				
0060	202-B076		1,503	Linear Feet	Removal of Traffic Stripe				
0070	202-B260		13	Each	Removal of Power Pole				
0080	202-B261		13,358	Linear Feet	Removal of Electric Power Cable, Including Hardware				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0090	203-A003 Changed 05/15/2009	(E)	22,629	Cubic Yard	Unclassified Excavation, FM, AH				
0100	203-EX017	(E)	156,942	Cubic Yard	Borrow Excavation, AH, FME, Class B9				
0110	203-F001	(E)	7,533	Cubic Yard	Channel Excavation, FM				
0120	203-G003	(E)	29,477	Cubic Yard	Excess Excavation, FM, AH				
0130	206-A001	(S)	202	Cubic Yard	Structure Excavation				
0140	209-A001		1,470	Square Yard	Geotextile Stabilization, Type V				
0150	213-C001		9	Ton	Superphosphate				
0160	216-A001		232	Square Yard	Solid Sodding				
0170	217-A001		664	Square Yard	Ditch Liner				
0180	219-A001		5	Thousand Gallon	Watering	20.	00	100.	00
0190	220-A001		9	Acre	Insect Pest Control	30.	00	270.	00
0200	221-A001	(S)	27	Cubic Yard	Portland Cement Concrete Paved Ditch				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0210	223-A001		1	Acre	Mowing	40.	00	40.	00
0220	224-A001		226	Square Yard	Soil Reinforcing Mat				
0230	234-A001		8,123	Linear Feet	Temporary Silt Fence				
0240	235-A001		1,792	Bale	Temporary Erosion Checks				
0250	236-A001		4	Each	Silt Basin, Type A				
0260	239-A001		482	Linear Feet	Temporary Slope Drains				
0270	408-A003	(A3)	2,932	Gallon	Asphalt for Prime Coat, Cut-Back MC-70 or Emulsified EA-1				
0280	501-E001		364	Linear Feet	Expansion Joints, Without Dowels				
0290	501-K001		800	Square Yard	Transverse Grooving				
0300	502-A001	(C)	800	Square Yard	Reinforced Cement Concrete Bridge End Pavement				
0310	603-CA002	(S)	92	Linear Feet	18" Reinforced Concrete Pipe, Class III				
0320	603-CA007	(S)	200	Linear Feet	48" Reinforced Concrete Pipe, Class III				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0330	603-CB002	(S)	2	Each	24" Reinforced Concrete End Section				
0340	603-CB006	(S)	2	Each	48" Reinforced Concrete End Section				
0350	606-B001		1,700	Linear Feet	Guard Rail, Class A, Type 1				
0360	606-D012		16	Each	Guard Rail, Bridge End Section, Type I				
0370	606-E001		16	Each	Guard Rail, Terminal End Section				
0380	609-D002	(S)	731	Linear Feet	Combination Concrete Curb and Gutter Type 2				
0390	616-A001	(S)	194	Square Yard	Concrete Median and/or Island Pavement, 4-inch				
0400	616-A003	(S)	27	Square Yard	Concrete Median and/or Island Pavement, 10-inch				
0410	618-A001		1	Lump Sum	Maintenance of Traffic	XXXXXXXX	XXX		
0420	618-C001		1	Lump Sum	Construction & Removal of Detour Bridge	XXXXXXXX	XXX		
0430	619-A1004		4	Mile	Temporary Traffic Stripe, Continuous White, Paint				
0440	619-A1007		2,280	Linear Feet	Temporary Traffic Stripe, Continuous White, Type 1 Tape				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0450	619-A2004		4	Mile	Temporary Traffic Stripe, Continuous Yellow, Paint				
0460	619-A2007		2,280	Linear Feet	Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape				
0470	619-A5002		68	Linear Feet	Temporary Traffic Stripe, Detail, Paint				
0480	619-A6003		36	Linear Feet	Temporary Traffic Stripe, Legend, Paint				
0490	619-C7001		81	Each	Two-Way Yellow Reflective High Performance Raised Marker				
0500	619-D1001		53	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet				
0510	619-D2001		775	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More				
0520	619-D4001		116	Square Feet	Directional Signs				
0530	619-F3004		12	Each	Delineators, Guard Rail, White				
0540	619-G4001 Changed 05/15/2009		600	Linear Feet	Barricades, Type III, Single Faced				
0550	619-G4005		24	Linear Feet	Barricades, Type III, Double Faced				
0560	619-G5001 Changed 05/15/2009		205	Each	Free Standing Plastic Drums				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0570	619-G7001		7	Each	Warning Lights, Type "B"				
0580	619-K2002		4	Each	Installation and Removal of Guard Rail, Type I Bridge End Section				
0590	619-K4001		6	Each	Installation and Removal of Guardrail, Terminal End Section				
0600	620-A001		1	Lump Sum	Mobilization	XXXXXXXXX	XXX		
0610	621-A001		1	Each	Field Laboratory				
0620	627-L001		209	Each	Two-Way Yellow Reflective High Performance Raised Markers				
0630	628-L002		1,140	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Skip Yellow				
0640	628-O001		2,281	Linear Feet	High Performance Cold Plastic Detail Stripe, White				
0650	630-F001		88	Each	Delineators, Guard Rail, White				
0660	630-G002		16	Each	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted				
0670	699-A001		1	Lump Sum	Roadway Construction Stakes	XXXXXXXXX	XXX		
0680	815-A009	(S)	10,312	Ton	Loose Riprap, Size 300 Changed 05/15/2009				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0690	815-E001 Changed 05/15/2009	(S)	14,042	Square Yard	Geotextile under Riprap				
0700	907-213-A001		56	Ton	Agricultural Limestone				
0710	907-225-A001		24	Acre	Grassing				
0720	907-225-B001		48	Ton	Agricultural Limestone				
0730	907-226-A001		9	Acre	Temporary Grassing				
0740	907-304-B009	(GT)	23,960	Ton	Granular Material, Class 3, Group D				
0750	907-304-F002	(GT)	5,541	Ton	Size 610 Crushed Stone Base				
0760	907-307-C003	(M)	12,187	Square Yard	6" Soil-Lime-Water Mixing, Class C				
0770	907-307-D001		165	Ton	Lime				
0780	907-403-A011	(BA1)	3,617	Ton	Hot Mix Asphalt, ST, 12.5-mm mixture				
0790	907-403-A012	(BA1)	6,889	Ton	Hot Mix Asphalt, ST, 19-mm mixture				
0800	907-403-A015	(BA1)	2,701	Ton	Hot Mix Asphalt, ST, 9.5-mm mixture				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0810	907-601-B003	(S)	1	Cubic Yard	Class "B" Structural Concrete, Minor Structures				
0820	907-603-ALT01	(S)	616	Linear Feet	18" Type A Alternate Pipe				
0830	907-603-ALT02	(S)	52	Linear Feet	24" Type A Alternate Pipe				
0840	907-603-ALT06	(S)	52	Linear Feet	48" Type A Alternate Pipe				
0850	907-617-A001		42	Each	Right-of-Way Marker				
0860	907-626-C008		10,678	Linear Feet	6" Thermoplastic Edge Stripe, Continuous White				
0870	907-626-D004		6,170	Linear Feet	6" Thermoplastic Traffic Stripe, Skip Yellow				
0880	907-626-E003		625	Linear Feet	6" Thermoplastic Traffic Stripe, Continuous Yellow				
0890	907-626-G004		2,266	Linear Feet	Thermoplastic Detail Stripe, White				
0900	907-626-H004		36	Linear Feet	Thermoplastic Legend, White				
ALTERNATE GROUP AA NUMBER 1									
0910	907-308-A001		26	Ton	Portland Cement				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0920	907-308-B002	(M)	3,047	Square Yard	Soil-Cement-Water Mixing, Optional Mixers, Design Soil				
ALTERNATE GROUP AA NUMBER 2									
0930	907-311-A003	(M)	3,047	Square Yard	Processing Lime and Fly Ash Treated Course, 6" Thick				
0940	907-311-B001		21	Ton	Lime				
0950	907-311-C002		82	Ton	Fly Ash, Class C or F				
Bridge Items									
0960	501-K001		4,387	Square Yard	Transverse Grooving				
0970	803-A001	(S)	11	Each	Test Pile				
0980	803-B001	(S)	8	Each	Conventional Static Loading Test	5,000.	00	40,000.	00
0990	803-C002	(S)	4,501	Linear Feet	14" x 14" Prestressed Concrete Piling				
1000	803-C003	(S)	3,565	Linear Feet	16" x 16" Prestressed Concrete Piling				
1010	803-D003	(S)	1,265	Linear Feet	HP 14 x 73 Steel Piling				
1020	803-J001	(S)	8	Each	Pile Restrike				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
1030	803-N001	(S)	10	Linear Feet	Exploration				
1040	803-O010	(S)	450	Linear Feet	Temporary Casing, 60" Diameter				
1050	805-A001	(S)	330,473	Pounds	Reinforcement				
1060	813-A001	(S)	1,974	Linear Feet	Concrete Railing				
1070	815-A009	(S)	1,782	Ton	Loose Riprap, Size 300				
1080	815-E001	(S)	1,470	Square Yard	Geotextile under Riprap				
1090	907-803-K006	(S)	744	Linear Feet	Drilled Shaft, 60" Diameter				
1100	907-803-L002	(S)	1	Each	Test Shaft, 60" Diameter				
1110	907-803-M005	(S)	128	Linear Feet	Trial Shaft, 60" Diameter				
1120	907-804-A001	(S)	1,863	Cubic Yard	Bridge Concrete, Class AA				
1130	907-804-C016 Changed 05/15/2009	(S)	2,841	Linear Feet	40' Prestressed Concrete Beam, Type I+2				
1140	907-804-C030 Changed 05/15/2009	(S)	1,436	Linear Feet	80' Prestressed Concrete Beam, Type III				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
1150	907-804-C145 Changed 05/15/2009	(S)	892	Linear Feet	50' Prestressed Concrete Beam, Type II + 2				
1160	907-804-C150	(S)	768	Linear Feet	110' Prestressed Concrete Beam, Type IV				

*** BID CERTIFICATION ***

TOTAL BID.....\$_____

*** DBE/WBE SECTION ***

Complete item nos. 1, 2, and/or 3 as appropriate. See Notice to Bidders addressing Disadvantaged Business Enterprises in Highway Construction.

1. I/We agree that no less than _____ percent shall be expended with small business concerns owned and controlled by socially and economically disadvantaged individuals (DBE and WBE).
2. Classification of Bidder: Small Business (DBE)_____ Small Business (WBE)_____
3. A joint venture with a Small Business (DBE/WBE): _____

*** SIGNATURE STATEMENT ***

BIDDER ACKNOWLEDGES THAT HE/SHE HAS CHECKED ALL ITEMS IN THIS PROPOSAL FOR ACCURACY AND CERTIFIED THAT THE FIGURES SHOWN THEREIN CONSTITUTE THEIR OFFICIAL BID.

BIDDER'S SIGNATURE

BIDDER'S COMPANY

BIDDER'S FEDERAL TAX ID NUMBER