

**Melinda L. McGrath**  
Deputy Executive Director/  
Chief Engineer

**Brenda Znachko**  
Deputy Executive Director/  
Administration



**Larry L. "Butch" Brown**  
Executive Director

**Steven K. Edwards**  
Director  
Office of Intermodal Planning

**Willie Huff**  
Director  
Office of Enforcement

---

*Contract Administration Division / P.O. Box 1850 / Jackson, Mississippi 39215-1850 / Telephone (601) 359-7700 / FAX (601) 359-7732 / GoMDOT.com*

---

**To: ALL POTENTIAL BIDDERS**

**Date: 05/21/2009**

**RE: IMD-0059-03(084) / 104423301 - Lauderdale County**

Bidders are hereby advised that the 'Z' bars shown on the Span Detail sheets for the bridges with raised concrete median island may be eliminated to allow a continuous pour of the bridge deck. If the 'Z' bars are eliminated, the Contractor will have to drill and epoxy No. 5 bars in the bridge deck to attach the raised median reinforcement. A detail of the No. 5 bar attachment will be furnished to the successful bidder.

Bidders are also advised that the wrong table was included on plan sheet no. EQ-10 for the 0.125" aluminum signs. Attached are the estimated quantities for the Sheet Aluminum 0.125" Thickness Signs. The quantity on the summary of quantities sheet of the plans and on the bid sheet in the proposal is correct. The successful bidder will be given a revised sheet no. EQ-10 reflecting these changes.

Your formal acknowledgment of receipt of this notification will be entered into our records and indicates your understanding of the raised concrete median island reinforcement option and the estimated quantities for the 0.125" signs on this project and that you have bid accordingly.

Please have an authorized representative of your company sign this FAX and return by FAX to 601-359-7732.

\_\_\_\_\_  
Melinda L. McGrath, P.E.  
Chief Engineer / Deputy Executive Director

\_\_\_\_\_  
Contractor

\_\_\_\_\_  
Authorized Signature

STATE MISS. PROJECT NO. IMD-0059-03(084)

LAUDERDALE COUNTY

**STANDARD ROADSIDE SIGNS**  
SHEET ALUMINUM 0.060" THICKNESS

SIGN NUMBER	SIZE	UNIT AREA (SQ. FT.)	QUANTITY REQUIRED	TOTAL SIGN AREA (SQ. FT.)	REMARKS
M1-1	24" x 24"	4	12	48	I-50
M1-2	24" x 24"	4	14	56	I-20
M1-3	24" x 24"	4	5	20	U.S. 80
M1-4	24" x 24"	4	5	20	S.R. 19
M2-1	21" x 15"	2.19	2	4.38	JCT
M2-1A	21" x 15"	2.19	4	8.76	JCT (INTERSTATE)
M3-1	24" x 12"	2	2	4	NORTH
M3-1A	24" x 12"	2	3	6	NORTH (INTERSTATE)
M3-2	24" x 12"	2	2	4	EAST
M3-2A	24" x 12"	2	4	8	EAST (INTERSTATE)
M3-3	24" x 12"	2	2	4	SOUTH
M3-3A	24" x 12"	2	3	6	SOUTH (INTERSTATE)
M3-4	24" x 12"	2	2	4	WEST
M3-4A	24" x 12"	2	4	8	WEST (INTERSTATE)
M4-5	24" x 12"	2	8	16	TO
M6-1L	21" x 16"	2.19	6	13.14	DIRECTIONAL ARROW
M6-1A	21" x 15"	2.19	4	8.76	
M6-1R	21" x 15"	2.19	6	13.14	
M6-1RA	21" x 15"	2.19	4	8.76	
M6-3A	21" x 15"	2.19	4	8.76	DIRECTIONAL UP (INTERSTATE)
R1-1	36" OCTAGON	9	2	18	STOP
R2-1	24" x 30"	5	1	5	30 MPH
R3-1	24" x 24"	4	2	8	NO RIGHT TURN
R3-1	30" x 30"	6.25	2	12.5	
R3-5L	30" x 36"	7.5	2	15	MANDATORY MOVEMENT SIGN
R3-7R	30" x 30"	6.25	2	12.5	RIGHT LANE MUST TURN RIGHT
R4-7	24" x 30"	5	2	10	KEEP RIGHT
R6-2R	24" x 30"	6	2	12	ONE WAY (ABOVE ARROW)
W1-8L	24" x 30"	6	11	66	CHEVRON (LEFT)
W1-8R	24" x 30"	6	11	66	CHEVRON (RIGHT)
W19-1	24" x 24"	4	2	8	30 MPH
W14-2	30" x 30"	6.25	2	12.5	NO OUTLET
<b>TOTAL (0.060" THICKNESS)</b>					<b>481.2</b>

**STANDARD ROADSIDE SIGNS**  
SHEET ALUMINUM 0.125" THICKNESS

SIGN NUMBER	SIZE	UNIT AREA (SQ. FT.)	QUANTITY REQUIRED	TOTAL SIGN AREA (SQ. FT.)	REMARKS
R1-1	48" OCTAGON	16	5	80	STOP
R1-2	36" TRIANGLE	3.80	15	56.5	YIELD
R2-1	36" x 48"	12	9	108	55 MPH
R2-1	36" x 48"	12	1	12	70 MPH
R6-1	36" x 36"	9	8	72	DO NOT ENTER
R6-1	48" x 48"	16	6	96	
R6-1a	42" x 36"	10.5	4	42	WRONG WAY
R6-1L	36" x 12"	3	10	30	ONE WAY (LEFT)
R6-1R	36" x 12"	3	8	24	
R11-2	48" x 30"	10	2	20	BARRICADE MOUNTED
W1-1R	36" x 36"	9	1	9	RIGHT TURN ARROW
W1-3L	36" x 36"	9	1	9	REVERSE TURN ARROW
W1-7	48" x 24"	8	3	24	LARGE ARROW (DOUBLE HEAD)
W2-2R	36" x 36"	9	1	9	CROSS ROAD
W3-1A	48" x 48"	16	3	48	STOP AHEAD
W3-3	48" x 48"	16	10	160	SIGNAL AHEAD
W4-1R	48" x 48"	16	2	32	MERGE
W6-3	48" x 48"	16	2	32	TWO-WAY TRAFFIC
SN7475	48" x 48"	16	6	96	BRIDGE MAY ICE IN COLD WEATHER
<b>TOTAL (0.125" THICKNESS)</b>					<b>961.5</b>

MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
**ESTIMATED QUANTITIES (STANDARD ROADSIDE SIGN FACES)**

PROJECT NO. IMD-0059-03(084)  
COUNTY : LAUDERDALE

REVISION: \_\_\_\_\_ DATE: \_\_\_\_\_  
 REVISION: \_\_\_\_\_ DATE: \_\_\_\_\_  
 REVISION: \_\_\_\_\_ DATE: \_\_\_\_\_

PROJECT NUMBER: EC-10  
SHEET NUMBER: 33

DESIGNER: \_\_\_\_\_ FILE NAME: \_\_\_\_\_  
 CHECKER: \_\_\_\_\_ DATE: \_\_\_\_\_

DESIGN TEAM: Florence & Hutchison, Inc. COUNTY : LAUDERDALE PROJECT No. IMD-0059-03(084)