

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) further propose to execute the attached contract agreement (Section 902) as soon as the work is awarded to me (us), and to begin and complete the work within the time limit(s) provided for in the Specifications and Advertisement. I (We) also propose to execute the attached contract bond (Section 903) in an amount not less than one hundred (100) percent of the total of my (our) part, but also to guarantee the excellence of both workmanship and materials until the work is finally accepted.

I (We) enclose a certified check, cashier's check or bid bond for **five percent (5%) of total bid** and hereby agree that in case of my (our) failure to execute the contract and furnish bond within Ten (10) days after notice of award, the amount of this check (bid bond) will be forfeited to the State of Mississippi as liquidated damages arising out of my (our) failure to execute the contract as proposed. It is understood that in case I am (we are) not awarded the work, the check will be returned as provided in the Specifications.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. 1 DATED 6/15/2009 ADDENDUM NO. DATED
ADDENDUM NO. DATED ADDENDUM NO. DATED

Number	Description
1	Revised Table of Contents; Added Notice to Bidders No. 1312; Revised Notice to Bidders No. 2600; Added Notice to Bidders No. 2673; Revised Bid Sheets; Revised Plan Sheets Nos. 2, 3, 12, 13, 14 and 98; EBS Download Required.

TOTAL ADDENDA: 1
(Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

Contractor

BY _____
Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

_____ President	_____ Address
_____ Secretary	_____ Address
_____ Treasurer	_____ Address

The following is my (our) itemized proposal.

Revised 09/21/2005

BR-2791-00(008) / 102527301 & 302

Yalobusha & Calhoun County(ies)

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

TABLE OF CONTENTS

PROJECT: BR-2791-00(008) / 102527301 & 302 -- Yalobusha and Calhoun Counties

901--Advertisement

904--Notice to Bidders: Governing Specs. - # 1
Final Cleanup - # 3
Fiber Reinforced Concrete - # 640
Disadvantage Business Enterprise, W/Supplement - # 696
On-The-Job Training Program - # 777
Payroll Requirements - # 883
Rumble Stripe - #1312
Errata & Modifications to 2004 Standard Specifications - # 1405
Safety Apparel - # 1808
Minimum Wage Rate - # 1869
Non-Quality Control/Quality Assurance Concrete - # 1922
Federal Bridge Formula - # 1928
Department of Labor Ruling - # 2239
Storm Water Discharge Associated w/ Construction Activities (≥ 5 Acres) - # 2348
Mississippi Resident Agent Requirement - # 2361
Status of ROW, W/Attachments - # 2382
Removal of Haul Permit - # 2400
American Recovery and Reinvestment Act (ARRA) Sign - # 2438
Requirements Under Section 902 of the ARRA - # 2476
Petroleum Products Base Price - # 2587
Special Reporting Criteria - # 2594
DBE Forms, Participation and Payment - # 2596
Contract Time - # 2600
Specialty Items - # 2601
Placement of Fill Material in Federally Regulated Areas - # 2602
DUNS Requirement for ARRA Funded Projects - #2616
Bridge Concrete - #2673

906: Required Federal Contract Provisions -- FHWA-1273, W/Supplement

907-104-1: Partnering Process

907-105-3: Cooperation By Contractors, W/Supplement

907-107-1: Liability Insurance, W/Supplement

907-107-3: Contractor's Protection Plan

907-107-6: Legal Relations & Responsibility to Public, W/Supplement

907-108-17: Prosecution and Progress

907-109-3: Partial Payment, W/Supplement

CONTINUED ON NEXT PAGE

- 907-213-2: Agricultural Limestone
- 907-225-1: Grassing, W/Supplement
- 907-226-1: Temporary Grassing
- 907-227-6: Hydroseeding
- 907-304-11: Granular Courses
- 907-401-2: Hot Mix Asphalt (HMA), W/Supplement
- 907-403-4: Hot Mix Asphalt (HMA), W/Supplement
- 907-407-1: Tack Coat
- 907-601-1: Structural Concrete
- 907-617-2: Right-Of-Way Markers
- 907-618-4: Placement of Temporary Traffic Stripe
- 907-626-15: Thermoplastic Traffic Markings
- 907-701-3: Hydraulic Cement, W/Supplement
- 907-703-7: Aggregates
- 907-708-5: Non-Metal Drainage Structures
- 907-709-1: Metal Pipe
- 907-711-3: Synthetic Structural Fiber Reinforcement
- 907-713-1: Admixtures for Concrete
- 907-714-5: Miscellaneous Materials, W/Supplement
- 907-720-1: Pavement Marking Materials
- 907-804-8: Concrete Bridges and Structures, W/Supplement

- 906-3: MDOT On-the-Job Training Program
- 906-6: MDOT On-the-Job Training Program - Alternate Program

SECTION 905 - PROPOSAL,
PROPOSAL SHEET NOS. 2-1 THRU 2-11,
COMBINATION BID PROPOSAL,
CERTIFICATE OF PERFORMANCE - PRIOR FEDERAL-AID CONTRACTS,
CERTIFICATION REGARDING NON-COLLUSION, DEBARMENT AND SUSPENSION,
SECTION 902 - CONTRACT FORM, AND SECTION 903 - CONTRACT BOND FORMS,
PILE DRIVING FORM,
OCR-485.

(REVISIONS TO THE ABOVE WILL BE INDICATED ON THE SECOND SHEET
OF SECTION 905 AS ADDENDA)

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904 - NOTICE TO BIDDERS NO. 1312

CODE: (SP)

DATE: 01/22/2007

SUBJECT: Rumble Stripe

Bidders are hereby advised that when edge lines are placed over rumble strips, the pavement marking stripe must be applied using the atomization method instead of extrusion / ribbon method. The thickness of the stripe will be 60-mils, unless otherwise noted in the plans/proposal or pay item description. To ensure the proper alignment of the rumble stripes, the Contractor will be required to place a layout line to be followed during installation of the edge lines over the rumble strips.

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904 - NOTICE TO BIDDERS NO. 2600

CODE: (SP)

DATE: 06/10/2009

SUBJECT: Contract Time

PROJECT: BR-2791-00(008) / 102527301 & 302 -- Yalobusha and Calhoun Counties

The calendar date for completion of work to be performed by the Contractor for this project shall be **February 18, 2011** which date or extended date as provided in Subsection 108.06 shall be the end of contract time. It is anticipated that the Notice of Award will be issued no later than **July 14, 2009** and the effective date of the Notice to Proceed / Beginning of Contract Time will be **August 6, 2009**.

Should the Contractor request a Notice to Proceed earlier than **August 6, 2009**, the requested date will become the new Notice to Proceed / Beginning of Contract Time date.

A progress schedule as referenced to in Subsection 108.03 will not be required for this contract.

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904- NOTICE TO BIDDERS NO. 2673

CODE: (SP)

DATE: June 10, 2009

SUBJECT: Bridge Concrete

PROJECT: BR-2791-00(008) / 102527301 & 302 – Yalobusha and Calhoun Counties

Bidders are hereby advised that Bridge Concrete, Class “AA” shall be used instead of Bridge Concrete, Class “BD” as shown in the plans.

Replacement of 9 bridges on SR 32 from Water Valley to SR 330, known as Federal Aid Project Nos. BR-2791-00(008) / 102527301 & 302, in the Counties of Yalobusha and Calhoun, State of Mississippi.

I (We) agree to complete the entire project within the specified contract time.

***** SPECIAL NOTICE TO BIDDERS *****

**BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED.
 BIDS WILL NOT BE CONSIDERED UNLESS THE BID CERTIFICATION LOCATED AT THE END OF THE BID SHEETS IS SIGNED**

*****BID SCHEDULE*****

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Item Amount	
						Dollar	Ct	Dollar	Ct
Roadway Items									
0010	201-A001		1	Lump Sum	Clearing and Grubbing	XXXXXXXX	XXX		
0020	201-B001		2	Acre	Clearing and Grubbing				
0030	202-A001		1	Lump Sum	Removal of Obstructions	XXXXXXXX	XXX		
0040	202-B005		24,747	Square Yard	Removal of Asphalt Pavement, All Depths				
0050	202-B053		860	Linear Feet	Removal of Guard Rail Including Post, Blockouts & Hardware				
0060	202-B064		302	Linear Feet	Removal of Pipe, 8" And Above				
0070	202-B076		6,000	Linear Feet	Removal of Traffic Stripe				
0080	202-B088		2	Each	Removal of Box Culvert Headwall, All Sizes				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0090	203-A003	(E)	25,721	Cubic Yard	Unclassified Excavation, FM, AH				
0100	203-EX017	(E)	70,104	Cubic Yard	Borrow Excavation, AH, FME, Class B9				
0110	203-G003	(E)	8,527	Cubic Yard	Excess Excavation, FM, AH				
0120	206-A001	(S)	7,020	Cubic Yard	Structure Excavation				
0130	206-B001	(E)	417	Cubic Yard	Select Material for Undercuts, Contractor Furnished, FM				
0140	209-A004		28,515	Square Yard	Geotextile Stabilization, Type V, Non-Woven				
0150	213-C001		19	Ton	Superphosphate				
0160	216-A001		508	Square Yard	Solid Sodding				
0170	217-A001		1,926	Square Yard	Ditch Liner				
0180	219-A001		10	Thousand Gallon	Watering	20.	00	200.	00
0190	220-A001		19	Acre	Insect Pest Control	30.	00	570.	00
0200	221-A001	(S)	72	Cubic Yard	Portland Cement Concrete Paved Ditch				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0210	223-A001		2	Acre	Mowing	40.	00	80.	00
0220	224-A001		637	Square Yard	Soil Reinforcing Mat				
0230	234-A001		12,170	Linear Feet	Temporary Silt Fence				
0240	235-A001		1,000	Bale	Temporary Erosion Checks				
0250	236-A004		12	Each	Silt Basin, Type D				
0260	406-A001		2,133	Square Yard	Cold Milling of Bituminous Pavement, All Depths				
0270	408-A003	(A3)	3,725	Gallon	Asphalt for Prime Coat, Cut-Back MC-70 or Emulsified EA-1				
0271	423-A001		4	Mile	Rumble Strips, Ground In				
					Added 06/15/2009				
0280	501-E001		304	Linear Feet	Expansion Joints, Without Dowels				
0290	501-K001		681	Square Yard	Transverse Grooving				
0300	502-A001	(C)	701	Square Yard	Reinforced Cement Concrete Bridge End Pavement				
0310	602-A001	(S)	262,368	Pounds	Reinforcing Steel				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0320	603-CA003	(S)	84	Linear Feet	24" Reinforced Concrete Pipe, Class III				
0330	603-CA007	(S)	68	Linear Feet	48" Reinforced Concrete Pipe, Class III				
0340	603-CB002	(S)	2	Each	24" Reinforced Concrete End Section				
0350	603-CB006	(S)	2	Each	48" Reinforced Concrete End Section				
0360	606-B001		1,275	Linear Feet	Guard Rail, Class A, Type 1				
0370	606-D012		12	Each	Guard Rail, Bridge End Section, Type I				
0380	606-E001		12	Each	Guard Rail, Terminal End Section				
0390	609-D002	(S)	997	Linear Feet	Combination Concrete Curb and Gutter Type 2				
0400	615-A015 Changed 06/15/2009	(S)	120	Linear Feet	Concrete Bridge End Barrier, 32"				
0410	616-A001	(S)	98	Square Yard	Concrete Median and/or Island Pavement, 4-inch				
0420	616-A003	(S)	28	Square Yard	Concrete Median and/or Island Pavement, 10-inch				
0430	618-A001		1	Lump Sum	Maintenance of Traffic	XXXXXXXX	XXX		

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0431	618-C001		1	Lump Sum	Construction & Removal of Detour Bridge	XXXXXXXX	XXX		
	Added 06/15/2009								
0440	619-A1001		18,111	Linear Feet	Temporary Traffic Stripe, Continuous White				
0450	619-A2001		18,008	Linear Feet	Temporary Traffic Stripe, Continuous Yellow				
0460	619-A4001		800	Linear Feet	Temporary Traffic Stripe, Skip Yellow				
0470	619-A5001		1,466	Linear Feet	Temporary Traffic Stripe, Detail				
0480	619-A6001		52	Linear Feet	Temporary Traffic Stripe, Legend				
0490	619-C7001		188	Each	Two-Way Yellow Reflective High Performance Raised Marker				
0500	619-D1001		601	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet				
0510	619-D2001		1,360	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More				
0520	619-D4001		116	Square Feet	Directional Signs				
0530	619-F3004		8	Each	Delineators, Guard Rail, White				
0540	619-G4001		582	Linear Feet	Barricades, Type III, Single Faced				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0550	619-G4005		108	Linear Feet	Barricades, Type III, Double Faced				
0560	619-G5001		319	Each	Free Standing Plastic Drums				
0570	619-G7001		41	Each	Warning Lights, Type "B"				
0580	619-K2002		4	Each	Installation and Removal of Guard Rail, Type I Bridge End Section				
0590	619-K4001		4	Each	Installation and Removal of Guardrail, Terminal End Section				
0600	620-A001		1	Lump Sum	Mobilization	XXXXXXXX	XXX		
0610	621-A001		1	Each	Field Laboratory				
0620	627-L001		224	Each	Two-Way Yellow Reflective High Performance Raised Markers				
0630	628-J002		1,212	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Continuous White				
0640	628-L002		210	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Skip Yellow				
0650	628-M002		792	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow				
0660	628-O002		53	Linear Feet	High Performance Cold Plastic Detail Stripe, Yellow				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0670	630-F001		66	Each	Delineators, Guard Rail, White				
0680	630-G002		12	Each	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted				
0690	699-A001		1	Lump Sum	Roadway Construction Stakes	XXXXXXXX	XXX		
0700	815-A009	(S)	1,274	Ton	Loose Riprap, Size 300				
0710	815-E001	(S)	1,116	Square Yard	Geotextile under Riprap				
0720	815-F002	(S)	36	Ton	Sediment Control Stone				
0730	907-225-A001		43	Acre	Grassing				
0740	907-225-B001		107	Ton	Agricultural Limestone				
0750	907-226-A001		21	Acre	Temporary Grassing				
0760	907-304-B009	(GT)	12,623	Ton	Granular Material, Class 3, Group D Changed 06/15/2009				
0770	907-304-F003	(GT)	8,107	Ton	3/4" and Down Crushed Stone Base Changed 06/15/2009				
0780	907-403-A011	(BA1)	4,522	Ton	Hot Mix Asphalt, ST, 12.5-mm mixture				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0790	907-403-A012	(BA1)	5,599	Ton	Hot Mix Asphalt, ST, 19-mm mixture				
0800	907-403-A015	(BA1)	3,195	Ton	Hot Mix Asphalt, ST, 9.5-mm mixture				
0810	907-601-A001	(S)	401	Cubic Yard	Class "B" Structural Concrete				
0820	907-601-B003	(S)	1	Cubic Yard	Class "B" Structural Concrete, Minor Structures				
0830	907-603-ALT01	(S)	1,272	Linear Feet	18" Type A Alternate Pipe				
0840	907-617-A001		113	Each	Right-of-Way Marker				
0850	907-626-C008		22,275	Linear Feet	6" Thermoplastic Edge Stripe, Continuous White				
0860	907-626-D004		2,140	Linear Feet	6" Thermoplastic Traffic Stripe, Skip Yellow				
0870	907-626-E003		20,058	Linear Feet	6" Thermoplastic Traffic Stripe, Continuous Yellow				
0880	907-626-G004		2,929	Linear Feet	Thermoplastic Detail Stripe, White				
0890	907-626-H004		362	Linear Feet	Thermoplastic Legend, White				
0900	907-804-B001	(S)	1,383	Cubic Yard	Box Bridge Concrete, Class B				
Bridge Items									

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0910	501-K001		1,822	Square Yard	Transverse Grooving				
0920	803-B001	(S)	6	Each	Conventional Static Loading Test	5,000.	00	30,000.	00
0930	803-D002	(S)	4,955	Linear Feet	HP 12 x 53 Steel Piling				
0940	803-D003	(S)	495	Linear Feet	HP 14 x 73 Steel Piling				
0950	803-I001	(S)	7	Each	PDA Test Pile				
0960	803-J001	(S)	6	Each	Pile Restrike				
0970	805-A001	(S)	168,491	Pounds	Reinforcement				
0980	813-A001	(S)	1,033	Linear Feet	Concrete Railing				
0990	815-A009	(S)	1,491	Ton	Loose Riprap, Size 300				
1000	815-E001	(S)	1,203	Square Yard	Geotextile under Riprap				
1010	907-804-A001 Changed 06/15/2009	(S)	946	Cubic Yard	Bridge Concrete, Class AA				
1020	907-804-A012 Deleted 06/15/2009	(S)				XXXXXXXX	XXX	XXXXXXXX	XXX

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
1020	907-804-A012	(S)				XXXXXXXXXX	XXX	XXXXXXXXXX	XXX
	Deleted 06/15/2009								
1030	907-804-C002	(S)	296	Linear Feet	60' Prestressed Concrete Beam, Type III				
1040	907-804-C016	(S)	1,385	Linear Feet	40' Prestressed Concrete Beam, Type I+2				
1050	907-804-C030	(S)	399	Linear Feet	80' Prestressed Concrete Beam, Type III				
1060	907-804-C177	(S)	448	Linear Feet	45' Prestressed Concrete Beam, Type I+2				

*** BID CERTIFICATION ***

TOTAL BID.....\$_____

*** DBE/WBE SECTION ***

Complete item nos. 1, 2, and/or 3 as appropriate. See Notice to Bidders addressing Disadvantaged Business Enterprises in Highway Construction.

1. I/We agree that no less than _____ percent shall be expended with small business concerns owned and controlled by socially and economically disadvantaged individuals (DBE and WBE).
2. Classification of Bidder: Small Business (DBE)_____ Small Business (WBE)_____
3. A joint venture with a Small Business (DBE/WBE): _____

*** SIGNATURE STATEMENT ***

BIDDER ACKNOWLEDGES THAT HE/SHE HAS CHECKED ALL ITEMS IN THIS PROPOSAL FOR ACCURACY AND CERTIFIED THAT THE FIGURES SHOWN THEREIN CONSTITUTE THEIR OFFICIAL BID.

BIDDER'S SIGNATURE

BIDDER'S COMPANY

BIDDER'S FEDERAL TAX ID NUMBER