

SCOTT (62)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	APAC - Mississippi, Inc.	W. E. Blain & Sons, Inc.	
Widening and overlaying approximately 4 miles of US Highway 80 near Morton, known as State Project No. MP-5080-62(017) / 303638301, in the County of Scott, State of Mississippi.					\$1,365,851.90	\$1,422,064.00	\$1,501,333.43	
Ref#	SM Item	Item Description	Item Qty	Units		1	2	
0010	202-B094	Removal of Curb &/or Curb and Gutter, All Types	208.000	LF		9.50	12.50	
0020	202-B097	Removal of Concrete Overlayed w/ Asphalt Pavement, All Depth	446.000	SY		58.00	57.00	
0030	203-G004	Excess Excavation, LVM, AH	50.000	CY		24.00	32.00	
0040	305-B001	Size I Stabilizer Aggregate, Coarse	50.000	CY		90.00	60.00	
0050	406-A001	Cold Milling of Bituminous Pavement, All Depths	4,500.000	SY		8.00	6.00	
0060	423-A001	Rumble Strips, Ground In	7.000	MI		450.00	650.00	
0070	501-D001	Expansion Joints, With Dowels	340.000	LF		27.00	29.00	
0080	501-I001	Joint Filler, Wooden Board	340.000	LF		20.00	21.00	
0090	503-B001	Saw Cut, Longitudinal Joints	344.000	LF		5.00	5.30	
0100	503-C007	Saw Cut, Full Depth	630.000	LF		12.00	13.00	
0110	503-D001	Concrete for Base Repair	6.000	CY		170.00	180.00	
0120	503-E002	Tie Bars, No. 5 Deformed Drilled and Epoxied or Grouted	711.000	EA		12.00	13.00	
0130	609-E001	Bituminous Curb	590.000	LF		20.00	12.00	
0140	616-B001	Hot Bituminous Median and/or Island Pavement	38.000	SY		90.00	130.00	
0150	618-A001	Maintenance of Traffic	1.000	LS		120,000.00	136,000.00	
0160	619-A1002	Temporary Traffic Stripe, Continuous White	8.000	MI		500.00	450.00	
0170	619-A2002	Temporary Traffic Stripe, Continuous Yellow	8.000	MI		500.00	450.00	
0180	619-A4006	Temporary Traffic Stripe, Skip Yellow	4.000	MI		500.00	800.00	
0190	619-A5001	Temporary Traffic Stripe, Detail	2,010.000	LF		0.10	0.16	
0200	619-A6001	Temporary Traffic Stripe, Legend	468.000	LF		1.00	0.26	
0210	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	120.000	SF		15.00	16.00	
0220	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	116.000	SF		8.00	8.50	
0230	619-G4005	Barricades, Type III, Double Faced	24.000	LF		20.00	21.00	
0240	627-J001	Two-Way Clear Reflective High Performance Raised Markers	221.000	EA		4.00	4.75	
0250	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	380.000	EA		4.00	4.75	
0260	907-304-A001	Granular Material, LVM, Class 5, Group C	1,350.000	CY		26.50	26.35	

SCOTT (62)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	APAC - Mississippi, Inc.	W. E. Blain & Sons, Inc.	
Widening and overlaying approximately 4 miles of US Highway 80 near Morton, known as State Project No. MP-5080-62(017) / 303638301, in the County of Scott, State of Mississippi.								
Ref#	SM Item	Item Description	Item Qty	Units		1	2	
0270	907-403-A006	Hot Mix Asphalt, MT, 12.5-mm mixture	6,600.000	TON		70.00	77.00	
0280	907-403-B004	Hot Mix Asphalt, MT, 12.5-mm mixture, Leveling	500.000	TON		90.00	120.00	
0290	907-403-C003	Hot Mix Asphalt, MT, 19-mm mixture, Trench Widening	4,350.000	TON		68.00	64.00	
0300	907-413-D001	Cleaning and Filling Joints in PCC Pavement	13,730.000	LF		5.00	10.85	
0310	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	14,784.000	LF		9.00	5.25	
0320	907-501-B002	8" Plain Cement Concrete Pavement, Broom Finish	446.000	SY		205.00	215.00	
0330	907-626-C004	6" Thermoplastic Edge Stripe, Continuous White	8.000	MI		2,300.00	2,300.00	
0340	907-626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	4.000	MI		1,200.00	850.00	
0350	907-626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	2.000	MI		2,600.00	2,700.00	
0360	907-626-G004	Thermoplastic Detail Stripe, White	1,628.000	LF		1.00	0.80	
0370	907-626-G005	Thermoplastic Detail Stripe, Yellow	382.000	LF		1.00	0.80	
0380	907-626-H004	Thermoplastic Legend, White	468.000	LF		2.00	2.65	