

NEWTON (51)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	N. L. Carson Construction Company, Inc.	Magco, Inc.	Joe McGee Construction Company, Inc.
Bridge replacement, on MS. Hwy. 15 between Decatur and Union, known as Federal Aid Project No. BR-0022-02(042) / 104129301, in the County of Newton, State of Mississippi.					\$3,980,787.29	\$3,168,300.94	\$3,220,885.13	\$3,441,856.39
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS		140,000.00	46,080.00	177,350.00
0020	201-B001	Clearing and Grubbing	1.000	ACRE		1,500.00	3,584.00	2,500.00
0030	202-A001	Removal of Obstructions	1.000	LS		13,000.00	16,640.00	10,000.00
0040	202-B025	Removal of Concrete Paved Ditch	73.000	SY		3.00	7.68	20.00
0050	202-B076	Removal of Traffic Stripe	2,900.000	LF		1.50	1.50	1.50
0060	202-B078	Removal of Pavement, All Types and Depths	7,699.000	SY		3.50	5.77	9.00
0070	202-B094	Removal of Curb &/or Curb and Gutter, All Types	149.000	LF		2.50	3.50	10.00
0080	202-B102	Removal of Guard Rail	1,120.000	LF		3.00	3.00	3.00
0090	202-B106	Removal of Pipe, All Sizes	120.000	LF		5.00	3.50	10.00
0100	202-B140	Removal of Box Bridge Headwall	2.000	EA		950.00	2,304.00	2,000.00
0110	202-B161	Removal of Existing Sign	1.000	EA		100.00	500.00	100.00
0120	203-EX033	Borrow Excavation, AH, FME, Class B17	34,049.000	CY		5.00	5.89	5.20
0130	203-G003	Excess Excavation, FM, AH	100.000	CY		3.00	5.57	20.00
0140	206-A001	Structure Excavation	416.000	CY		6.00	7.04	6.50
0150	206-B001	Select Material for Undercuts, Contractor Furnished, FM	114.000	CY		35.00	39.68	55.50
0160	212-A001	Light Ground Preparation	48,412.000	SY		0.01	0.02	0.02
0170	212-B001	Standard Ground Preparation	96,824.000	SY		0.07	0.05	0.05
0180	213-B001	Combination Fertilizer, 13-13-13	13.000	TON		650.00	600.00	600.00
0190	213-C001	Superphosphate	10.000	TON		400.00	500.00	500.00
0200	214-A002	Seeding, Bermudagrass	400.000	LBS		10.00	8.00	8.00
0210	214-A003	Seeding, Tall Fescue	200.000	LBS		5.00	3.00	3.00
0220	214-A004	Seeding, Crimson Clover	200.000	LBS		5.00	4.00	4.00
0230	214-A014	Seeding, Browntop Millet	200.000	LBS		0.20	2.00	2.00
0240	214-A015	Seeding, Oats	900.000	LBS		0.20	1.00	1.00
0250	214-A017	Seeding, Rye Grass	250.000	LBS		1.00	1.00	1.00
0260	215-A001	Vegetative Materials for Mulch	50.000	TON		200.00	180.00	180.00

NEWTON (51)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	N. L. Carson Construction Company, Inc.	Magco, Inc.	Joe McGee Construction Company, Inc.
Bridge replacement, on MS. Hwy. 15 between Decatur and Union, known as Federal Aid Project No. BR-0022-02(042) / 104129301, in the County of Newton, State of Mississippi.					\$3,980,787.29	\$3,168,300.94	\$3,220,885.13	\$3,441,856.39
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0270	216-A001	Solid Sodding	948.000	SY		6.00	4.00	4.00
0280	217-A001	Ditch Liner	253.000	SY		2.00	3.00	3.00
0290	219-A001	Watering	19.000	KGAL		20.00	20.00	20.00
0300	220-A001	Insect Pest Control	10.000	ACRE		30.00	30.00	30.00
0310	221-A001	Portland Cement Concrete Paved Ditch	24.000	CY		284.00	366.08	425.00
0320	223-A001	Mowing	1.000	ACRE		40.00	40.00	40.00
0330	224-A001	Soil Reinforcing Mat	1,851.000	SY		6.00	4.00	4.00
0340	234-A001	Temporary Silt Fence	5,253.000	LF		3.00	3.50	3.50
0350	235-A001	Temporary Erosion Checks	1,015.000	BALE		5.00	8.00	3.00
0360	239-A001	Temporary Slope Drains	235.000	LF		5.00	11.52	10.00
0370	406-A001	Cold Milling of Bituminous Pavement, All Depths	1,867.000	SY		7.05	9.12	6.40
0380	408-A003	Asphalt for Prime Coat, Cut-Back MC-70 or Emulsified EA-1	992.000	GAL		4.50	0.50	5.00
0390	501-E001	Expansion Joints, Without Dowels	180.000	LF		9.00	8.32	10.00
0400	501-K001	Transverse Grooving	400.000	SY		2.61	2.62	2.60
0410	502-A001	Reinforced Cement Concrete Bridge End Pavement	400.000	SY		100.00	83.20	87.50
0420	602-A001	Reinforcing Steel	73,548.000	LBS		0.67	0.64	0.75
0430	606-B001	Guard Rail, Class A, Type 1	850.000	LF		21.00	21.00	21.00
0440	606-D015	Guard Rail, Bridge End Section	8.000	EA		2,350.00	2,350.00	2,350.00
0450	606-E002	Guard Rail, Terminal End Section, Flared	8.000	EA		2,150.00	2,350.00	2,150.00
0460	609-D002	Combination Concrete Curb and Gutter Type 2	52.000	LF		18.00	23.68	40.00
0470	618-A001	Maintenance of Traffic	1.000	LS		20,200.00	21,080.00	53,400.00
0480	618-C001	Construction & Removal of Detour Bridge	1.000	LS		155,384.00	57,455.00	120,000.00
0490	619-A1002	Temporary Traffic Stripe, Continuous White	4.000	MI		450.00	450.00	1,000.00
0500	619-A2002	Temporary Traffic Stripe, Continuous Yellow	1.000	MI		450.00	450.00	1,000.00
0510	619-A2006	Temporary Traffic Stripe, Continuous Yellow, Type 1 or 2 Tap	1.000	MI		3,500.00	3,500.00	2,000.00
0520	619-A4006	Temporary Traffic Stripe, Skip Yellow	1.000	MI		800.00	800.00	1,000.00

NEWTON (51)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	N. L. Carson Construction Company, Inc.	Magco, Inc.	Joe McGee Construction Company, Inc.
Bridge replacement, on MS. Hwy. 15 between Decatur and Union, known as Federal Aid Project No. BR-0022-02(042) / 104129301, in the County of Newton, State of Mississippi.					\$3,980,787.29	\$3,168,300.94	\$3,220,885.13	\$3,441,856.39
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0530	619-A6001	Temporary Traffic Stripe, Legend	204.000	LF		0.50	0.50	1.00
0540	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	156.000	EA		5.00	5.00	10.00
0550	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	245.000	SF		10.00	10.00	7.00
0560	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	632.000	SF		15.00	15.00	7.00
0570	619-G4001	Barricades, Type III, Single Faced	336.000	LF		25.00	25.00	11.00
0580	619-G4005	Barricades, Type III, Double Faced	102.000	LF		35.00	35.00	13.00
0590	619-G5001	Free Standing Plastic Drums	119.000	EA		85.00	85.00	36.00
0600	619-G7001	Warning Lights, Type "B"	5.000	EA		950.00	950.00	350.00
0610	620-A001	Mobilization	1.000	LS		185,000.00	185,728.25	88,000.00
0620	621-A001	Field Laboratory	1.000	EA		12,000.00	7,000.00	10,000.00
0630	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	82.000	EA		5.00	5.00	10.00
0640	628-J002	6" High Performance Cold Plastic Traffic Stripe, Continuous	640.000	LF		4.00	4.00	8.00
0650	628-L002	6" High Performance Cold Plastic Traffic Stripe, Skip Yellow	320.000	LF		4.25	4.25	8.00
0660	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	94.000	SF		25.00	25.00	25.00
0670	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	115.000	LBS		3.50	3.50	3.50
0680	630-F001	Delineators, Guard Rail, White	44.000	EA		18.00	18.00	18.00
0690	630-K003	Welded & Seamless Steel Pipe Posts, 4"	93.000	LF		55.00	55.00	55.00
0700	699-A001	Roadway Construction Stakes	1.000	LS		77,450.00	57,600.00	156,995.00
0710	907-213-A001	Agricultural Limestone	60.000	TON		100.00	100.00	70.00
0720	907-304-C001	Granular Material, AEA, Class 5, Group C	1,957.000	CY		17.00	12.80	25.00
0730	907-304-C005	Granular Material, AEA, Class 9, Group C	3,837.000	CY		5.50	7.68	12.00
0740	907-307-C003	6" Soil-Lime-Water Mixing, Class C	1,187.000	SY		2.15	2.15	1.60
0750	907-307-D001	Lime	16.000	TON		175.00	175.00	190.00
0760	907-403-A006	Hot Mix Asphalt, MT, 12.5-mm mixture	2,105.000	TON		87.44	87.44	95.00
0770	907-403-A007	Hot Mix Asphalt, MT, 19-mm mixture	4,733.000	TON		78.50	78.50	76.00
0780	907-601-B003	Class "B" Structural Concrete, Minor Structures	1.000	CY		1,100.00	985.60	1,100.00

NEWTON (51)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	N. L. Carson Construction Company, Inc.	Magco, Inc.	Joe McGee Construction Company, Inc.
Bridge replacement, on MS. Hwy. 15 between Decatur and Union, known as Federal Aid Project No. BR-0022-02(042) / 104129301, in the County of Newton, State of Mississippi.					\$3,980,787.29	\$3,168,300.94	\$3,220,885.13	\$3,441,856.39
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0790	907-603-ALT01	18" Type A Alternate Pipe	168.000	LF		18.00	40.96	16.70
0800	907-617-A001	Right-of-Way Marker	32.000	EA		228.00	300.00	50.00
0810	907-618-D001	Construction and Removal of Detour Road	1.000	LS		550,000.00	695,040.00	730,000.00
0820	907-626-C004	6" Thermoplastic Edge Stripe, Continuous White	2.000	MI		2,200.00	2,200.00	2,500.00
0830	907-626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	1.000	MI		450.00	450.00	1,500.00
0840	907-626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	1.000	MI		2,450.00	2,450.00	2,500.00
0850	907-626-G004	Thermoplastic Detail Stripe, White	504.000	LF		0.75	0.75	2.00
0860	907-626-H004	Thermoplastic Legend, White	102.000	LF		2.00	2.00	5.00
0870	907-804-B001	Box Bridge Concrete, Class B	452.000	CY		300.00	372.48	360.00
0880	907-308-A001	Portland Cement	138.000	TON		150.00	150.00	140.00
0890	907-308-B001	Soil-Cement-Water Mixing, Optional Mixers, Base	11,873.000	SY		2.15	2.15	1.60
0900	907-311-A003	Processing Lime and Fly Ash Treated Course, 6" Thick	11,873.000	SY				
0910	907-311-B001	Lime	91.000	TON				
0920	907-311-C001	Fly Ash, Class C	366.000	TON				
0930	907-308-A001	Portland Cement	90.000	TON		150.00	150.00	140.00
0940	907-308-B002	Soil-Cement-Water Mixing, Optional Mixers, Design Soil	10,686.000	SY		2.15	2.15	1.60
0950	907-311-A003	Processing Lime and Fly Ash Treated Course, 6" Thick	10,686.000	SY				
0960	907-311-B001	Lime	72.000	TON				
0970	907-311-C001	Fly Ash, Class C	289.000	TON				
0980	501-K001	Transverse Grooving	1,067.000	SY		2.61	2.62	2.60
0990	803-B001	Conventional Static Loading Test	4.000	EA		5,000.00	5,000.00	5,000.00
1000	803-D002	HP 12 x 53 Steel Piling	1,615.000	LF		34.00	47.36	38.50
1010	803-D003	HP 14 x 73 Steel Piling	1,155.000	LF		42.00	62.72	47.40
1020	803-F009	20" Pre-Formed Pile Hole	784.000	LF		15.00	10.00	1.00
1030	803-I001	PDA Test Pile	4.000	EA		5,500.00	5,760.00	7,650.00
1040	803-J001	Pile Restrike	4.000	EA		750.00	1,280.00	1.00

NEWTON (51)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	N. L. Carson Construction Company, Inc.	Magco, Inc.	Joe McGee Construction Company, Inc.
Bridge replacement, on MS. Hwy. 15 between Decatur and Union, known as Federal Aid Project No. BR-0022-02(042) / 104129301, in the County of Newton, State of Mississippi.					\$3,980,787.29	\$3,168,300.94	\$3,220,885.13	\$3,441,856.39
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
1050	805-A001	Reinforcement	78,528.000	LBS		0.67	0.69	0.75
1060	813-A001	Concrete Railing	486.000	LF		43.00	39.70	50.00
1070	815-A009	Loose Riprap, Size 300	797.000	TON		42.00	49.92	46.85
1080	815-E001	Geotextile under Riprap	572.000	SY		2.20	1.92	3.50
1090	907-804-A001	Bridge Concrete, Class AA	482.000	CY		487.00	499.20	500.00
1100	907-804-C016	40' Prestressed Concrete Beam, Type I+2	1,424.000	LF		89.50	71.68	59.50

NEWTON (51)					Key, LLC			
Bridge replacement, on MS. Hwy. 15 between Decatur and Union, known as Federal Aid Project No. BR-0022-02(042) / 104129301, in the County of Newton, State of Mississippi.					\$3,596,048.66			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0010	201-A001	Clearing and Grubbing	1.000	LS	45,000.00			
0020	201-B001	Clearing and Grubbing	1.000	ACRE	5,000.00			
0030	202-A001	Removal of Obstructions	1.000	LS	15,000.00			
0040	202-B025	Removal of Concrete Paved Ditch	73.000	SY	20.00			
0050	202-B076	Removal of Traffic Stripe	2,900.000	LF	1.50			
0060	202-B078	Removal of Pavement, All Types and Depths	7,699.000	SY	4.00			
0070	202-B094	Removal of Curb &/or Curb and Gutter, All Types	149.000	LF	10.00			
0080	202-B102	Removal of Guard Rail	1,120.000	LF	3.00			
0090	202-B106	Removal of Pipe, All Sizes	120.000	LF	12.00			
0100	202-B140	Removal of Box Bridge Headwall	2.000	EA	750.00			
0110	202-B161	Removal of Existing Sign	1.000	EA	1,000.00			
0120	203-EX033	Borrow Excavation, AH, FME, Class B17	34,049.000	CY	6.80			
0130	203-G003	Excess Excavation, FM, AH	100.000	CY	15.00			
0140	206-A001	Structure Excavation	416.000	CY	8.50			
0150	206-B001	Select Material for Undercuts, Contractor Furnished, FM	114.000	CY	35.00			
0160	212-A001	Light Ground Preparation	48,412.000	SY	0.01			
0170	212-B001	Standard Ground Preparation	96,824.000	SY	0.07			
0180	213-B001	Combination Fertilizer, 13-13-13	13.000	TON	650.00			
0190	213-C001	Superphosphate	10.000	TON	400.00			
0200	214-A002	Seeding, Bermudagrass	400.000	LBS	10.00			
0210	214-A003	Seeding, Tall Fescue	200.000	LBS	5.00			
0220	214-A004	Seeding, Crimson Clover	200.000	LBS	5.00			
0230	214-A014	Seeding, Browntop Millet	200.000	LBS	0.20			
0240	214-A015	Seeding, Oats	900.000	LBS	0.20			
0250	214-A017	Seeding, Rye Grass	250.000	LBS	1.00			
0260	215-A001	Vegetative Materials for Mulch	50.000	TON	200.00			

NEWTON (51)					Key, LLC			
Bridge replacement, on MS. Hwy. 15 between Decatur and Union, known as Federal Aid Project No. BR-0022-02(042) / 104129301, in the County of Newton, State of Mississippi.					\$3,596,048.66			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0270	216-A001	Solid Sodding	948.000	SY	6.00			
0280	217-A001	Ditch Liner	253.000	SY	2.00			
0290	219-A001	Watering	19.000	KGAL	20.00			
0300	220-A001	Insect Pest Control	10.000	ACRE	30.00			
0310	221-A001	Portland Cement Concrete Paved Ditch	24.000	CY	575.00			
0320	223-A001	Mowing	1.000	ACRE	40.00			
0330	224-A001	Soil Reinforcing Mat	1,851.000	SY	6.00			
0340	234-A001	Temporary Silt Fence	5,253.000	LF	4.00			
0350	235-A001	Temporary Erosion Checks	1,015.000	BALE	10.00			
0360	239-A001	Temporary Slope Drains	235.000	LF	12.00			
0370	406-A001	Cold Milling of Bituminous Pavement, All Depths	1,867.000	SY	10.00			
0380	408-A003	Asphalt for Prime Coat, Cut-Back MC-70 or Emulsified EA-1	992.000	GAL	1.00			
0390	501-E001	Expansion Joints, Without Dowels	180.000	LF	9.00			
0400	501-K001	Transverse Grooving	400.000	SY	2.50			
0410	502-A001	Reinforced Cement Concrete Bridge End Pavement	400.000	SY	120.00			
0420	602-A001	Reinforcing Steel	73,548.000	LBS	0.85			
0430	606-B001	Guard Rail, Class A, Type 1	850.000	LF	21.00			
0440	606-D015	Guard Rail, Bridge End Section	8.000	EA	2,350.00			
0450	606-E002	Guard Rail, Terminal End Section, Flared	8.000	EA	2,150.00			
0460	609-D002	Combination Concrete Curb and Gutter Type 2	52.000	LF	28.50			
0470	618-A001	Maintenance of Traffic	1.000	LS	35,000.00			
0480	618-C001	Construction & Removal of Detour Bridge	1.000	LS	130,000.00			
0490	619-A1002	Temporary Traffic Stripe, Continuous White	4.000	MI	450.00			
0500	619-A2002	Temporary Traffic Stripe, Continuous Yellow	1.000	MI	450.00			
0510	619-A2006	Temporary Traffic Stripe, Continuous Yellow, Type 1 or 2 Tap	1.000	MI	3,500.00			
0520	619-A4006	Temporary Traffic Stripe, Skip Yellow	1.000	MI	800.00			

NEWTON (51)					Key, LLC			
Bridge replacement, on MS. Hwy. 15 between Decatur and Union, known as Federal Aid Project No. BR-0022-02(042) / 104129301, in the County of Newton, State of Mississippi.					\$3,596,048.66			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0530	619-A6001	Temporary Traffic Stripe, Legend	204.000	LF	0.50			
0540	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	156.000	EA	5.00			
0550	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	245.000	SF	10.00			
0560	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	632.000	SF	15.00			
0570	619-G4001	Barricades, Type III, Single Faced	336.000	LF	25.00			
0580	619-G4005	Barricades, Type III, Double Faced	102.000	LF	35.00			
0590	619-G5001	Free Standing Plastic Drums	119.000	EA	85.00			
0600	619-G7001	Warning Lights, Type "B"	5.000	EA	950.00			
0610	620-A001	Mobilization	1.000	LS	220,000.00			
0620	621-A001	Field Laboratory	1.000	EA	20,000.00			
0630	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	82.000	EA	5.00			
0640	628-J002	6" High Performance Cold Plastic Traffic Stripe, Continuous	640.000	LF	4.00			
0650	628-L002	6" High Performance Cold Plastic Traffic Stripe, Skip Yellow	320.000	LF	4.25			
0660	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	94.000	SF	25.00			
0670	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	115.000	LBS	3.50			
0680	630-F001	Delineators, Guard Rail, White	44.000	EA	18.00			
0690	630-K003	Welded & Seamless Steel Pipe Posts, 4"	93.000	LF	55.00			
0700	699-A001	Roadway Construction Stakes	1.000	LS	70,000.00			
0710	907-213-A001	Agricultural Limestone	60.000	TON	100.00			
0720	907-304-C001	Granular Material, AEA, Class 5, Group C	1,957.000	CY	33.60			
0730	907-304-C005	Granular Material, AEA, Class 9, Group C	3,837.000	CY	11.30			
0740	907-307-C003	6" Soil-Lime-Water Mixing, Class C	1,187.000	SY	2.15			
0750	907-307-D001	Lime	16.000	TON	175.00			
0760	907-403-A006	Hot Mix Asphalt, MT, 12.5-mm mixture	2,105.000	TON	87.44			
0770	907-403-A007	Hot Mix Asphalt, MT, 19-mm mixture	4,733.000	TON	78.50			
0780	907-601-B003	Class "B" Structural Concrete, Minor Structures	1.000	CY	1,100.00			

NEWTON (51)					Key, LLC			
Bridge replacement, on MS. Hwy. 15 between Decatur and Union, known as Federal Aid Project No. BR-0022-02(042) / 104129301, in the County of Newton, State of Mississippi.					\$3,596,048.66			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0790	907-603-ALT01	18" Type A Alternate Pipe	168.000	LF	35.00			
0800	907-617-A001	Right-of-Way Marker	32.000	EA	275.00			
0810	907-618-D001	Construction and Removal of Detour Road	1.000	LS	800,000.00			
0820	907-626-C004	6" Thermoplastic Edge Stripe, Continuous White	2.000	MI	2,200.00			
0830	907-626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	1.000	MI	450.00			
0840	907-626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	1.000	MI	2,450.00			
0850	907-626-G004	Thermoplastic Detail Stripe, White	504.000	LF	0.75			
0860	907-626-H004	Thermoplastic Legend, White	102.000	LF	2.00			
0870	907-804-B001	Box Bridge Concrete, Class B	452.000	CY	410.00			
0880	907-308-A001	Portland Cement	138.000	TON	150.00			
0890	907-308-B001	Soil-Cement-Water Mixing, Optional Mixers, Base	11,873.000	SY	2.15			
0900	907-311-A003	Processing Lime and Fly Ash Treated Course, 6" Thick	11,873.000	SY				
0910	907-311-B001	Lime	91.000	TON				
0920	907-311-C001	Fly Ash, Class C	366.000	TON				
0930	907-308-A001	Portland Cement	90.000	TON	150.00			
0940	907-308-B002	Soil-Cement-Water Mixing, Optional Mixers, Design Soil	10,686.000	SY	2.15			
0950	907-311-A003	Processing Lime and Fly Ash Treated Course, 6" Thick	10,686.000	SY				
0960	907-311-B001	Lime	72.000	TON				
0970	907-311-C001	Fly Ash, Class C	289.000	TON				
0980	501-K001	Transverse Grooving	1,067.000	SY	2.50			
0990	803-B001	Conventional Static Loading Test	4.000	EA	5,000.00			
1000	803-D002	HP 12 x 53 Steel Piling	1,615.000	LF	37.00			
1010	803-D003	HP 14 x 73 Steel Piling	1,155.000	LF	48.00			
1020	803-F009	20" Pre-Formed Pile Hole	784.000	LF	8.00			
1030	803-I001	PDA Test Pile	4.000	EA	7,000.00			
1040	803-J001	Pile Restrike	4.000	EA	500.00			

NEWTON (51)					Key, LLC			
Bridge replacement, on MS. Hwy. 15 between Decatur and Union, known as Federal Aid Project No. BR-0022-02(042) / 104129301, in the County of Newton, State of Mississippi.					\$3,596,048.66			
Ref#	SM Item	Item Description	Item Qty	Units	4			
1050	805-A001	Reinforcement	78,528.000	LBS	0.82			
1060	813-A001	Concrete Railing	486.000	LF	45.00			
1070	815-A009	Loose Riprap, Size 300	797.000	TON	57.00			
1080	815-E001	Geotextile under Riprap	572.000	SY	3.00			
1090	907-804-A001	Bridge Concrete, Class AA	482.000	CY	510.00			
1100	907-804-C016	40' Prestressed Concrete Beam, Type I+2	1,424.000	LF	70.00			