

ALCORN (2)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	APAC - Mississippi, Inc.		
Construction necessary to upgrade the intersection of US 72 and CR 218/306, known as Federal Aid Project No. HSIP-0007-01(075) / 105553301, in the County of Alcorn, State of Mississippi.					\$413,345.15	\$448,328.86		
Ref#	SM Item	Item Description	Item Qty	Units		1		
0010	201-A001	Clearing and Grubbing	1.000	LS		12,500.00		
0020	202-B125	Removal of Signal Pole Including Hardware and Wiring	4.000	EA		419.60		
0030	202-B161	Removal of Existing Sign	20.000	EA		100.00		
0040	202-B188	Removal of Concrete Curb	10.000	LF		50.00		
0050	202-B194	Removal of Sign Post and Footing	2.000	EA		200.00		
0060	203-A003	Unclassified Excavation, FM, AH	245.000	CY		18.00		
0070	203-G004	Excess Excavation, LVM, AH	8.000	CY		100.00		
0080	209-A004	Geotextile Stabilization, Type V, Non-Woven	457.000	SY		4.50		
0090	212-B001	Standard Ground Preparation	1,235.000	SY		1.50		
0100	213-B001	Combination Fertilizer, 13-13-13	1.000	TON		500.00		
0110	213-C001	Superphosphate	1.000	TON		500.00		
0120	214-A002	Seeding, Bermudagrass	6.000	LBS		50.00		
0130	214-A003	Seeding, Tall Fescue	7.000	LBS		50.00		
0140	214-A004	Seeding, Crimson Clover	3.000	LBS		50.00		
0150	215-A001	Vegetative Materials for Mulch	1.000	TON		500.00		
0160	216-A001	Solid Sodding	22.000	SY		10.00		
0170	219-A001	Watering	1.000	KGAL		20.00		
0180	220-A001	Insect Pest Control	1.000	ACRE		30.00		
0190	221-A001	Portland Cement Concrete Paved Ditch	2.000	CY		1,250.00		
0200	406-A001	Cold Milling of Bituminous Pavement, All Depths	10,476.000	SY		3.25		
0210	602-A001	Reinforcing Steel	477.000	LBS		0.90		
0220	618-A001	Maintenance of Traffic	1.000	LS		41,000.00		
0230	619-A3001	Temporary Traffic Stripe, Skip White	3,600.000	LF		0.50		
0240	619-A5001	Temporary Traffic Stripe, Detail	11,790.000	LF		0.40		
0250	619-A6001	Temporary Traffic Stripe, Legend	1,520.000	LF		0.75		
0260	619-A6002	Temporary Traffic Stripe, Legend	720.000	SF		2.00		

ALCORN (2)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	APAC - Mississippi, Inc.		
Construction necessary to upgrade the intersection of US 72 and CR 218/306, known as Federal Aid Project No. HSIP-0007-01(075) / 105553301, in the County of Alcorn, State of Mississippi.					\$413,345.15	\$448,328.86		
Ref#	SM Item	Item Description	Item Qty	Units		1		
0270	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	48.000	SF		10.00		
0280	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	256.000	SF		10.00		
0290	619-G4001	Barricades, Type III, Single Faced	24.000	LF		22.00		
0300	620-A001	Mobilization	1.000	LS		39,000.00		
0310	627-J001	Two-Way Clear Reflective High Performance Raised Markers	30.000	EA		10.00		
0320	627-K001	Red-Clear Reflective High Performance Raised Markers	111.000	EA		10.00		
0330	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	12.000	EA		10.00		
0340	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	69.000	SF		22.50		
0350	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	96.000	SF		24.50		
0360	630-B001	Interstate Directional Signs, Bolted Extruded Aluminum Panel	118.000	SF		28.00		
0370	630-C001	Steel U-Section Posts, 2.0 lb/ft	13.000	LF		8.50		
0380	630-C003	Steel U-Section Posts, 3.0 lb/ft	72.000	LF		9.50		
0390	630-D003	Structural Steel Beams, W6 x 9	95.000	LF		45.00		
0400	630-E001	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles	111.000	LBS		4.50		
0410	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	144.000	LBS		4.50		
0420	630-K001	Welded & Seamless Steel Pipe Posts, 3"	30.000	LF		45.00		
0430	630-K003	Welded & Seamless Steel Pipe Posts, 4"	87.000	LF		50.00		
0440	635-A001	Vehicle Loop Assemblies	744.000	LF		6.29		
0450	636-A003	Shielded Cable, 4 Conductor	2,000.000	LF		1.05		
0460	640-A016	Traffic Signal Heads, Type 1 LED	6.000	EA		1,518.95		
0470	640-A017	Traffic Signal Heads, Type 2 LED	2.000	EA		897.94		
0480	640-A018	Traffic Signal Heads, Type 3 LED	2.000	EA		1,563.01		
0490	640-A031	Traffic Signal Heads, Type 1A LED	3.000	EA		3,356.80		
0500	640-A043	Traffic Signal Heads, Type 2A LED	2.000	EA		3,461.70		
0510	640-A044	Traffic Signal Heads, Type 8Y LED	4.000	EA		314.70		
0520	642-A008	Solid State Traffic Actuated Controllers, Type 8A	1.000	EA		14,686.00		

ALCORN (2)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	APAC - Mississippi, Inc.		
Construction necessary to upgrade the intersection of US 72 and CR 218/306, known as Federal Aid Project No. HSIP-0007-01(075) / 105553301, in the County of Alcorn, State of Mississippi.							\$413,345.15	\$448,328.86
Ref#	SM Item	Item Description	Item Qty	Units		1		
0530	645-A001	Flasher Assembly	2.000	EA		209.80		
0540	647-A001	Pullbox, Type 1	9.000	EA		419.60		
0550	647-A002	Pullbox, Type 3	3.000	EA		524.50		
0560	647-A005	Pullbox, Type 2	2.000	EA		472.05		
0570	666-B016	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 7	900.000	LF		1.05		
0580	666-B023	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 8, 3	2,000.000	LF		2.31		
0590	666-D005	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG	300.000	LF		1.05		
0600	666-D011	Electric Cable, Aerial Supported in Conduit, IMSA 20-1, AWG	300.000	LF		2.31		
0610	668-A016	Traffic Signal Conduit, Underground, Type 4, 1"	1,600.000	LF		6.29		
0620	668-A018	Traffic Signal Conduit, Underground, Type 4, 2"	120.000	LF		6.82		
0630	668-B024	Traffic Signal Conduit, Underground Drilled or Jacked, Rolle	500.000	LF		11.54		
0640	668-B025	Traffic Signal Conduit, Underground Drilled or Jacked, Rolle	250.000	LF		12.59		
0650	668-C003	Traffic Signal Conduit, Aerial Supported, Type 1, 1"	300.000	LF		13.64		
0660	907-213-A001	Agricultural Limestone	1.000	TON		500.00		
0670	907-304-A008	Granular Material, LVM, Class 3, Group C	233.000	CY		39.75		
0680	907-304-H002	3/4" and Down Crushed Stone Base, LVM	175.000	CY		56.00		
0690	907-403-A002	Hot Mix Asphalt, HT, 19-mm mixture	91.000	TON		97.00		
0700	907-403-D001	Hot Mix Asphalt, HT, 12.5-mm mixture, Polymer Modified	36.000	TON		97.00		
0710	907-403-D004	Hot Mix Asphalt, HT, 9.5-mm mixture, Polymer Modified	891.000	TON		91.50		
0720	907-601-B003	Class "B" Structural Concrete, Minor Structures	8.000	CY		1,150.00		
0730	907-626-A004	6" Thermoplastic Traffic Stripe, Skip White	1,800.000	LF		2.00		
0740	907-626-G004	Thermoplastic Detail Stripe, White	3,590.000	LF		1.75		
0750	907-626-G005	Thermoplastic Detail Stripe, Yellow	2,305.000	LF		1.75		
0760	907-626-H004	Thermoplastic Legend, White	760.000	LF		2.50		
0770	907-626-H005	Thermoplastic Legend, White	360.000	SF		8.00		
0780	907-639-A019	Traffic Signal Equipment Pole, Type II, 17' Shaft, 70' Arm	2.000	EA		9,755.70		

ALCORN (2)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	APAC - Mississippi, Inc.		
Construction necessary to upgrade the intersection of US 72 and CR 218/306, known as Federal Aid Project No. HSIP-0007-01(075) / 105553301, in the County of Alcorn, State of Mississippi.					\$413,345.15	\$448,328.86		
Ref#	SM Item	Item Description	Item Qty	Units		1		
0790	907-639-A059	Traffic Signal Equipment Pole, Type III, 17' Shaft, 55' & 70	1.000	EA		11,643.90		
0800	907-639-A060	Traffic Signal Equipment Pole, Type V, 8' Shaft	2.000	EA		1,049.00		
0810	907-639-C002	Pole Foundations, 36" Diameter	4.000	CY		524.50		
0820	907-639-C004	Pole Foundations, 30" Diameter	4.000	CY		419.60		