

COPIAH (15)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Clear River Construction Company, Inc.	Broome, LLC	Hemphill Construction Company, Inc.
Construction necessary for Site Improvements on the Copiah County Rest Areas on I-55 northbound & southbound, known as Federal Aid Project Nos. STP/IM-0055-01(095) / 105571301, 302, 303 & 304, in the County of Copiah, State of Mississippi.					\$2,307,070.85	\$1,280,473.65	\$1,402,130.50	\$1,568,440.00
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS		10,000.00	28,000.00	3,124.00
0020	202-B005	Removal of Asphalt Pavement, All Depths	731.000	SY		3.00	3.10	8.70
0030	202-B025	Removal of Concrete Paved Ditch	16.000	SY		10.00	4.50	10.00
0040	202-B035	Removal of Concrete Sidewalk	861.000	SY		5.00	4.50	10.00
0050	202-B070	Removal of Sign Including Post & Footing	43.000	EA		10.00	35.00	227.00
0060	202-B076	Removal of Traffic Stripe	4,580.000	LF		1.05	1.00	1.06
0070	202-B081	Removal of Continuously Reinforced Concrete Pavement, 8-inch	131.000	SY		15.00	20.00	10.40
0080	202-B093	Removal of Curb & Gutter, All Types	1,199.000	LF		2.50	2.50	10.00
0090	202-B106	Removal of Pipe, All Sizes	12.000	LF		10.00	10.00	16.70
0100	202-B186	Removal of Low Mast Lighting Assembly and Foundation	79.000	EA		177.00	171.00	176.30
0110	202-B247	Removal of Pull Box	12.000	EA		110.00	31.00	37.00
0120	202-B270	Removal of Flower Planter	450.000	LF		4.00	4.00	10.70
0130	203-A003	Unclassified Excavation, FM, AH	1,014.000	CY		10.00	12.00	19.00
0140	211-B001	Topsoil for Slope Treatment, Contractor Furnished	10.000	CY		35.00	35.00	42.00
0150	211-C001	Topsoil for Plant Holes, Contractor Furnished	35.000	CY		42.00	40.00	42.00
0160	212-B001	Standard Ground Preparation	1,121.000	SY		0.55	1.10	0.55
0170	213-B001	Combination Fertilizer, 13-13-13	2.000	TON		887.00	690.00	882.00
0180	213-B002	Combination Fertilizer, 8-8-8	2.000	TON		887.00	690.00	882.00
0190	216-B005	Solid Sodding, 419 Hybrid Bermuda	2,776.000	SY		3.75	4.30	4.00
0200	221-A001	Portland Cement Concrete Paved Ditch	3.000	CY		350.00	360.00	228.00
0210	232-A002	Fertilizer for Woody Plant Material, Tablet, 21 gram	2.000	K		220.00	400.00	20.00
0220	232-A003	Fertilizer for Woody Plant Material, Tablet, 10 gram	2.000	K		220.00	300.00	220.00
0230	234-A001	Temporary Silt Fence	1,770.000	LF		2.50	2.90	2.75
0240	235-A001	Temporary Erosion Checks	10.000	BALE		10.00	13.90	9.00
0250	501-D001	Expansion Joints, With Dowels	481.000	LF		8.50	8.80	11.00
0260	503-C005	Saw Cut, 8-inch	1,141.000	LF		9.75	9.90	8.90

COPIAH (15)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Clear River Construction Company, Inc.	Broome, LLC	Hemphill Construction Company, Inc.
Construction necessary for Site Improvements on the Copiah County Rest Areas on I-55 northbound & southbound, known as Federal Aid Project Nos. STP/IM-0055-01(095) / 105571301, 302, 303 & 304, in the County of Copiah, State of Mississippi.					\$2,307,070.85	\$1,280,473.65	\$1,402,130.50	\$1,568,440.00
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0270	608-B001	Concrete Sidewalk, With Reinforcement	235.000	SY		32.00	39.00	60.00
0280	608-B001	Concrete Sidewalk, With Reinforcement	477.000	SY		38.50	50.00	82.00
0290	609-C001	Concrete Curb, Integral, Type 1	1,160.000	LF		6.00	8.00	20.00
0300	619-D4001	Directional Signs	116.000	SF		38.00	36.00	50.00
0310	620-A001	Mobilization	1.000	LS		18,500.00	125,500.00	35,855.00
0320	628-O001	High Performance Cold Plastic Detail Stripe, White	2,498.000	LF		4.00	4.00	3.90
0330	628-O002	High Performance Cold Plastic Detail Stripe, Yellow	1,268.000	LF		4.00	4.00	3.90
0340	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	122.000	SF		37.00	35.00	37.00
0350	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	234.000	SF		37.00	35.00	37.00
0360	630-C003	Steel U-Section Posts, 3.0 lb/ft	576.000	LF		10.00	9.50	10.00
0370	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	262.000	LBS		4.80	4.50	4.70
0380	630-K003	Welded & Seamless Steel Pipe Posts, 4"	62.000	LF		68.50	65.00	68.50
0390	666-B023	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 8, 3	2,600.000	LF		7.75	3.95	7.70
0400	666-B041	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 6, 3	6,600.000	LF		8.30	4.90	8.25
0410	682-A031	Underground Branch Circuit, AWG 6, 3 Conductor	415.000	LF		7.75	9.25	7.70
0420	682-A036	Underground Branch Circuit, AWG 8, 3 Conductor	475.000	LF		7.50	8.65	7.50
0430	682-D001	Underground Pull Box	58.000	EA		875.00	623.00	990.00
0440	684-A003	Pole Foundation, 24" Diameter	75.000	CY		276.00	804.00	275.00
0450	684-B003	Slip Casing, 24" Diameter	648.000	LF		0.55	5.75	0.55
0460	699-A001	Roadway Construction Stakes	1.000	LS		10,000.00	32,000.00	8,200.00
0470	907-203-I001	Site Grading	200.000	SY		5.00	2.50	6.50
0480	907-230-A001	Shrub Planting, Asiatic Jasmine	2,000.000	EA		3.85	5.00	3.90
0490	907-230-A011	Shrub Planting, Dwarf Yaupon Holly	88.000	EA		15.50	9.75	15.50
0500	907-230-A014	Shrub Planting, Homestead Purple Verbena	28.000	EA		6.50	6.00	6.60
0510	907-230-A045	Shrub Planting, Clara Indian Hawthorn	260.000	EA		15.50	9.75	15.50
0520	907-230-A053	Shrub Planting, Anthony Waterer Spiraea	18.000	EA		15.50	14.00	15.50

COPIAH (15)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Clear River Construction Company, Inc.	Broome, LLC	Hemphill Construction Company, Inc.
Construction necessary for Site Improvements on the Copiah County Rest Areas on I-55 northbound & southbound, known as Federal Aid Project Nos. STP/IM-0055-01(095) / 105571301, 302, 303 & 304, in the County of Copiah, State of Mississippi.					\$2,307,070.85	\$1,280,473.65	\$1,402,130.50	\$1,568,440.00
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0530	907-230-A097	Shrub Planting, Radtko Double Knockout Rose	20.000	EA		27.65	16.00	27.55
0540	907-230-A098	Shrub Planting, Purple Pixie Loropetalum	103.000	EA		27.65	9.75	27.55
0550	907-230-A099	Shrub Planting, Miss Huff Hardy Lantana	4.000	EA		11.00	5.25	11.00
0560	907-230-B007	Tree Planting, Natchez Crape Myrtle	8.000	EA		265.00	190.00	264.50
0570	907-230-B025	Tree Planting, Foster's Holly	8.000	EA		220.00	295.00	220.00
0580	907-230-B049	Tree Planting, Australis Sweetbay Magnolia	4.000	EA		335.00	450.00	330.00
0590	907-230-C001	Bed Edging	340.000	LF		3.35	4.75	3.30
0600	907-230-D001	Bed Preparation	3,625.000	SF		0.55	0.20	0.55
0610	907-233-A001	Tree Bark Mulch, Type III	35.000	CY		50.00	38.00	53.00
0620	907-233-A002	Tree Bark Mulch, Type V	2,555.000	CY		24.35	36.50	24.25
0630	907-258-A001	Charcoal Grill	2.000	EA		500.00	880.00	386.00
0640	907-258-D001	Wooden Picnic Table and Benches	5.000	EA		700.00	590.00	630.00
0650	907-258-E001	Trash Receptacle	20.000	EA		985.00	720.00	935.00
0660	907-258-F001	Water Hydrant	2.000	EA		1,200.00	400.00	2,230.00
0670	907-258-J001	Metal Bench	14.000	EA		1,550.00	1,550.00	1,520.00
0680	907-258-N001	Car Stop	6.000	EA		125.00	120.00	135.00
0690	907-258-PP016	Bollard	6.000	EA		500.00	480.00	313.00
0700	907-258-PP021	Travel Trailer Sewage Dump Station	2.000	EA		2,500.00	1,100.00	963.00
0710	907-258-PP022	Vending Building Thru Wall Unit	2.000	EA		2,500.00	1,808.00	2,085.00
0720	907-259-A001	Lighting Assembly, Nonlighted Bollard	4.000	EA		753.00	585.00	750.00
0730	907-259-B001	Lighting Assembly, Bollards	14.000	EA		1,400.00	1,072.00	1,395.00
0740	907-259-C001	Lighting Assembly, Flag Pole Lighting	4.000	EA		970.00	808.00	964.00
0750	907-262-PP001	Waste Water Treatment Plant Maintenance/Rehabilitation	1.000	EA		147,000.00	128,100.00	171,800.00
0760	907-282-A001	Sprinkler Head, 1812-PRS-15Q	8.000	EA		42.00	25.50	42.00
0770	907-282-A002	Sprinkler Head, 1812-PRS-15H	13.000	EA		42.00	25.50	42.00
0780	907-282-A004	Sprinkler Head, 1812-PRS-15EST	38.000	EA		42.00	25.50	42.00

COPIAH (15)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Clear River Construction Company, Inc.	Broome, LLC	Hemphill Construction Company, Inc.
Construction necessary for Site Improvements on the Copiah County Rest Areas on I-55 northbound & southbound, known as Federal Aid Project Nos. STP/IM-0055-01(095) / 105571301, 302, 303 & 304, in the County of Copiah, State of Mississippi.					\$2,307,070.85	\$1,280,473.65	\$1,402,130.50	\$1,568,440.00
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0790	907-282-A006	Sprinkler Head, 1812-PRS-15CST	17.000	EA		42.00	25.50	42.00
0800	907-282-A007	Sprinkler Head, 1804-PRS-15Q	23.000	EA		42.00	16.00	42.00
0810	907-282-A008	Sprinkler Head, 1804-PRS-15H	34.000	EA		42.00	16.00	42.00
0820	907-282-A014	Sprinkler Head, 1804-PRS-15TQ	3.000	EA		42.00	16.00	42.00
0830	907-282-A015	Sprinkler Head, 1804-PRS-15F	15.000	EA		42.00	16.00	42.00
0840	907-282-A053	Sprinkler Head, 1804-PRS-15T	2.000	EA		42.00	16.00	42.00
0850	907-282-A064	Sprinkler Head, 1804-PRS-15EST	2.000	EA		42.00	16.00	42.00
0860	907-282-B001	Piping, 1/2" Diameter	845.000	LF		0.45	0.35	10.50
0870	907-282-B002	Piping, 3/4" Diameter	646.000	LF		0.65	0.40	0.70
0880	907-282-B003	Piping, 1" Diameter	252.000	LF		0.90	0.70	0.90
0890	907-282-B004	Piping, 1 1/4" Diameter	269.000	LF		1.40	0.80	1.40
0900	907-282-B005	Piping, 1 1/2" Diameter	21.000	LF		4.45	4.00	4.40
0910	907-282-B006	Piping, 2" Diameter	153.000	LF		4.45	2.15	4.40
0920	907-282-C002	Sleeves, 4"	271.000	LF		7.50	10.00	7.50
0930	907-282-D001	Valve Control Wire	1,024.000	LF		0.55	0.30	0.55
0940	907-282-E001	Trench Excavation and Backfill	2,446.000	LF		0.55	0.90	0.55
0950	907-282-G004	Electric Controller, 8 Station	2.000	EA		555.00	534.00	550.00
0960	907-282-H002	Electric Control Valve, 1 1/2"	4.000	EA		135.00	180.00	132.00
0970	907-282-H003	Electric Control Valve, 2"	4.000	EA		166.00	215.00	165.00
0980	907-282-I001	Backflow Preventer, 2"	2.000	EA		775.00	800.00	771.00
0990	907-282-J004	Isolation Valve, 2"	2.000	EA		166.00	295.00	165.00
1000	907-282-K001	Quick Coupler Key with Hose and Swivel	2.000	EA		245.00	310.00	242.50
1010	907-290-A001	Flagpole	4.000	EA		1,800.00	2,814.00	2,560.00
1020	907-304-A003	Granular Material, LVM, Class 6, Group D	1,200.000	CY		16.50	11.80	22.00
1030	907-307-C003	6" Soil-Lime-Water Mixing, Class C	2,557.000	SY		4.50	6.75	2.40
1040	907-307-D001	Lime	35.000	TON		180.00	200.00	187.00

COPIAH (15)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Clear River Construction Company, Inc.	Broome, LLC	Hemphill Construction Company, Inc.
Construction necessary for Site Improvements on the Copiah County Rest Areas on I-55 northbound & southbound, known as Federal Aid Project Nos. STP/IM-0055-01(095) / 105571301, 302, 303 & 304, in the County of Copiah, State of Mississippi.					\$2,307,070.85	\$1,280,473.65	\$1,402,130.50	\$1,568,440.00
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
1050	907-403-A001	Hot Mix Asphalt, HT, 12.5-mm mixture	782.000	TON		114.00	97.00	114.00
1060	907-501-A001	8" Reinforced Cement Concrete Pavement, Broom Finish	3,320.000	SY		55.00	60.00	70.00
1070	907-601-B003	Class "B" Structural Concrete, Minor Structures	10.000	CY		650.00	1,500.00	1,260.00
1080	907-605-U003	8" Non-perforated Pipe for Underdrains, PVC	48.000	LF		10.00	10.00	18.20
1090	907-607-PP007	Fence Slats, Vinyl	1.000	LS		5,000.00	2,080.00	6,000.00
1100	907-608-C001	Colored Concrete Sidewalk	667.000	SY		45.00	60.00	105.00
1110	907-608-E001	Exposed Aggregate Concrete Sidewalk	10.000	SY		50.00	52.00	123.00
1120	907-611-B001	Brick Pavers	1,008.000	SF		15.00	12.00	24.00
1130	907-626-G001	Thermoplastic Detail Stripe, Blue-ADA	509.000	LF		1.60	2.50	1.60
1140	907-626-G004	Thermoplastic Detail Stripe, White	459.000	LF		0.90	2.00	0.90
1150	907-626-H002	Thermoplastic Legend, Blue-ADA Handicap Symbol	6.000	EA		400.00	300.00	395.00
1160	907-626-H004	Thermoplastic Legend, White	193.000	LF		2.10	4.00	2.10
1170	907-630-PP001	Handicap Parking Sign with Post	6.000	EA		300.00	225.00	275.00
1180	907-683-B012	Lighting Assembly, Low Mast, Type 30-1-12-400	44.000	EA		2,171.00	1,960.00	3,287.00
1190	907-683-B013	Lighting Assembly, Low Mast, Type 16-1-0-150	32.000	EA		3,085.00	1,990.00	3,067.00
1200	907-809-PP003	Modular Block Retaining Wall	1.000	LS		12,000.00	10,225.00	14,000.00

COPIAH (15)					Paul Jackson & Son, Inc.	Bulldog Construction Company, Inc.		
Construction necessary for Site Improvements on the Copiah County Rest Areas on I-55 northbound & southbound, known as Federal Aid Project Nos. STP/IM-0055-01(095) / 105571301, 302, 303 & 304, in the County of Copiah, State of Mississippi.					\$1,582,419.20	\$1,883,186.25		
Ref#	SM Item	Item Description	Item Qty	Units	4	5		
0010	201-A001	Clearing and Grubbing	1.000	LS	41,059.00	50,000.00		
0020	202-B005	Removal of Asphalt Pavement, All Depths	731.000	SY	9.06	12.00		
0030	202-B025	Removal of Concrete Paved Ditch	16.000	SY	7.25	37.75		
0040	202-B035	Removal of Concrete Sidewalk	861.000	SY	7.25	11.00		
0050	202-B070	Removal of Sign Including Post & Footing	43.000	EA	12.08	181.25		
0060	202-B076	Removal of Traffic Stripe	4,580.000	LF	1.21	1.50		
0070	202-B081	Removal of Continuously Reinforced Concrete Pavement, 8-inch	131.000	SY	12.08	30.25		
0080	202-B093	Removal of Curb & Gutter, All Types	1,199.000	LF	6.57	12.00		
0090	202-B106	Removal of Pipe, All Sizes	12.000	LF	12.08	18.25		
0100	202-B186	Removal of Low Mast Lighting Assembly and Foundation	79.000	EA	193.22	241.00		
0110	202-B247	Removal of Pull Box	12.000	EA	120.76	90.75		
0120	202-B270	Removal of Flower Planter	450.000	LF	5.12	14.50		
0130	203-A003	Unclassified Excavation, FM, AH	1,014.000	CY	8.76	30.25		
0140	211-B001	Topsoil for Slope Treatment, Contractor Furnished	10.000	CY	42.15	60.50		
0150	211-C001	Topsoil for Plant Holes, Contractor Furnished	35.000	CY	36.23	45.00		
0160	212-B001	Standard Ground Preparation	1,121.000	SY	0.22	0.75		
0170	213-B001	Combination Fertilizer, 13-13-13	2.000	TON	647.28	966.50		
0180	213-B002	Combination Fertilizer, 8-8-8	2.000	TON	614.67	966.50		
0190	216-B005	Solid Sodding, 419 Hybrid Bermuda	2,776.000	SY	4.23	4.50		
0200	221-A001	Portland Cement Concrete Paved Ditch	3.000	CY	105.00	604.00		
0210	232-A002	Fertilizer for Woody Plant Material, Tablet, 21 gram	2.000	K	156.99	237.50		
0220	232-A003	Fertilizer for Woody Plant Material, Tablet, 10 gram	2.000	K	150.95	237.50		
0230	234-A001	Temporary Silt Fence	1,770.000	LF	3.02	7.00		
0240	235-A001	Temporary Erosion Checks	10.000	BALE	12.08	30.25		
0250	501-D001	Expansion Joints, With Dowels	481.000	LF	4.83	9.00		
0260	503-C005	Saw Cut, 8-inch	1,141.000	LF	9.18	10.00		

COPIAH (15)					Paul Jackson & Son, Inc.	Bulldog Construction Company, Inc.		
Construction necessary for Site Improvements on the Copiah County Rest Areas on I-55 northbound & southbound, known as Federal Aid Project Nos. STP/IM-0055-01(095) / 105571301, 302, 303 & 304, in the County of Copiah, State of Mississippi.					\$1,582,419.20	\$1,883,186.25		
Ref#	SM Item	Item Description	Item Qty	Units	4	5		
0270	608-B001	Concrete Sidewalk, With Reinforcement	235.000	SY	44.99	65.25		
0280	608-B001	Concrete Sidewalk, With Reinforcement	477.000	SY	84.78	76.00		
0290	609-C001	Concrete Curb, Integral, Type 1	1,160.000	LF	7.25	9.75		
0300	619-D4001	Directional Signs	116.000	SF	30.19	90.50		
0310	620-A001	Mobilization	1.000	LS	52,373.00	80,000.00		
0320	628-O001	High Performance Cold Plastic Detail Stripe, White	2,498.000	LF	4.53	4.50		
0330	628-O002	High Performance Cold Plastic Detail Stripe, Yellow	1,268.000	LF	4.53	4.50		
0340	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	122.000	SF	42.27	41.50		
0350	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	234.000	SF	42.27	41.50		
0360	630-C003	Steel U-Section Posts, 3.0 lb/ft	576.000	LF	11.48	11.25		
0370	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	262.000	LBS	5.44	5.50		
0380	630-K003	Welded & Seamless Steel Pipe Posts, 4"	62.000	LF	78.50	77.25		
0390	666-B023	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 8, 3	2,600.000	LF	8.46	6.25		
0400	666-B041	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 6, 3	6,600.000	LF	9.06	7.50		
0410	682-A031	Underground Branch Circuit, AWG 6, 3 Conductor	415.000	LF	8.46	9.50		
0420	682-A036	Underground Branch Circuit, AWG 8, 3 Conductor	475.000	LF	8.22	9.00		
0430	682-D001	Underground Pull Box	58.000	EA	1,086.84	1,191.00		
0440	684-A003	Pole Foundation, 24" Diameter	75.000	CY	302.00	483.25		
0450	684-B003	Slip Casing, 24" Diameter	648.000	LF	0.61	12.00		
0460	699-A001	Roadway Construction Stakes	1.000	LS	19,322.00	47,500.00		
0470	907-203-I001	Site Grading	200.000	SY	6.04	12.00		
0480	907-230-A001	Shrub Planting, Asiatic Jasmine	2,000.000	EA	4.11	4.25		
0490	907-230-A011	Shrub Planting, Dwarf Yaupon Holly	88.000	EA	11.72	17.00		
0500	907-230-A014	Shrub Planting, Homestead Purple Verbena	28.000	EA	4.84	7.25		
0510	907-230-A045	Shrub Planting, Clara Indian Hawthorn	260.000	EA	11.72	17.00		
0520	907-230-A053	Shrub Planting, Anthony Waterer Spiraea	18.000	EA	16.91	17.00		

COPIAH (15)					Paul Jackson & Son, Inc.	Bulldog Construction Company, Inc.		
Construction necessary for Site Improvements on the Copiah County Rest Areas on I-55 northbound & southbound, known as Federal Aid Project Nos. STP/IM-0055-01(095) / 105571301, 302, 303 & 304, in the County of Copiah, State of Mississippi.					\$1,582,419.20	\$1,883,186.25		
Ref#	SM Item	Item Description	Item Qty	Units	4	5		
0530	907-230-A097	Shrub Planting, Radtko Double Knockout Rose	20.000	EA	19.32	30.25		
0540	907-230-A098	Shrub Planting, Purple Pixie Loropetalum	103.000	EA	11.72	30.25		
0550	907-230-A099	Shrub Planting, Miss Huff Hardy Lantana	4.000	EA	4.84	12.00		
0560	907-230-B007	Tree Planting, Natchez Crape Myrtle	8.000	EA	153.97	290.00		
0570	907-230-B025	Tree Planting, Foster's Holly	8.000	EA	226.43	241.75		
0580	907-230-B049	Tree Planting, Australis Sweetbay Magnolia	4.000	EA	256.62	362.50		
0590	907-230-C001	Bed Edging	340.000	LF	3.63	3.75		
0600	907-230-D001	Bed Preparation	3,625.000	SF	0.18	0.75		
0610	907-233-A001	Tree Bark Mulch, Type III	35.000	CY	21.74	58.00		
0620	907-233-A002	Tree Bark Mulch, Type V	2,555.000	CY	26.57	26.50		
0630	907-258-A001	Charcoal Grill	2.000	EA	313.98	906.00		
0640	907-258-D001	Wooden Picnic Table and Benches	5.000	EA	374.34	2,416.00		
0650	907-258-E001	Trash Receptacle	20.000	EA	567.58	1,933.00		
0660	907-258-F001	Water Hydrant	2.000	EA	1,118.00	3,020.00		
0670	907-258-J001	Metal Bench	14.000	EA	1,304.21	3,020.00		
0680	907-258-N001	Car Stop	6.000	EA	30.19	90.75		
0690	907-258-PP016	Bollard	6.000	EA	237.90	302.00		
0700	907-258-PP021	Travel Trailer Sewage Dump Station	2.000	EA	1,450.00	4,832.00		
0710	907-258-PP022	Vending Building Thru Wall Unit	2.000	EA	293.45	7,250.00		
0720	907-259-A001	Lighting Assembly, Nonlighted Bollard	4.000	EA	706.45	725.00		
0730	907-259-B001	Lighting Assembly, Bollards	14.000	EA	1,294.55	1,329.00		
0740	907-259-C001	Lighting Assembly, Flag Pole Lighting	4.000	EA	975.75	1,027.00		
0750	907-262-PP001	Waste Water Treatment Plant Maintenance/Rehabilitation	1.000	EA	177,892.00	181,215.00		
0760	907-282-A001	Sprinkler Head, 1812-PRS-15Q	8.000	EA	30.80	46.00		
0770	907-282-A002	Sprinkler Head, 1812-PRS-15H	13.000	EA	30.80	46.00		
0780	907-282-A004	Sprinkler Head, 1812-PRS-15EST	38.000	EA	30.80	46.00		

COPIAH (15)					Paul Jackson & Son, Inc.	Bulldog Construction Company, Inc.		
Construction necessary for Site Improvements on the Copiah County Rest Areas on I-55 northbound & southbound, known as Federal Aid Project Nos. STP/IM-0055-01(095) / 105571301, 302, 303 & 304, in the County of Copiah, State of Mississippi.					\$1,582,419.20	\$1,883,186.25		
Ref#	SM Item	Item Description	Item Qty	Units	4	5		
0790	907-282-A006	Sprinkler Head, 1812-PRS-15CST	17.000	EA	30.80	46.00		
0800	907-282-A007	Sprinkler Head, 1804-PRS-15Q	23.000	EA	19.32	46.00		
0810	907-282-A008	Sprinkler Head, 1804-PRS-15H	34.000	EA	19.32	46.00		
0820	907-282-A014	Sprinkler Head, 1804-PRS-15TQ	3.000	EA	19.32	46.00		
0830	907-282-A015	Sprinkler Head, 1804-PRS-15F	15.000	EA	19.32	46.00		
0840	907-282-A053	Sprinkler Head, 1804-PRS-15T	2.000	EA	19.32	46.00		
0850	907-282-A064	Sprinkler Head, 1804-PRS-15EST	2.000	EA	19.32	46.00		
0860	907-282-B001	Piping, 1/2" Diameter	845.000	LF	0.43	0.50		
0870	907-282-B002	Piping, 3/4" Diameter	646.000	LF	0.49	0.75		
0880	907-282-B003	Piping, 1" Diameter	252.000	LF	0.85	1.00		
0890	907-282-B004	Piping, 1 1/4" Diameter	269.000	LF	0.97	1.50		
0900	907-282-B005	Piping, 1 1/2" Diameter	21.000	LF	2.35	5.00		
0910	907-282-B006	Piping, 2" Diameter	153.000	LF	2.35	5.00		
0920	907-282-C002	Sleeves, 4"	271.000	LF	7.53	8.25		
0930	907-282-D001	Valve Control Wire	1,024.000	LF	0.16	1.00		
0940	907-282-E001	Trench Excavation and Backfill	2,446.000	LF	0.61	1.00		
0950	907-282-G004	Electric Controller, 8 Station	2.000	EA	644.86	604.00		
0960	907-282-H002	Electric Control Valve, 1 1/2"	4.000	EA	144.92	145.00		
0970	907-282-H003	Electric Control Valve, 2"	4.000	EA	181.14	181.25		
0980	907-282-I001	Backflow Preventer, 2"	2.000	EA	835.66	845.00		
0990	907-282-J004	Isolation Valve, 2"	2.000	EA	181.14	181.00		
1000	907-282-K001	Quick Coupler Key with Hose and Swivel	2.000	EA	177.52	266.00		
1010	907-290-A001	Flagpole	4.000	EA	1,536.07	3,625.00		
1020	907-304-A003	Granular Material, LVM, Class 6, Group D	1,200.000	CY	14.50	30.25		
1030	907-307-C003	6" Soil-Lime-Water Mixing, Class C	2,557.000	SY	6.65	8.50		
1040	907-307-D001	Lime	35.000	TON	241.52	241.75		

COPIAH (15)					Paul Jackson & Son, Inc.	Bulldog Construction Company, Inc.		
Construction necessary for Site Improvements on the Copiah County Rest Areas on I-55 northbound & southbound, known as Federal Aid Project Nos. STP/IM-0055-01(095) / 105571301, 302, 303 & 304, in the County of Copiah, State of Mississippi.					\$1,582,419.20	\$1,883,186.25		
Ref#	SM Item	Item Description	Item Qty	Units	4	5		
1050	907-403-A001	Hot Mix Asphalt, HT, 12.5-mm mixture	782.000	TON	150.95	128.25		
1060	907-501-A001	8" Reinforced Cement Concrete Pavement, Broom Finish	3,320.000	SY	84.78	90.75		
1070	907-601-B003	Class "B" Structural Concrete, Minor Structures	10.000	CY	105.00	664.50		
1080	907-605-U003	8" Non-perforated Pipe for Underdrains, PVC	48.000	LF	18.12	30.25		
1090	907-607-PP007	Fence Slats, Vinyl	1.000	LS	2,000.00	3,624.25		
1100	907-608-C001	Colored Concrete Sidewalk	667.000	SY	60.38	111.00		
1110	907-608-E001	Exposed Aggregate Concrete Sidewalk	10.000	SY	108.68	87.00		
1120	907-611-B001	Brick Pavers	1,008.000	SF	16.91	18.25		
1130	907-626-G001	Thermoplastic Detail Stripe, Blue-ADA	509.000	LF	1.82	1.75		
1140	907-626-G004	Thermoplastic Detail Stripe, White	459.000	LF	1.03	1.00		
1150	907-626-H002	Thermoplastic Legend, Blue-ADA Handicap Symbol	6.000	EA	452.85	445.00		
1160	907-626-H004	Thermoplastic Legend, White	193.000	LF	2.42	2.50		
1170	907-630-PP001	Handicap Parking Sign with Post	6.000	EA	120.76	362.50		
1180	907-683-B012	Lighting Assembly, Low Mast, Type 30-1-12-400	44.000	EA	2,928.00	2,307.50		
1190	907-683-B013	Lighting Assembly, Low Mast, Type 16-1-0-150	32.000	EA	2,778.00	2,356.00		
1200	907-809-PP003	Modular Block Retaining Wall	1.000	LS	14,159.11	14,500.00		