

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) further propose to execute the attached contract agreement (Section 902) as soon as the work is awarded to me (us), and to begin and complete the work within the time limit(s) provided for in the Specifications and Advertisement. I (We) also propose to execute the attached contract bond (Section 903) in an amount not less than one hundred (100) percent of the total of my (our) part, but also to guarantee the excellence of both workmanship and materials until the work is finally accepted.

I (We) enclose a certified check, cashier's check or bid bond for **five percent (5%) of total bid** and hereby agree that in case of my (our) failure to execute the contract and furnish bond within Ten (10) days after notice of award, the amount of this check (bid bond) will be forfeited to the State of Mississippi as liquidated damages arising out of my (our) failure to execute the contract as proposed. It is understood that in case I am (we are) not awarded the work, the check will be returned as provided in the Specifications.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. 1 DATED 3/16/2010 ADDENDUM NO. DATED
ADDENDUM NO. DATED ADDENDUM NO. DATED

Number	Description
1	Bidsheets, replace same; Revised or Added Plan Sht. Nos. 3, 6, 12, 26-32, 40-42, 48-53, 56-64, 75-79, 92-96, 100.10, 100.11, 100.34-100.36, 100.41-100.43, 100.49-100.51, 100.101-100.104; Amendment EBS Download Required.

TOTAL ADDENDA: 1
(Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

Contractor

BY _____
Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

_____ President	_____ Address
_____ Secretary	_____ Address
_____ Treasurer	_____ Address

The following is my (our) itemized proposal.

Revised 09/21/2005

STP-0063-02(026) / 105375301

Forrest County(ies)

Construction necessary to upgrade SR 42 east of Petal, known as Federal Aid Project No. STP-0063-02(026) / 105375301, in the County of Forrest, State of Mississippi.

I (We) agree to complete the entire project within the specified contract time.

***** SPECIAL NOTICE TO BIDDERS *****

**BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED.
 BIDS WILL NOT BE CONSIDERED UNLESS THE BID CERTIFICATION LOCATED AT THE END OF THE BID SHEETS IS SIGNED**

*****BID SCHEDULE*****

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Item Amount	
						Dollar	Ct	Dollar	Ct
Roadway Items									
0010	201-A001		1	Lump Sum	Clearing and Grubbing	XXXXXXXX	XXX		
0020	202-B002		8,631	Square Yard	Removal of Asphalt Driveways, All Depths				
0030	202-B005		16,794	Square Yard	Removal of Asphalt Pavement, All Depths				
0040	202-B017		76	Linear Feet	Removal of Concrete Combination Curb & Gutter				
0050	202-B024		14	Square Yard	Removal of Concrete Median & Island Pavement, All Depths				
0060	202-B057		1	Each	Removal of Inlets, All Sizes				
0070	202-B079		4	Each	Removal of Headwall				
0080	202-B106		4,305	Linear Feet	Removal of Pipe, All Sizes				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0090	202-B149		16	Mile	Removal of Traffic Stripe				
0100	203-A003	(E)	87,888	Cubic Yard	Unclassified Excavation, FM, AH				
0110	203-EX013	(E)	6,727	Cubic Yard	Borrow Excavation, AH, FME, Class B7				
0120	206-A001	(S)	6,139	Cubic Yard	Structure Excavation				
0130	206-B001	(E)	120	Cubic Yard	Select Material for Undercuts, Contractor Furnished, FM				
0140	209-A004		147,677	Square Yard	Geotextile Stabilization, Type V, Non-Woven				
0150	213-C001		22	Ton	Superphosphate				
0160	216-A001		24,200	Square Yard	Solid Sodding				
0170	217-A001		1,687	Square Yard	Ditch Liner				
0180	219-A001		89	Thousand Gallon	Watering	20.	00	1,780.	00
0190	220-A001		45	Acre	Insect Pest Control	30.	00	1,350.	00
0200	221-A001	(S)	489	Cubic Yard	Portland Cement Concrete Paved Ditch				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0210	223-A001		45	Acre	Mowing	40.	00	1,800.	00
0220	224-A001		212	Square Yard	Soil Reinforcing Mat				
0230	234-A001		16,500	Linear Feet	Temporary Silt Fence				
0240	235-A001		904	Bale	Temporary Erosion Checks				
0250	236-A002		7	Each	Silt Basin, Type B				
0260	236-A004		18	Each	Silt Basin, Type D				
0270	406-A001		25,000	Square Yard	Cold Milling of Bituminous Pavement, All Depths				
0280	503-C004		7,000	Linear Feet	Saw Cut, 7-inch				
0290	602-A001	(S)	71,355	Pounds	Reinforcing Steel				
0300	603-CA088	(S)	11,224	Linear Feet	18" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets				
0310	603-CA089	(S)	1,468	Linear Feet	24" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets				
0320	603-CA090	(S)	310	Linear Feet	30" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0330	603-CA091	(S)	72	Linear Feet	36" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets				
0340	603-CA107	(S)	76	Linear Feet	24" Reinforced Concrete Pipe, Class V, Jacked or Bored				
0350	603-CA125	(S)	112	Linear Feet	30" Reinforced Concrete Pipe, Class V, Jacked or Bored				
0360	603-CB001	(S)	6	Each	18" Reinforced Concrete End Section				
0370	603-CB002	(S)	10	Each	24" Reinforced Concrete End Section				
0380	603-CB003	(S)	7	Each	30" Reinforced Concrete End Section				
0390	603-CB004	(S)	2	Each	36" Reinforced Concrete End Section				
0400	603-CE039	(S)	156	Linear Feet	22" x 13" Concrete Arch Pipe, Class A III, Flexible Plastic Gaskets				
0410	603-CF001	(S)	1	Each	22" x 13" Concrete Arch Pipe End Section				
0420	604-A001		7,742	Pounds	Castings				
0430	604-B001		1,143	Pounds	Gratings				
0435	609-B001 Added 03/16/2010	(S)	1,600	Linear Feet	Concrete Curb, Header				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0440	609-D002	(S)	863	Linear Feet	Combination Concrete Curb and Gutter Type 2				
0450	609-D004	(S)	49,376	Linear Feet	Combination Concrete Curb and Gutter Type 3A Modified				
0460	614-A002	(S)	200	Square Yard	Concrete Driveway, Without Reinforcement, 6-inch Thickness				
0470	614-B002	(S)	450	Square Yard	Concrete Driveway, With Reinforcement, 6-inch Thickness				
0480	616-A001	(S)	16,759	Square Yard	Concrete Median and/or Island Pavement, 4-inch				
0490	616-A003	(S)	1,613	Square Yard	Concrete Median and/or Island Pavement, 10-inch				
0500	618-A001		1	Lump Sum	Maintenance of Traffic	XXXXXXXX	XXX		
0510	619-A1002		32	Mile	Temporary Traffic Stripe, Continuous White				
0520	619-A2002		32	Mile	Temporary Traffic Stripe, Continuous Yellow				
0530	619-A3006		10	Mile	Temporary Traffic Stripe, Skip White				
0540	619-A4001		4,246	Linear Feet	Temporary Traffic Stripe, Skip Yellow				
0550	619-A5001		48,508	Linear Feet	Temporary Traffic Stripe, Detail				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0560	619-A6001		7,279	Linear Feet	Temporary Traffic Stripe, Legend				
0570	619-A6002		3,429	Square Feet	Temporary Traffic Stripe, Legend				
0580	619-C7001		1,502	Each	Two-Way Yellow Reflective High Performance Raised Marker				
0590	619-D1001		379	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet				
0600	619-D2001		474	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More				
0610	619-G4001		30	Linear Feet	Barricades, Type III, Single Faced				
0620	619-G5001		1,032	Each	Free Standing Plastic Drums				
0630	619-G7001		6	Each	Warning Lights, Type "B"				
0640	620-A001		1	Lump Sum	Mobilization	XXXXXXXX	XXX		
0650	627-K001		1,237	Each	Red-Clear Reflective High Performance Raised Markers				
0660	627-L001		743	Each	Two-Way Yellow Reflective High Performance Raised Markers				
0670	630-A001		142	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0680	630-A002		491	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness				
0690	630-B001		63	Square Feet	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted				
0700	630-C003		569	Linear Feet	Steel U-Section Posts, 3.0 lb/ft				
0710	630-D003		94	Linear Feet	Structural Steel Beams, W6 x 9				
0720	630-E001		170	Pounds	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles				
0730	630-E004		341	Pounds	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar				
0740	630-K001		29	Linear Feet	Welded & Seamless Steel Pipe Posts, 3"				
0750	630-K003		244	Linear Feet	Welded & Seamless Steel Pipe Posts, 4"				
0760	635-A001		96	Linear Feet	Vehicle Loop Assemblies				
0770	636-A002		970	Linear Feet	Shielded Cable				
0780	638-A005		1	Each	Loop Detector Amplifier, Card Rack Mounted, 4 Channel				
0790	640-A016		8	Each	Traffic Signal Heads, Type 1 LED				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0800	640-A022		2	Each	Traffic Signal Heads, Type 7 LED				
0810	642-A008		1	Each	Solid State Traffic Actuated Controllers, Type 8A				
0820	644-A001		4	Each	Optical Detector				
0830	644-B001		760	Linear Feet	Optical Detector Cable				
0840	644-C002		1	Each	Phase Selector, 4 Channel				
0850	647-A001		3	Each	Pullbox, Type 1				
0860	647-A003		1	Each	Pullbox, Type 4				
0870	647-A005		3	Each	Pullbox, Type 2				
0880	648-A001		1	Each	Radio Interconnect, Installed in New Controller Cabinet				
0890	648-B001		1	Each	Radio Interconnect, Installed in Existing Controller Cabinet				
0900	666-B016		800	Linear Feet	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 7 Conductor				
0910	666-B022		180	Linear Feet	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 8, 2 Conductor				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0920	668-A016		324	Linear Feet	Traffic Signal Conduit, Underground, Type 4, 1"				
0930	668-A018		84	Linear Feet	Traffic Signal Conduit, Underground, Type 4, 2"				
0940	668-B023		500	Linear Feet	Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 1"				
0950	668-B025		312	Linear Feet	Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 3"				
0960	699-A001		1	Lump Sum	Roadway Construction Stakes	XXXXXXXXXX	XXX		
0970	907-225-A001		45	Acre	Grassing				
0980	907-225-B001		130	Ton	Agricultural Limestone				
0990	907-226-A001		23	Acre	Temporary Grassing				
1000	907-237-A002		1,070	Linear Feet	Wattles, 12"				
1010	907-237-A003		340	Linear Feet	Wattles, 20"				
1020	907-245-A001		340	Linear Feet	Triangular Silt Dike				
1030	907-246-A001		1,410	Linear Feet	Sandbags				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
1040	907-247-A001		5	Each	Temporary Stream Diversion				
1050	907-304-A003	(GY)	23,741	Cubic Yard	Granular Material, LVM, Class 6, Group D				
1060	907-304-F001	(GT)	39,400	Ton	Size 825 Crushed Stone Base				
1070	907-403-A001	(BA1)	7,875	Ton	Hot Mix Asphalt, HT, 12.5-mm mixture				
1080	907-403-A002	(BA1)	5,703	Ton	Hot Mix Asphalt, HT, 19-mm mixture				
1090	907-403-A006	(BA1)	1,641	Ton	Hot Mix Asphalt, MT, 12.5-mm mixture				
1100	907-403-A007	(BA1)	830	Ton	Hot Mix Asphalt, MT, 19-mm mixture				
1110	907-403-A010	(BA1)	1,231	Ton	Hot Mix Asphalt, MT, 9.5-mm mixture				
1120	907-403-A011	(BA1)	2,830	Ton	Hot Mix Asphalt, ST, 12.5-mm mixture				
1130	907-403-A012	(BA1)	26,867	Ton	Hot Mix Asphalt, ST, 19-mm mixture				
1140	907-403-A015	(BA1)	2,122	Ton	Hot Mix Asphalt, ST, 9.5-mm mixture				
1150	907-403-D001	(BA1)	18,738	Ton	Hot Mix Asphalt, HT, 12.5-mm mixture, Polymer Modified				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
1160	907-403-D002	(BA1)	5,703	Ton	Hot Mix Asphalt, HT, 19-mm mixture, Polymer Modified				
1170	907-403-D004	(BA1)	11,578	Ton	Hot Mix Asphalt, HT, 9.5-mm mixture, Polymer Modified				
1180	907-601-A001	(S)	81	Cubic Yard	Class "B" Structural Concrete				
1190	907-601-B003	(S)	247	Cubic Yard	Class "B" Structural Concrete, Minor Structures				
1200	907-603-ALT01	(S)	576	Linear Feet	18" Type A Alternate Pipe				
1210	907-617-A001		69	Each	Right-of-Way Marker				
1220	907-626-A003		6	Mile	6" Thermoplastic Traffic Stripe, Skip White				
1230	907-626-B004		1	Mile	6" Thermoplastic Traffic Stripe, Continuous White				
1240	907-626-C003		9	Mile	6" Thermoplastic Double Drop Edge Stripe, Continuous White				
1250	907-626-E004		4	Mile	6" Thermoplastic Traffic Stripe, Continuous Yellow				
1260	907-626-F003		4	Mile	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow				
1270	907-626-G004		10,216	Linear Feet	Thermoplastic Detail Stripe, White				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
1280	907-626-G005		13,128	Linear Feet	Thermoplastic Detail Stripe, Yellow				
1290	907-626-H004		2,370	Linear Feet	Thermoplastic Legend, White				
1300	907-626-H005		1,741	Square Feet	Thermoplastic Legend, White				
1310	907-639-A013		2	Each	Traffic Signal Equipment Pole, Type III, 17' Shaft, 50' & 50' Arms				
1320	907-639-C002		8	Cubic Yard	Pole Foundations, 36" Diameter				
1330	907-649-A004		4	Each	Video Detection System, 1 Sensor, Type 2				
1340	907-804-B001	(S)	403	Cubic Yard	Box Bridge Concrete, Class B				

*** BID CERTIFICATION ***

TOTAL BID.....\$_____

*** DBE/WBE SECTION ***

Complete item nos. 1, 2, and/or 3 as appropriate. See Notice to Bidders addressing Disadvantaged Business Enterprises in Highway Construction.

1. I/We agree that no less than _____ percent shall be expended with small business concerns owned and controlled by socially and economically disadvantaged individuals (DBE and WBE).
2. Classification of Bidder: Small Business (DBE)_____ Small Business (WBE)_____
3. A joint venture with a Small Business (DBE/WBE): _____

*** SIGNATURE STATEMENT ***

BIDDER ACKNOWLEDGES THAT HE/SHE HAS CHECKED ALL ITEMS IN THIS PROPOSAL FOR ACCURACY AND CERTIFIED THAT THE FIGURES SHOWN THEREIN CONSTITUTE THEIR OFFICIAL BID.

BIDDER'S SIGNATURE

BIDDER'S COMPANY

BIDDER'S FEDERAL TAX ID NUMBER