

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) further propose to execute the attached contract agreement (Section 902) as soon as the work is awarded to me (us), and to begin and complete the work within the time limit(s) provided for in the Specifications and Advertisement. I (We) also propose to execute the attached contract bond (Section 903) in an amount not less than one hundred (100) percent of the total of my (our) part, but also to guarantee the excellence of both workmanship and materials until the work is finally accepted.

I (We) enclose a certified check, cashier's check or bid bond for **five percent (5%) of total bid** and hereby agree that in case of my (our) failure to execute the contract and furnish bond within Ten (10) days after notice of award, the amount of this check (bid bond) will be forfeited to the State of Mississippi as liquidated damages arising out of my (our) failure to execute the contract as proposed. It is understood that in case I am (we are) not awarded the work, the check will be returned as provided in the Specifications.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. 1 DATED 11/15/2010 ADDENDUM NO. DATED
 ADDENDUM NO. DATED ADDENDUM NO. DATED

Number	Description
1	Bidsheets, replace same; Revised Plan Sheet Nos. 2, 14, & 16.1; Amendment EBS Download Required.

TOTAL ADDENDA: 1
 (Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

 Contractor

BY _____
 Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

_____ President	_____ Address
_____ Secretary	_____ Address
_____ Treasurer	_____ Address

The following is my (our) itemized proposal.

Revised 09/21/2005

STP-0540-00(005) / 100596301

Kemper County(ies)

Reconstruction of SR 16 between Scooba and the Alabama State Line, known as Federal Aid Project No. STP-0540-00(005) / 100596301, in the County of Kemper, State of Mississippi.

I (We) agree to complete the entire project within the specified contract time.

***** SPECIAL NOTICE TO BIDDERS *****

**BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED.
 BIDS WILL NOT BE CONSIDERED UNLESS THE BID CERTIFICATION LOCATED AT THE END OF THE BID SHEETS IS SIGNED**

*****BID SCHEDULE*****

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Item Amount	
						Dollar	Ct	Dollar	Ct
Roadway Items									
0010	201-A001		1	Lump Sum	Clearing and Grubbing	XXXXXXXX	XXX		
0020	201-B001		9	Acre	Clearing and Grubbing				
0030	202-B005		38,629	Square Yard	Removal of Asphalt Pavement, All Depths				
0040	202-B038		693	Linear Feet	Removal of Curb, All Types				
0050	202-B064		2,167	Linear Feet	Removal of Pipe, 8" And Above				
0060	202-B076		7,080	Linear Feet	Removal of Traffic Stripe				
0070	202-B102		1,000	Linear Feet	Removal of Guard Rail				
0080	203-A003	(E)	89,811	Cubic Yard	Unclassified Excavation, FM, AH				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0090	203-D001	(E)	1,000	Cubic Yard	Muck Excavation, FM				
0100	203-E058	(E)	4,392	Cubic Yard	Borrow Excavation, FM, Class B15, AH				
0110	203-G003	(E)	84,885	Cubic Yard	Excess Excavation, FM, AH				
0120	206-A001	(S)	3,146	Cubic Yard	Structure Excavation				
0130	206-B001	(E)	500	Cubic Yard	Select Material for Undercuts, Contractor Furnished, FM				
0140	209-A004		2,133	Square Yard	Geotextile Stabilization, Type V, Non-Woven				
0150	211-B001	(E)	29,443	Cubic Yard	Topsoil for Slope Treatment, Contractor Furnished				
0160	213-C001		37	Ton	Superphosphate				
0170	215-A001		146	Ton	Vegetative Materials for Mulch				
0180	216-A001		1,009	Square Yard	Solid Sodding				
0190	217-A001		4,555	Square Yard	Ditch Liner				
0200	219-A001 Changed 11/15/2010		20	Thousand Gallon	Watering	20.	00	400.	00

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0210	220-A001		37	Acre	Insect Pest Control	30.	00	1,110.	00
0220	221-A001	(S)	265	Cubic Yard	Portland Cement Concrete Paved Ditch				
0230	223-A001		1	Acre	Mowing	40.	00	40.	00
0240	224-A001		12,207	Square Yard	Soil Reinforcing Mat				
0250	234-A001		41,258	Linear Feet	Temporary Silt Fence				
0260	235-A001		1,344	Bale	Temporary Erosion Checks				
0270	239-A001		100	Linear Feet	Temporary Slope Drains				
0280	310-B001	(GY)	650	Cubic Yard	Size I Stabilizer Aggregate, Coarse				
0290	406-A001		11,000	Square Yard	Cold Milling of Bituminous Pavement, All Depths				
0300	408-A003	(A3)	481	Gallon	Asphalt for Prime Coat, Cut-Back MC-70 or Emulsified EA-1				
0310	423-A001		12	Mile	Rumble Strips, Ground In				
0320	602-A001	(S)	170	Pounds	Reinforcing Steel				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0330	603-CA003	(S)	364	Linear Feet	24" Reinforced Concrete Pipe, Class III				
0340	603-CA004	(S)	128	Linear Feet	30" Reinforced Concrete Pipe, Class III				
0350	603-CA005	(S)	176	Linear Feet	36" Reinforced Concrete Pipe, Class III				
0360	603-CA006	(S)	360	Linear Feet	42" Reinforced Concrete Pipe, Class III				
0370	603-CA007	(S)	892	Linear Feet	48" Reinforced Concrete Pipe, Class III				
0380	603-CA008	(S)	216	Linear Feet	54" Reinforced Concrete Pipe, Class III				
0390	603-CA107	(S)	80	Linear Feet	24" Reinforced Concrete Pipe, Class V, Jacked or Bored				
0400	603-CB002	(S)	12	Each	24" Reinforced Concrete End Section				
0410	603-CB003	(S)	2	Each	30" Reinforced Concrete End Section				
0420	603-CB004	(S)	4	Each	36" Reinforced Concrete End Section				
0430	603-CB005	(S)	8	Each	42" Reinforced Concrete End Section				
0440	603-CB006	(S)	22	Each	48" Reinforced Concrete End Section				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0450	603-CB007	(S)	6	Each	54" Reinforced Concrete End Section				
0460	603-CE003	(S)	328	Linear Feet	36" x 23" Concrete Arch Pipe, Class A III				
0470	603-CE004	(S)	196	Linear Feet	44" x 27" Concrete Arch Pipe, Class A III				
0480	603-CE005	(S)	144	Linear Feet	51" x 31" Concrete Arch Pipe, Class A III				
0490	603-CE009	(S)	336	Linear Feet	88" x 54" Concrete Arch Pipe, Class A III				
0500	603-CF003	(S)	2	Each	36" x 23" Concrete Arch Pipe End Section				
0510	603-CF004	(S)	6	Each	44" x 27" Concrete Arch Pipe End Section				
0520	603-CF005	(S)	4	Each	51" x 31" Concrete Arch Pipe End Section				
0530	603-CF009	(S)	6	Each	88" x 54" Concrete Arch Pipe End Section				
0540	606-B001		800	Linear Feet	Guard Rail, Class A, Type 1				
0550	606-D008		8	Each	Guard Rail, Bridge End Section, Type H				
0560	606-E001		8	Each	Guard Rail, Terminal End Section				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0570	609-D002	(S)	423	Linear Feet	Combination Concrete Curb and Gutter Type 2				
0580	618-A001		1	Lump Sum	Maintenance of Traffic	XXXXXXXX	XXX		
0590	619-A1002		18	Mile	Temporary Traffic Stripe, Continuous White				
0600	619-A2002		2	Mile	Temporary Traffic Stripe, Continuous Yellow				
0610	619-A4006		9	Mile	Temporary Traffic Stripe, Skip Yellow				
0620	619-A5001		2,884	Linear Feet	Temporary Traffic Stripe, Detail				
0630	619-A6001		1,360	Linear Feet	Temporary Traffic Stripe, Legend				
0640	619-C7001		1,328	Each	Two-Way Yellow Reflective High Performance Raised Marker				
0650	619-C8001		88	Each	One-Way Clear Reflective High Performance Raised Marker				
0660	619-D1001		682	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet				
0670	619-D2001		1,068	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More				
0680	619-G4001		1,260	Linear Feet	Barricades, Type III, Single Faced				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0690	619-G4004		72	Linear Feet	Barricades, Type III, Single Faced, Permanent, Red/White				
0700	619-G5001		144	Each	Free Standing Plastic Drums				
0710	619-G7001		4	Each	Warning Lights, Type "B"				
0720	620-A001		1	Lump Sum	Mobilization	XXXXXXXXXX	XXX		
0730	621-A001		1	Each	Field Laboratory				
0740	627-L001		864	Each	Two-Way Yellow Reflective High Performance Raised Markers				
0750	628-J002		618	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Continuous White				
0760	628-L002		309	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Skip Yellow				
0770	630-A001		126	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness				
0780	630-A002		174	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness				
0790	630-B001		52	Square Feet	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted				
0800	630-C004		416	Linear Feet	Steel U-Section Posts, 3.0 to 3.5 lb/ft				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0810	630-D003		92	Linear Feet	Structural Steel Beams, W6 x 9				
0820	630-E002		96	Pounds	Structural Steel Angles & Bars, 3 1/2" x 3 1/2" x 1/4" Angles				
0830	630-E004		116	Pounds	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar				
0840	630-F001		44	Each	Delineators, Guard Rail, White				
0850	630-G002		8	Each	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted				
0860	630-K003		93	Linear Feet	Welded & Seamless Steel Pipe Posts, 4"				
0870	699-A001		1	Lump Sum	Roadway Construction Stakes	XXXXXXXXX	XXX		
0880	815-A006	(S)	500	Ton	Loose Riprap, Size 100 Changed 11/15/2010				
0890	815-A009	(S)	330	Ton	Loose Riprap, Size 300 Changed 11/15/2010				
0900	815-E001	(S)	489	Square Yard	Geotextile under Riprap				
0910	907-225-A001		73	Acre	Grassing				
0920	907-225-B001		219	Ton	Agricultural Limestone				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
0930	907-226-A001		37	Acre	Temporary Grassing				
0940	907-237-A003		980	Linear Feet	Wattles, 20"				
0950	907-245-A001		640	Linear Feet	Triangular Silt Dike				
0960	907-246-A001		500	Linear Feet	Sandbags				
0970	907-304-C001	(GY)	16,072	Cubic Yard	Granular Material, AEA, Class 5, Group C				
0980	907-304-C005	(GY)	13,486	Cubic Yard	Granular Material, AEA, Class 9, Group C				
0990	907-304-F002	(GT)	12,693	Ton	Size 610 Crushed Stone Base				
1000	907-307-C003	(M)	51,503	Square Yard	6" Soil-Lime-Water Mixing, Class C				
1010	907-307-D001		695	Ton	Lime				
1020	907-407-A001	(A2)	18,746	Gallon	Asphalt for Tack Coat				
1030	907-601-B003	(S)	24	Cubic Yard	Class "B" Structural Concrete, Minor Structures				
1040	907-603-ALT01	(S)	3,904	Linear Feet	18" Type A Alternate Pipe				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
1050	907-603-ALT03	(S)	104	Linear Feet	30" Type A Alternate Pipe				
1060	907-617-A001		105	Each	Right-of-Way Marker				
1070	907-626-C004		12	Mile	6" Thermoplastic Edge Stripe, Continuous White				
1080	907-626-D003		6	Mile	6" Thermoplastic Traffic Stripe, Skip Yellow				
1090	907-626-E004		1	Mile	6" Thermoplastic Traffic Stripe, Continuous Yellow				
1100	907-626-G004		1,866	Linear Feet	Thermoplastic Detail Stripe, White				
1110	907-626-G005		1,358	Linear Feet	Thermoplastic Detail Stripe, Yellow				
1120	907-626-H004		695	Linear Feet	Thermoplastic Legend, White				
ALTERNATE GROUP AA NUMBER 1									
1130	907-308-A001		696	Ton	Portland Cement				
1140	907-308-B001	(M)	50,443	Square Yard	Soil-Cement-Water Mixing, Optional Mixers, Base				
1150	907-308-B002	(M)	12,876	Square Yard	Soil-Cement-Water Mixing, Optional Mixers, Design Soil				
ALTERNATE GROUP AA NUMBER 2									

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
1160	907-311-A003	(M)	63,319	Square Yard	Processing Lime and Fly Ash Treated Course, 6" Thick				
1170	907-311-B001		475	Ton	Lime				
1180	907-311-C002		1,900	Ton	Fly Ash, Class C or F				
ALTERNATE GROUP BB NUMBER 1									
1190	907-403-A006	(BA1)	16,965	Ton	Hot Mix Asphalt, MT, 12.5-mm mixture				
1200	907-403-A007	(BA1)	16,168	Ton	Hot Mix Asphalt, MT, 19-mm mixture				
1210	907-403-A012	(BA1)	6,682	Ton	Hot Mix Asphalt, ST, 19-mm mixture				
1220	907-403-B004	(BA1)	493	Ton	Hot Mix Asphalt, MT, 12.5-mm mixture, Leveling				
1230	907-403-B005	(BA1)	6,036	Ton	Hot Mix Asphalt, MT, 19-mm mixture, Leveling				
1240	907-403-C003	(BA1)	1,381	Ton	Hot Mix Asphalt, MT, 19-mm mixture, Trench Widening				
ALTERNATE GROUP BB NUMBER 2									
1250	907-403-M002	(BA1)	16,965	Ton	Warm Mix Asphalt, MT, 12.5-mm mixture				
1260	907-403-M004	(BA1)	6,682	Ton	Warm Mix Asphalt, ST, 19-mm mixture				

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Bid Amount	
1270	907-403-M007	(BA1)	16,168	Ton	Warm Mix Asphalt, MT, 19-mm mixture				
1280	907-403-N006	(BA1)	493	Ton	Warm Mix Asphalt, MT, 12.5-mm mixture, Leveling				
1290	907-403-N007	(BA1)	6,036	Ton	Warm Mix Asphalt, MT, 19-mm mixture, Leveling				
1300	907-403-O003	(BA1)	1,381	Ton	Warm Mix Asphalt, MT, 19-mm mixture, Trench Widening				

*** BID CERTIFICATION ***

TOTAL BID.....\$_____

*** DBE/WBE SECTION ***

Complete item nos. 1, 2, and/or 3 as appropriate. See Notice to Bidders addressing Disadvantaged Business Enterprises in Highway Construction.

1. I/We agree that no less than _____ percent shall be expended with small business concerns owned and controlled by socially and economically disadvantaged individuals (DBE and WBE).
2. Classification of Bidder: Small Business (DBE)_____ Small Business (WBE)_____
3. A joint venture with a Small Business (DBE/WBE): _____

*** SIGNATURE STATEMENT ***

BIDDER ACKNOWLEDGES THAT HE/SHE HAS CHECKED ALL ITEMS IN THIS PROPOSAL FOR ACCURACY AND CERTIFIED THAT THE FIGURES SHOWN THEREIN CONSTITUTE THEIR OFFICIAL BID.

BIDDER'S SIGNATURE

BIDDER'S COMPANY

BIDDER'S FEDERAL TAX ID NUMBER