

**Melinda L. McGrath**  
Deputy Executive Director/  
Chief Engineer

**Brenda Znachko**  
Deputy Executive Director/  
Administration



**Larry L. "Butch" Brown**  
Executive Director

**Charles R. Carr**  
Director  
Office of Intermodal Planning

**Willie Huff**  
Director  
Office of Enforcement

---

*Contract Administration Division / P.O. Box 1850 / Jackson, Mississippi 39215-1850 / Telephone (601) 359-7700 / FAX (601) 359-7732 / GoMDOT.com*

---

**To: ALL POTENTIAL BIDDERS**

**Date: 01/21/2011**

**RE: Call No. 16, BWO-3165-82(001) / 502310301, BWO-3168-82(001) / 502310302,  
BWO-3166-82(001) / 502311301 & BWO-3167-82(001) / 502311302 -Yazoo County**

Bidders are advised of the following clarifications on the above referenced project:

- 1) Roof Framing for the Project Office shall be similar to the Framing Plan shown on Working Number A1.3, Sheet 58 for the Maintenance Area Headquarters
- 2) The ceramic tile specified has been discontinued. Another ceramic tile of similar quality will be selected by the Department and the information furnished to the low-bidder at the pre-construction conference.
- 3) Panels and feeder to be 3-phase, 4-wire (except for shed panel "ES" - which is 1-phase, 3-wire). Add fourth conductor to all other feeders on riser diagram.
- 4) No intercom system is required. Provide push button at reception desk to allow remote release of door locking device indicated.
- 5) Provide a simple security panel with 7-amp hour battery backup in Telephone Room 104 to serve security devices indicated on drawings. Maintenance Area Headquarters: Provide simple security panel with 7 amp-hour battery backup in Electrical Room 114 to serve security devices indicated on Drawings. Install backlit keypads in locations as shown on Drawings. Contract shall furnish complete and operable system and submit shop drawings prior to installation.
- 6) 600 amp ATS is required for mobile generator as shown on site plan sheet 40. Service entrance feeder from utility pole shall route through ATS as indicated on site plan.
- 7) All exterior lighting is accomplished via building mounted fixtures as shown on site plan, sheet 40. No type H pole mounted fixtures are required on this project.
- 8) NiCad is required as per specifications. NiCad batteries are more reliable than traditional lead acid.
- 9) 24 hours of run time is required as per Section 26 32 13-16, subsection I. item 7.

**Melinda L. McGrath**  
Deputy Executive Director/  
Chief Engineer

**Brenda Znachko**  
Deputy Executive Director/  
Administration



**Larry L. "Butch" Brown**  
Executive Director

**Charles R. Carr**  
Director  
Office of Intermodal Planning

**Willie Huff**  
Director  
Office of Enforcement

---

*Contract Administration Division / P.O. Box 1850 / Jackson, Mississippi 39215-1850 / Telephone (601) 359-7700 / FAX (601) 359-7732 / GoMDOT.com*

---

Your formal acknowledgment of receipt of this notification will be entered into our records and indicates your understanding of this fax and that you have bid accordingly.

Please have an authorized representative of your company sign this page and return by FAX to 601-359-7732.

\_\_\_\_\_  
Melinda L. McGrath, P.E.  
Chief Engineer / Deputy Executive Director

\_\_\_\_\_  
Contractor

\_\_\_\_\_  
Authorized Signature