

ATTALA (4)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	T. L. Wallace Construction, Inc.	Key, LLC	Ellis Construction Company, Inc.
Bridge Replacements on SR 12 from Kosciusko to the Choctaw County Line, known as State Project No. BR-0018-02(045) / 103325302, in the County of Attala, State of Mississippi.					\$16,444,374.65	\$19,191,477.07	\$19,721,681.94	\$22,621,984.72
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS		500,000.00	350,000.00	1,085,000.00
0020	201-B001	Clearing and Grubbing	24.000	ACRE		106.00	2,000.00	4,500.00
0030	202-A001	Removal of Obstructions	1.000	LS		267,000.00	140,000.00	274,000.00
0040	202-B005	Removal of Asphalt Pavement, All Depths	68,860.000	SY		1.70	2.15	4.00
0050	202-B064	Removal of Pipe, 8" And Above	500.000	LF		7.55	8.00	9.00
0060	202-B076	Removal of Traffic Stripe	14,385.000	LF		0.79	0.75	0.75
0070	202-B088	Removal of Box Culvert Headwall, All Sizes	2.000	EA		6,320.00	1,500.00	2,500.00
0080	202-B102	Removal of Guard Rail	1,200.000	LF		2.15	2.00	2.00
0090	202-B105	Removal of Pipe Headwall, All Sizes	6.000	EA		292.00	300.00	800.00
0100	203-A003	Unclassified Excavation, FM, AH	71,598.000	CY		3.70	2.85	3.25
0110	203-EX017	Borrow Excavation, AH, FME, Class B9	447,524.000	CY		7.15	6.25	6.25
0120	203-G003	Excess Excavation, FM, AH	10,514.000	CY		4.00	3.75	3.75
0130	206-A001	Structure Excavation	2,012.000	CY		10.55	9.00	8.00
0140	206-B001	Select Material for Undercuts, Contractor Furnished, FM	268.000	CY		31.60	45.00	30.00
0150	209-A004	Geotextile Stabilization, Type V, Non-Woven	36,345.000	SY		2.40	2.60	2.00
0160	213-C001	Superphosphate	53.000	TON		522.00	550.00	495.00
0170	216-A001	Solid Sodding	675.000	SY		1.90	2.00	1.80
0180	217-A001	Ditch Liner	11,684.000	SY		1.25	1.30	1.20
0190	219-A001	Watering	5.000	KGAL		20.00	20.00	20.00
0200	220-A001	Insect Pest Control	53.000	ACRE		30.00	30.00	30.00
0210	221-A001	Portland Cement Concrete Paved Ditch	172.000	CY		411.00	375.00	340.00
0220	223-A001	Mowing	157.000	ACRE		40.00	40.00	40.00
0230	224-A001	Soil Reinforcing Mat	3,597.000	SY		2.85	3.00	2.70
0240	234-A001	Temporary Silt Fence	13,302.000	LF		2.85	3.00	2.70
0250	235-A001	Temporary Erosion Checks	44.000	BALE		9.50	10.00	9.00
0260	236-A004	Silt Basin, Type D	24.000	EA		2,170.00	750.00	3,400.00

ATTALA (4)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	T. L. Wallace Construction, Inc.	Key, LLC	Ellis Construction Company, Inc.
Bridge Replacements on SR 12 from Kosciusko to the Choctaw County Line, known as State Project No. BR-0018-02(045) / 103325302, in the County of Attala, State of Mississippi.					\$16,444,374.65	\$19,191,477.07	\$19,721,681.94	\$22,621,984.72
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0270	236-B004	Maintenance and Removal of Existing Silt Basins, Type D	24.000	EA		2,170.00	250.00	1,500.00
0280	310-B001	Size I Stabilizer Aggregate, Coarse	340.000	CY		59.50	39.00	60.00
0290	406-A001	Cold Milling of Bituminous Pavement, All Depths	4,200.000	SY		4.50	5.00	7.00
0300	408-A003	Asphalt for Prime Coat, Cut-Back MC-70 or Emulsified EA-1	17,497.000	GAL		3.90	3.68	4.00
0310	423-A001	Rumble Strips, Ground In	8.000	MI		395.00	375.00	375.00
0320	501-E001	Expansion Joints, Without Dowels	1,967.000	LF		10.55	9.00	10.00
0330	501-K001	Transverse Grooving	5,334.000	SY		2.45	2.40	2.41
0340	502-A001	Reinforced Cement Concrete Bridge End Pavement	5,047.000	SY		40.00	120.00	90.00
0350	602-A001	Reinforcing Steel	133,198.000	LBS		0.84	0.92	1.00
0360	603-CA002	18" Reinforced Concrete Pipe, Class III	32.000	LF		37.90	40.00	30.50
0370	603-CB001	18" Reinforced Concrete End Section	96.000	EA		100.00	950.00	800.00
0380	603-CE001	22" x 13" Concrete Arch Pipe, Class A III	60.000	LF		55.00	60.00	59.00
0390	603-CE004	44" x 27" Concrete Arch Pipe, Class A III	80.000	LF		105.00	135.00	114.00
0400	603-CF001	22" x 13" Concrete Arch Pipe End Section	1.000	EA		718.00	950.00	800.00
0410	603-CF004	44" x 27" Concrete Arch Pipe End Section	2.000	EA		1,375.00	1,800.00	1,900.00
0420	603-SB035	18" Branch Connections, Stub into Box Bridge	8.000	EA		422.00	400.00	1,000.00
0430	606-B001	Guard Rail, Class A, Type 1	3,250.000	LF		16.85	16.00	16.00
0440	606-D012	Guard Rail, Bridge End Section, Type I	40.000	EA		2,000.00	1,900.00	1,900.00
0450	606-E001	Guard Rail, Terminal End Section	40.000	EA		2,000.00	1,900.00	1,900.00
0460	609-D002	Combination Concrete Curb and Gutter Type 2	535.000	LF		22.10	40.00	20.00
0470	615-A018	Concrete Bridge End Barrier, 33.5"	400.000	LF		39.60	40.00	36.75
0480	618-A001	Maintenance of Traffic	1.000	LS		82,500.00	40,000.00	280,000.00
0490	618-C001	Construction & Removal of Detour Bridge	1.000	LS		973,000.00	1,440,000.00	1,950,000.00
0500	619-A1001	Temporary Traffic Stripe, Continuous White	31,680.000	LF		0.16	0.15	0.15
0511	619-A2005	Temporary Traffic Stripe, Continuous Yellow, Type 1 or 2 Tap	19,500.000	LF		0.95	0.15	0.90
0520	619-A2001	Temporary Traffic Stripe, Continuous Yellow	31,680.000	LF		0.16	0.90	0.15

ATTALA (4)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	T. L. Wallace Construction, Inc.	Key, LLC	Ellis Construction Company, Inc.
Bridge Replacements on SR 12 from Kosciusko to the Choctaw County Line, known as State Project No. BR-0018-02(045) / 103325302, in the County of Attala, State of Mississippi.					\$16,444,374.65	\$19,191,477.07	\$19,721,681.94	\$22,621,984.72
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0530	619-A5003	Temporary Traffic Stripe, Detail, Type 1 or 2 Tape	17,458.000	LF		0.95	0.90	0.90
0540	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	642.000	EA		5.30	5.00	5.00
0550	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	347.000	SF		6.35	6.00	7.00
0560	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	1,540.000	SF		6.35	6.00	7.00
0570	619-F1001	Concrete Median Barrier, Precast	896.000	LF		33.85	40.00	36.00
0580	619-F2001	Remove and Reset Concrete Median Barrier, Precast	896.000	LF		5.50	40.00	20.00
0590	619-F3004	Delineators, Guard Rail, White	88.000	EA		18.95	18.00	18.00
0600	619-G4001	Barricades, Type III, Single Faced	552.000	LF		14.75	14.00	16.00
0610	619-G5001	Free Standing Plastic Drums	182.000	EA		42.10	40.00	45.00
0620	619-G7001	Warning Lights, Type "B"	40.000	EA		422.00	400.00	150.00
0630	619-K1001	Installation and Removal of Guard Rail, Type I, Class A	1,100.000	LF		15.80	15.00	15.00
0640	619-K4001	Installation and Removal of Guardrail, Terminal End Section	44.000	EA		1,160.00	1,100.00	1,100.00
0650	620-A001	Mobilization	1.000	LS		1,250,000.00	1,200,000.00	2,375,000.00
0660	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	1,118.000	EA		5.30	5.00	5.00
0665	629-A001	Vehicular Impact Attenuator, 50 MPH	1.000	EA		15,700.00	11,000.00	11,000.00
0670	630-F001	Delineators, Guard Rail, White	260.000	EA		18.95	18.00	18.00
0680	630-G002	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	44.000	EA		78.95	75.00	75.00
0690	699-A001	Roadway Construction Stakes	1.000	LS		207,000.00	200,000.00	221,000.00
0700	815-A006	Loose Riprap, Size 100	1,920.000	TON		46.45	62.00	55.00
0710	815-A009	Loose Riprap, Size 300	11,300.000	TON		47.65	64.00	56.00
0720	815-E001	Geotextile under Riprap	8,025.000	SY		2.40	2.65	2.00
0730	815-F002	Sediment Control Stone	1,200.000	TON		49.65	60.00	62.00
0740	907-225-A001	Grassing	107.000	ACRE		711.00	750.00	675.00
0750	907-225-B001	Agricultural Limestone	320.000	TON		66.35	70.00	63.00
0760	907-226-A001	Temporary Grassing	107.000	ACRE		664.00	1,000.00	630.00
0770	907-227-A001	Hydroseeding	27.000	ACRE		1,430.00	1,500.00	1,350.00

ATTALA (4)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	T. L. Wallace Construction, Inc.	Key, LLC	Ellis Construction Company, Inc.
Bridge Replacements on SR 12 from Kosciusko to the Choctaw County Line, known as State Project No. BR-0018-02(045) / 103325302, in the County of Attala, State of Mississippi.					\$16,444,374.65	\$19,191,477.07	\$19,721,681.94	\$22,621,984.72
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0775	907-234-C002	Super Silt Fence	4,800.000	LF		10.45	11.00	9.90
0776	907-234-F001	Turbidity Barrier	1,000.000	LF		17.65	12.00	20.00
0780	907-237-A003	Wattles, 20"	960.000	LF		5.70	6.00	5.40
0790	907-245-A001	Triangular Silt Dike	144.000	LF		10.45	11.00	9.90
0800	907-246-A001	Sandbags	6,962.000	LF		4.75	5.00	4.50
0810	907-247-A001	Temporary Stream Diversion	2.000	EA		7,400.00	17,000.00	20,000.00
0820	907-304-B009	Granular Material, Class 3, Group D	57,154.000	TON		19.25	17.75	19.75
0830	907-304-F002	Size 610 Crushed Stone Base	14,920.000	TON		44.20	55.00	46.25
0840	907-407-A001	Asphalt for Tack Coat	52,491.000	GAL		1.05	1.00	2.85
0850	907-601-B003	Class "B" Structural Concrete, Minor Structures	1.000	CY		1,960.00	1,500.00	2,500.00
0860	907-603-ALT01	18" Type A Alternate Pipe	460.000	LF		21.70	20.00	22.00
0870	907-603-ALT02	24" Type A Alternate Pipe	140.000	LF		33.10	31.00	26.00
0880	907-603-ALT04	36" Type A Alternate Pipe	128.000	LF		59.20	53.00	50.00
0890	907-603-ALT06	48" Type A Alternate Pipe	32.000	LF		87.60	73.00	72.50
0900	907-617-A001	Right-of-Way Marker	91.000	EA		143.00	225.00	215.00
0910	907-626-B003	6" Thermoplastic Traffic Stripe, Continuous White	8,020.000	LF		0.63	0.60	0.60
0920	907-626-D004	6" Thermoplastic Traffic Stripe, Skip Yellow	5,800.000	LF		0.32	0.30	0.30
0925	907-626-E003	6" Thermoplastic Traffic Stripe, Continuous Yellow	19,020.000	LF		0.58	0.55	0.55
0935	907-626-F008	6" Thermoplastic Edge Stripe, Continuous Yellow	27,300.000	LF		0.42	0.40	0.40
0940	907-626-G004	Thermoplastic Detail Stripe, White	5,918.000	LF		0.95	0.90	0.90
0950	907-626-G005	Thermoplastic Detail Stripe, Yellow	1,640.000	LF		0.95	0.90	0.90
0960	907-626-H004	Thermoplastic Legend, White	684.000	LF		3.20	3.00	3.00
0970	907-804-B001	Box Bridge Concrete, Class B	1,380.000	CY		342.00	350.00	475.00
0980	907-403-A006	Hot Mix Asphalt, MT, 12.5-mm mixture	10,100.000	TON		95.75	90.95	89.53
0990	907-403-A007	Hot Mix Asphalt, MT, 19-mm mixture	13,942.000	TON		91.95	87.32	86.05
1000	907-403-A010	Hot Mix Asphalt, MT, 9.5-mm mixture	7,576.000	TON		101.00	95.48	95.81

ATTALA (4)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	T. L. Wallace Construction, Inc.	Key, LLC	Ellis Construction Company, Inc.
Bridge Replacements on SR 12 from Kosciusko to the Choctaw County Line, known as State Project No. BR-0018-02(045) / 103325302, in the County of Attala, State of Mississippi.					\$16,444,374.65	\$19,191,477.07	\$19,721,681.94	\$22,621,984.72
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
1010	907-403-M002	Warm Mix Asphalt, MT, 12.5-mm mixture	10,100.000	TON				
1020	907-403-M006	Warm Mix Asphalt, MT, 9.5-mm mixture	7,576.000	TON				
1030	907-403-M007	Warm Mix Asphalt, MT, 19-mm mixture	13,942.000	TON				
1040	628-J002	6" High Performance Cold Plastic Traffic Stripe, Continuous	3,960.000	LF		5.30	5.00	5.00
1050	628-L002	6" High Performance Cold Plastic Traffic Stripe, Skip Yellow	1,980.000	LF		5.30	5.00	5.00
1060	628-M002	6" High Performance Cold Plastic Traffic Stripe, Continuous	3,960.000	LF		5.30	5.00	5.00
1070	907-626-J003	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous	3,960.000	LF				
1080	907-626-K003	6" Inverted Profile Thermoplastic Traffic Stripe, Skip Yello	1,980.000	LF				
1090	907-626-L001	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous	3,960.000	LF				
1100	501-K001	Transverse Grooving	7,367.000	SY		2.45	2.40	2.41
1110	803-B002	Conventional Static Pile Load Test	20.000	EA		5,000.00	5,000.00	5,000.00
1120	803-C002	14" x 14" Prestressed Concrete Piling	12,920.000	LF		38.00	41.00	33.00
1130	803-C003	16" x 16" Prestressed Concrete Piling	5,000.000	LF		42.00	49.00	38.00
1140	803-F009	20" Pre-Formed Pile Hole	1,412.000	LF		22.90	15.00	18.00
1150	803-I001	PDA Test Pile	22.000	EA		4,760.00	9,000.00	5,900.00
1160	803-J001	Pile Restrike	20.000	EA		692.00	650.00	800.00
1170	805-A001	Reinforcement	538,390.000	LBS		0.87	0.92	0.63
1180	813-A001	Concrete Railing	3,315.000	LF		39.45	40.00	36.75
1190	815-A009	Loose Riprap, Size 300	4,742.000	TON		47.65	62.00	56.00
1200	815-E001	Geotextile under Riprap	3,523.000	SY		2.40	2.60	2.00
1210	907-804-A001	Bridge Concrete, Class AA	3,098.000	CY		615.00	625.00	700.00
1220	907-804-C016	40' Prestressed Concrete Beam, Type I+2	7,808.000	LF		73.00	61.00	73.00
1230	907-804-C019	60' Prestressed Concrete Beam, Type II+2	1,787.000	LF		87.30	80.00	88.00

ATTALA (4)					Eutaw Construction Company, Inc.			
Bridge Replacements on SR 12 from Kosciusko to the Choctaw County Line, known as State Project No. BR-0018-02(045) / 103325302, in the County of Attala, State of Mississippi.					\$23,289,541.25			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0010	201-A001	Clearing and Grubbing	1.000	LS	1,250,000.00			
0020	201-B001	Clearing and Grubbing	24.000	ACRE	2,500.00			
0030	202-A001	Removal of Obstructions	1.000	LS	1,500,000.00			
0040	202-B005	Removal of Asphalt Pavement, All Depths	68,860.000	SY	1.60			
0050	202-B064	Removal of Pipe, 8" And Above	500.000	LF	11.00			
0060	202-B076	Removal of Traffic Stripe	14,385.000	LF	0.75			
0070	202-B088	Removal of Box Culvert Headwall, All Sizes	2.000	EA	6,000.00			
0080	202-B102	Removal of Guard Rail	1,200.000	LF	2.00			
0090	202-B105	Removal of Pipe Headwall, All Sizes	6.000	EA	450.00			
0100	203-A003	Unclassified Excavation, FM, AH	71,598.000	CY	3.00			
0110	203-EX017	Borrow Excavation, AH, FME, Class B9	447,524.000	CY	3.00			
0120	203-G003	Excess Excavation, FM, AH	10,514.000	CY	8.00			
0130	206-A001	Structure Excavation	2,012.000	CY	10.00			
0140	206-B001	Select Material for Undercuts, Contractor Furnished, FM	268.000	CY	30.00			
0150	209-A004	Geotextile Stabilization, Type V, Non-Woven	36,345.000	SY	2.70			
0160	213-C001	Superphosphate	53.000	TON	495.00			
0170	216-A001	Solid Sodding	675.000	SY	1.80			
0180	217-A001	Ditch Liner	11,684.000	SY	1.20			
0190	219-A001	Watering	5.000	KGAL	20.00			
0200	220-A001	Insect Pest Control	53.000	ACRE	30.00			
0210	221-A001	Portland Cement Concrete Paved Ditch	172.000	CY	390.00			
0220	223-A001	Mowing	157.000	ACRE	40.00			
0230	224-A001	Soil Reinforcing Mat	3,597.000	SY	2.70			
0240	234-A001	Temporary Silt Fence	13,302.000	LF	2.50			
0250	235-A001	Temporary Erosion Checks	44.000	BALE	8.00			
0260	236-A004	Silt Basin, Type D	24.000	EA	800.00			

ATTALA (4)					Eutaw Construction Company, Inc.			
Bridge Replacements on SR 12 from Kosciusko to the Choctaw County Line, known as State Project No. BR-0018-02(045) / 103325302, in the County of Attala, State of Mississippi.					\$23,289,541.25			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0270	236-B004	Maintenance and Removal of Existing Silt Basins, Type D	24.000	EA	800.00			
0280	310-B001	Size I Stabilizer Aggregate, Coarse	340.000	CY	71.00			
0290	406-A001	Cold Milling of Bituminous Pavement, All Depths	4,200.000	SY	4.25			
0300	408-A003	Asphalt for Prime Coat, Cut-Back MC-70 or Emulsified EA-1	17,497.000	GAL	3.68			
0310	423-A001	Rumble Strips, Ground In	8.000	MI	850.00			
0320	501-E001	Expansion Joints, Without Dowels	1,967.000	LF	3.00			
0330	501-K001	Transverse Grooving	5,334.000	SY	1.00			
0340	502-A001	Reinforced Cement Concrete Bridge End Pavement	5,047.000	SY	60.00			
0350	602-A001	Reinforcing Steel	133,198.000	LBS	0.80			
0360	603-CA002	18" Reinforced Concrete Pipe, Class III	32.000	LF	40.00			
0370	603-CB001	18" Reinforced Concrete End Section	96.000	EA	700.00			
0380	603-CE001	22" x 13" Concrete Arch Pipe, Class A III	60.000	LF	63.00			
0390	603-CE004	44" x 27" Concrete Arch Pipe, Class A III	80.000	LF	101.00			
0400	603-CF001	22" x 13" Concrete Arch Pipe End Section	1.000	EA	1,045.00			
0410	603-CF004	44" x 27" Concrete Arch Pipe End Section	2.000	EA	1,750.00			
0420	603-SB035	18" Branch Connections, Stub into Box Bridge	8.000	EA	400.00			
0430	606-B001	Guard Rail, Class A, Type 1	3,250.000	LF	16.00			
0440	606-D012	Guard Rail, Bridge End Section, Type I	40.000	EA	1,900.00			
0450	606-E001	Guard Rail, Terminal End Section	40.000	EA	1,900.00			
0460	609-D002	Combination Concrete Curb and Gutter Type 2	535.000	LF	21.00			
0470	615-A018	Concrete Bridge End Barrier, 33.5"	400.000	LF	36.75			
0480	618-A001	Maintenance of Traffic	1.000	LS	100,000.00			
0490	618-C001	Construction & Removal of Detour Bridge	1.000	LS	3,000,000.00			
0500	619-A1001	Temporary Traffic Stripe, Continuous White	31,680.000	LF	0.15			
0511	619-A2005	Temporary Traffic Stripe, Continuous Yellow, Type 1 or 2 Tap	19,500.000	LF	0.90			
0520	619-A2001	Temporary Traffic Stripe, Continuous Yellow	31,680.000	LF	0.15			

ATTALA (4)					Eutaw Construction Company, Inc.			
Bridge Replacements on SR 12 from Kosciusko to the Choctaw County Line, known as State Project No. BR-0018-02(045) / 103325302, in the County of Attala, State of Mississippi.					\$23,289,541.25			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0530	619-A5003	Temporary Traffic Stripe, Detail, Type 1 or 2 Tape	17,458.000	LF	0.90			
0540	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	642.000	EA	5.00			
0550	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	347.000	SF	7.00			
0560	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	1,540.000	SF	7.00			
0570	619-F1001	Concrete Median Barrier, Precast	896.000	LF	31.00			
0580	619-F2001	Remove and Reset Concrete Median Barrier, Precast	896.000	LF	5.00			
0590	619-F3004	Delineators, Guard Rail, White	88.000	EA	18.00			
0600	619-G4001	Barricades, Type III, Single Faced	552.000	LF	16.00			
0610	619-G5001	Free Standing Plastic Drums	182.000	EA	45.00			
0620	619-G7001	Warning Lights, Type "B"	40.000	EA	150.00			
0630	619-K1001	Installation and Removal of Guard Rail, Type I, Class A	1,100.000	LF	15.00			
0640	619-K4001	Installation and Removal of Guardrail, Terminal End Section	44.000	EA	1,100.00			
0650	620-A001	Mobilization	1.000	LS	2,300,000.00			
0660	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	1,118.000	EA	5.00			
0665	629-A001	Vehicular Impact Attenuator, 50 MPH	1.000	EA	11,000.00			
0670	630-F001	Delineators, Guard Rail, White	260.000	EA	18.00			
0680	630-G002	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	44.000	EA	75.00			
0690	699-A001	Roadway Construction Stakes	1.000	LS	250,000.00			
0700	815-A006	Loose Riprap, Size 100	1,920.000	TON	60.00			
0710	815-A009	Loose Riprap, Size 300	11,300.000	TON	60.00			
0720	815-E001	Geotextile under Riprap	8,025.000	SY	2.70			
0730	815-F002	Sediment Control Stone	1,200.000	TON	47.00			
0740	907-225-A001	Grassing	107.000	ACRE	675.00			
0750	907-225-B001	Agricultural Limestone	320.000	TON	63.00			
0760	907-226-A001	Temporary Grassing	107.000	ACRE	630.00			
0770	907-227-A001	Hydroseeding	27.000	ACRE	1,350.00			

ATTALA (4)					Eutaw Construction Company, Inc.			
Bridge Replacements on SR 12 from Kosciusko to the Choctaw County Line, known as State Project No. BR-0018-02(045) / 103325302, in the County of Attala, State of Mississippi.					\$23,289,541.25			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0775	907-234-C002	Super Silt Fence	4,800.000	LF	11.50			
0776	907-234-F001	Turbidity Barrier	1,000.000	LF	15.00			
0780	907-237-A003	Wattles, 20"	960.000	LF	6.00			
0790	907-245-A001	Triangular Silt Dike	144.000	LF	11.50			
0800	907-246-A001	Sandbags	6,962.000	LF	6.00			
0810	907-247-A001	Temporary Stream Diversion	2.000	EA	10,000.00			
0820	907-304-B009	Granular Material, Class 3, Group D	57,154.000	TON	24.00			
0830	907-304-F002	Size 610 Crushed Stone Base	14,920.000	TON	48.00			
0840	907-407-A001	Asphalt for Tack Coat	52,491.000	GAL	1.00			
0850	907-601-B003	Class "B" Structural Concrete, Minor Structures	1.000	CY	2,000.00			
0860	907-603-ALT01	18" Type A Alternate Pipe	460.000	LF	25.00			
0870	907-603-ALT02	24" Type A Alternate Pipe	140.000	LF	33.00			
0880	907-603-ALT04	36" Type A Alternate Pipe	128.000	LF	50.75			
0890	907-603-ALT06	48" Type A Alternate Pipe	32.000	LF	68.00			
0900	907-617-A001	Right-of-Way Marker	91.000	EA	150.00			
0910	907-626-B003	6" Thermoplastic Traffic Stripe, Continuous White	8,020.000	LF	0.60			
0920	907-626-D004	6" Thermoplastic Traffic Stripe, Skip Yellow	5,800.000	LF	0.30			
0925	907-626-E003	6" Thermoplastic Traffic Stripe, Continuous Yellow	19,020.000	LF	0.55			
0935	907-626-F008	6" Thermoplastic Edge Stripe, Continuous Yellow	27,300.000	LF	0.40			
0940	907-626-G004	Thermoplastic Detail Stripe, White	5,918.000	LF	0.90			
0950	907-626-G005	Thermoplastic Detail Stripe, Yellow	1,640.000	LF	0.90			
0960	907-626-H004	Thermoplastic Legend, White	684.000	LF	3.00			
0970	907-804-B001	Box Bridge Concrete, Class B	1,380.000	CY	315.00			
0980	907-403-A006	Hot Mix Asphalt, MT, 12.5-mm mixture	10,100.000	TON	90.95			
0990	907-403-A007	Hot Mix Asphalt, MT, 19-mm mixture	13,942.000	TON	87.32			
1000	907-403-A010	Hot Mix Asphalt, MT, 9.5-mm mixture	7,576.000	TON	95.50			

ATTALA (4)					Eutaw Construction Company, Inc.			
Bridge Replacements on SR 12 from Kosciusko to the Choctaw County Line, known as State Project No. BR-0018-02(045) / 103325302, in the County of Attala, State of Mississippi.					\$23,289,541.25			
Ref#	SM Item	Item Description	Item Qty	Units	4			
1010	907-403-M002	Warm Mix Asphalt, MT, 12.5-mm mixture	10,100.000	TON				
1020	907-403-M006	Warm Mix Asphalt, MT, 9.5-mm mixture	7,576.000	TON				
1030	907-403-M007	Warm Mix Asphalt, MT, 19-mm mixture	13,942.000	TON				
1040	628-J002	6" High Performance Cold Plastic Traffic Stripe, Continuous	3,960.000	LF	5.00			
1050	628-L002	6" High Performance Cold Plastic Traffic Stripe, Skip Yellow	1,980.000	LF	5.00			
1060	628-M002	6" High Performance Cold Plastic Traffic Stripe, Continuous	3,960.000	LF	5.00			
1070	907-626-J003	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous	3,960.000	LF				
1080	907-626-K003	6" Inverted Profile Thermoplastic Traffic Stripe, Skip Yello	1,980.000	LF				
1090	907-626-L001	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous	3,960.000	LF				
1100	501-K001	Transverse Grooving	7,367.000	SY	2.50			
1110	803-B002	Conventional Static Pile Load Test	20.000	EA	5,000.00			
1120	803-C002	14" x 14" Prestressed Concrete Piling	12,920.000	LF	45.00			
1130	803-C003	16" x 16" Prestressed Concrete Piling	5,000.000	LF	58.00			
1140	803-F009	20" Pre-Formed Pile Hole	1,412.000	LF	30.50			
1150	803-I001	PDA Test Pile	22.000	EA	4,500.00			
1160	803-J001	Pile Restrike	20.000	EA	2,000.00			
1170	805-A001	Reinforcement	538,390.000	LBS	1.00			
1180	813-A001	Concrete Railing	3,315.000	LF	40.00			
1190	815-A009	Loose Riprap, Size 300	4,742.000	TON	60.00			
1200	815-E001	Geotextile under Riprap	3,523.000	SY	2.70			
1210	907-804-A001	Bridge Concrete, Class AA	3,098.000	CY	613.00			
1220	907-804-C016	40' Prestressed Concrete Beam, Type I+2	7,808.000	LF	85.00			
1230	907-804-C019	60' Prestressed Concrete Beam, Type II+2	1,787.000	LF	109.00			