

LEAKE (40)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Key, LLC	N. L. Carson Construction Company, Inc.
Replacement of Bridges No. 98.7, No. 101.0 and No. 101.5 on SR 16 between the Madison County Line and SR 25, known as State Project No. BR-0024-03(014) / 100490302, in the County of Leake, State of Mississippi.					\$8,075,898.89	\$8,900,000.00	\$9,130,360.23	\$9,594,957.73
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS		85,608.54	100,000.00	285,058.00
0020	201-B001	Clearing and Grubbing	1.000	ACRE		3,106.97	2,100.00	2,500.00
0030	202-A001	Removal of Obstructions	1.000	LS		129,223.67	140,000.00	135,000.00
0040	202-B005	Removal of Asphalt Pavement, All Depths	4,317.000	SY		6.57	2.50	2.75
0050	202-B064	Removal of Pipe, 8" And Above	21.000	LF		24.12	7.00	6.00
0060	202-B076	Removal of Traffic Stripe	3,900.000	LF		1.00	1.00	1.05
0070	202-B102	Removal of Guard Rail	2,092.000	LF		3.00	3.00	3.00
0080	202-B130	Removal of Piling	20.000	EA		482.24	500.00	500.00
0090	203-EX027	Borrow Excavation, AH, FME, Class B14	69,036.000	CY		5.51	6.35	6.25
0100	211-B001	Topsoil for Slope Treatment, Contractor Furnished	14,616.000	CY		0.10	7.50	10.00
0110	213-C001	Superphosphate	18.000	TON		500.00	650.00	577.50
0120	215-A001	Vegetative Materials for Mulch	103.000	TON		165.00	185.00	210.00
0130	217-A001	Ditch Liner	488.000	SY		2.00	2.00	1.58
0140	220-A001	Insect Pest Control	18.000	ACRE		30.00	30.00	30.00
0150	221-A001	Portland Cement Concrete Paved Ditch	55.000	CY		350.00	425.00	375.00
0160	223-A001	Mowing	1.000	ACRE		40.00	40.00	40.00
0170	224-A001	Soil Reinforcing Mat	267.000	SY		3.00	5.00	6.30
0180	234-A001	Temporary Silt Fence	25,000.000	LF		2.35	3.00	3.15
0190	235-A001	Temporary Erosion Checks	1,122.000	BALE		7.50	9.00	9.45
0200	239-A001	Temporary Slope Drains	143.000	LF		10.48	10.00	8.00
0210	406-A001	Cold Milling of Bituminous Pavement, All Depths	1,067.000	SY		11.70	8.00	10.22
0220	501-E001	Expansion Joints, Without Dowels	291.000	LF		9.28	8.00	11.00
0230	501-K001	Transverse Grooving	603.000	SY		2.51	2.65	2.64
0240	502-A001	Reinforced Cement Concrete Bridge End Pavement	621.000	SY		113.73	125.00	105.00
0250	603-CB005	42" Reinforced Concrete End Section	2.000	EA		1,496.90	2,000.00	1,750.00
0260	606-B001	Guard Rail, Class A, Type 1	1,275.000	LF		16.00	17.75	16.80

LEAKE (40)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Key, LLC	N. L. Carson Construction Company, Inc.
Replacement of Bridges No. 98.7, No. 101.0 and No. 101.5 on SR 16 between the Madison County Line and SR 25, known as State Project No. BR-0024-03(014) / 100490302, in the County of Leake, State of Mississippi.					\$8,075,898.89	\$8,900,000.00	\$9,130,360.23	\$9,594,957.73
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0270	606-D012	Guard Rail, Bridge End Section, Type I	12.000	EA		2,000.00	2,000.00	2,100.00
0280	606-E002	Guard Rail, Terminal End Section, Flared	12.000	EA		1,900.00	1,950.00	1,995.00
0290	615-A018	Concrete Bridge End Barrier, 33.5"	120.000	LF		35.00	40.00	55.20
0300	618-A001	Maintenance of Traffic	1.000	LS		36,147.73	25,000.00	55,000.00
0310	619-A1001	Temporary Traffic Stripe, Continuous White	11,966.000	LF		0.20	0.20	0.21
0320	619-A2001	Temporary Traffic Stripe, Continuous Yellow	11,966.000	LF		0.20	0.20	0.21
0330	619-A2005	Temporary Traffic Stripe, Continuous Yellow, Type 1 or 2 Tap	3,900.000	LF		1.00	1.00	1.05
0340	619-A5003	Temporary Traffic Stripe, Detail, Type 1 or 2 Tape	4,769.000	LF		1.00	1.00	1.05
0350	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	139.000	EA		5.00	5.00	5.25
0360	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	116.000	SF		12.49	10.50	6.30
0370	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	714.000	SF		11.25	10.50	6.30
0380	619-F3004	Delineators, Guard Rail, White	36.000	EA		18.00	15.00	18.90
0390	619-G4001	Barricades, Type III, Single Faced	98.000	LF		43.50	20.25	13.65
0400	619-G4005	Barricades, Type III, Double Faced	24.000	LF		39.53	21.00	16.70
0410	619-G5001	Free Standing Plastic Drums	42.000	EA		63.80	42.00	44.00
0420	619-G7001	Warning Lights, Type "B"	4.000	EA		126.86	515.00	417.50
0430	620-A001	Mobilization	1.000	LS		807,400.03	500,000.00	813,522.00
0440	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	180.000	EA		5.00	5.00	5.25
0450	628-J002	6" High Performance Cold Plastic Traffic Stripe, Continuous	2,624.000	LF		5.00	5.00	5.25
0460	628-M002	6" High Performance Cold Plastic Traffic Stripe, Continuous	2,624.000	LF		5.00	5.00	5.25
0470	630-F001	Delineators, Guard Rail, White	66.000	EA		18.00	15.00	18.90
0480	630-G002	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	12.000	EA		75.00	75.00	78.75
0490	699-A001	Roadway Construction Stakes	1.000	LS		99,741.17	110,000.00	207,370.00
0500	815-A006	Loose Riprap, Size 100	1,000.000	TON		51.73	60.00	56.00
0510	815-A009	Loose Riprap, Size 300	1,721.000	TON		51.73	60.00	56.00
0520	815-E001	Geotextile under Riprap	1,384.000	SY		2.55	2.60	2.44

LEAKE (40)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Key, LLC	N. L. Carson Construction Company, Inc.
Replacement of Bridges No. 98.7, No. 101.0 and No. 101.5 on SR 16 between the Madison County Line and SR 25, known as State Project No. BR-0024-03(014) / 100490302, in the County of Leake, State of Mississippi.					\$8,075,898.89	\$8,900,000.00	\$9,130,360.23	\$9,594,957.73
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0530	815-F002	Sediment Control Stone	1,000.000	TON		56.06	65.00	69.00
0540	907-225-A001	Grassing	75.000	ACRE		650.00	700.00	887.50
0550	907-225-B001	Agricultural Limestone	109.000	TON		60.00	75.00	78.75
0560	907-226-A001	Temporary Grassing	27.000	ACRE		600.00	1,000.00	687.50
0570	907-237-A003	Wattles, 20"	1,000.000	LF		4.00	5.00	6.30
0580	907-245-A001	Triangular Silt Dike	500.000	LF		9.00	10.00	11.55
0590	907-246-A001	Sandbags	500.000	LF		5.00	5.00	5.25
0600	907-304-B001	Granular Material, Class 5, Group C	8,652.000	TON		17.50	19.50	19.00
0610	907-304-B005	Granular Material, Class 9, Group C	22,830.000	TON		11.03	14.00	6.50
0620	907-307-C003	6" Soil-Lime-Water Mixing, Class C	1,914.000	SY		1.65	1.45	4.68
0630	907-307-D001	Lime	26.000	TON		184.97	180.00	236.25
0640	907-407-A001	Asphalt for Tack Coat	3,743.000	GAL		3.30	3.00	3.47
0650	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	291.000	LF		31.35	30.00	18.55
0660	907-601-B003	Class "B" Structural Concrete, Minor Structures	1.000	CY		2,061.07	1,500.00	1,500.00
0670	907-603-ALT01	18" Type A Alternate Pipe	52.000	LF		20.40	23.00	30.00
0680	907-603-ALT05	42" Type A Alternate Pipe	48.000	LF		74.85	80.00	80.00
0690	907-617-A001	Right-of-Way Marker	25.000	EA		300.00	250.00	247.80
0700	907-618-D001	Construction and Removal of Detour Road	1.000	LS		2,232,571.89	2,150,000.00	2,108,319.89
0702	907-618-E001	Detour Bridge Piling	3,250.000	LF		40.00	50.00	39.75
0704	907-618-F001	Detour Bridge Test Pile	1.000	LS		30,277.47	65,000.00	55,000.00
0710	907-626-C007	6" Thermoplastic Double Drop Edge Stripe, Continuous White	11,780.000	LF		0.55	0.55	0.58
0720	907-626-D005	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	4,250.000	LF		0.20	0.20	0.21
0730	907-626-E005	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yell	3,360.000	LF		0.55	0.55	0.58
0740	907-308-A001	Portland Cement	96.000	TON		131.65	130.00	156.50
0750	907-308-B002	Soil-Cement-Water Mixing, Optional Mixers, Design Soil	11,310.000	SY		1.68	1.45	1.73
0760	907-311-A003	Processing Lime and Fly Ash Treated Course, 6" Thick	11,310.000	SY				

LEAKE (40)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Key, LLC	N. L. Carson Construction Company, Inc.
Replacement of Bridges No. 98.7, No. 101.0 and No. 101.5 on SR 16 between the Madison County Line and SR 25, known as State Project No. BR-0024-03(014) / 100490302, in the County of Leake, State of Mississippi.					\$8,075,898.89	\$8,900,000.00	\$9,130,360.23	\$9,594,957.73
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0770	907-311-B001	Lime	82.000	TON				
0780	907-311-C002	Fly Ash, Class C or F	326.000	TON				
0790	907-403-A006	Hot Mix Asphalt, MT, 12.5-mm mixture	2,055.000	TON		89.70	93.78	94.10
0800	907-403-A007	Hot Mix Asphalt, MT, 19-mm mixture	1,206.000	TON		96.60	94.00	101.35
0810	907-403-C003	Hot Mix Asphalt, MT, 19-mm mixture, Trench Widening	489.000	TON		110.50	104.52	115.94
0820	907-403-M002	Warm Mix Asphalt, MT, 12.5-mm mixture	2,055.000	TON				
0830	907-403-M007	Warm Mix Asphalt, MT, 19-mm mixture	1,206.000	TON				
0840	907-403-O003	Warm Mix Asphalt, MT, 19-mm mixture, Trench Widening	489.000	TON				
0850	501-K001	Transverse Grooving	5,311.000	SY		2.51	2.65	2.64
0860	803-B002	Conventional Static Pile Load Test	6.000	EA		5,000.00	5,000.00	5,000.00
0870	803-C002	14" x 14" Prestressed Concrete Piling	2,375.000	LF		32.00	39.00	36.00
0880	803-C003	16" x 16" Prestressed Concrete Piling	4,425.000	LF		38.00	44.00	41.00
0890	803-D003	HP 14 x 73 Steel Piling	2,280.000	LF		48.00	58.00	48.35
0900	803-D007	HP 14 x 89 Steel Piling	1,755.000	LF		56.00	68.00	56.10
0910	803-I001	PDA Test Pile	13.000	EA		5,381.50	8,000.00	6,300.00
0920	803-J001	Pile Restrike	6.000	EA		2,440.61	700.00	500.00
0930	805-A001	Reinforcement	513,883.000	LBS		0.94	0.90	0.92
0940	813-A001	Concrete Railing	2,390.000	LF		35.00	38.00	44.70
0950	815-A009	Loose Riprap, Size 300	1,170.000	TON		51.73	60.00	56.00
0960	815-E001	Geotextile under Riprap	1,108.000	SY		4.03	2.60	2.44
0970	907-804-A001	Bridge Concrete, Class AA	756.000	CY		500.00	600.00	550.00
0980	907-804-A012	Bridge Concrete, Class BD	1,568.000	CY		876.21	875.00	850.00
0990	907-804-C016	40' Prestressed Concrete Beam, Type I+2	4,956.000	LF		60.00	60.00	87.00
1000	907-804-C030	80' Prestressed Concrete Beam, Type III	1,436.000	LF		65.00	90.00	120.00
1010	907-804-C150	110' Prestressed Concrete Beam, Type IV	768.000	LF		125.00	130.00	151.00

LEAKE (40)					Malouf Construction, LLC			
Replacement of Bridges No. 98.7, No. 101.0 and No. 101.5 on SR 16 between the Madison County Line and SR 25, known as State Project No. BR-0024-03(014) / 100490302, in the County of Leake, State of Mississippi.					\$10,382,368.05			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0010	201-A001	Clearing and Grubbing	1.000	LS	200,000.00			
0020	201-B001	Clearing and Grubbing	1.000	ACRE	3,200.00			
0030	202-A001	Removal of Obstructions	1.000	LS	100,000.00			
0040	202-B005	Removal of Asphalt Pavement, All Depths	4,317.000	SY	4.00			
0050	202-B064	Removal of Pipe, 8" And Above	21.000	LF	27.00			
0060	202-B076	Removal of Traffic Stripe	3,900.000	LF	1.12			
0070	202-B102	Removal of Guard Rail	2,092.000	LF	3.30			
0080	202-B130	Removal of Piling	20.000	EA	360.00			
0090	203-EX027	Borrow Excavation, AH, FME, Class B14	69,036.000	CY	8.65			
0100	211-B001	Topsoil for Slope Treatment, Contractor Furnished	14,616.000	CY	9.52			
0110	213-C001	Superphosphate	18.000	TON	750.00			
0120	215-A001	Vegetative Materials for Mulch	103.000	TON	215.00			
0130	217-A001	Ditch Liner	488.000	SY	2.30			
0140	220-A001	Insect Pest Control	18.000	ACRE	30.00			
0150	221-A001	Portland Cement Concrete Paved Ditch	55.000	CY	375.00			
0160	223-A001	Mowing	1.000	ACRE	40.00			
0170	224-A001	Soil Reinforcing Mat	267.000	SY	5.00			
0180	234-A001	Temporary Silt Fence	25,000.000	LF	2.60			
0190	235-A001	Temporary Erosion Checks	1,122.000	BALE	8.65			
0200	239-A001	Temporary Slope Drains	143.000	LF	9.45			
0210	406-A001	Cold Milling of Bituminous Pavement, All Depths	1,067.000	SY	12.00			
0220	501-E001	Expansion Joints, Without Dowels	291.000	LF	9.60			
0230	501-K001	Transverse Grooving	603.000	SY	2.76			
0240	502-A001	Reinforced Cement Concrete Bridge End Pavement	621.000	SY	98.00			
0250	603-CB005	42" Reinforced Concrete End Section	2.000	EA	2,100.00			
0260	606-B001	Guard Rail, Class A, Type 1	1,275.000	LF	17.60			

LEAKE (40)					Malouf Construction, LLC			
Replacement of Bridges No. 98.7, No. 101.0 and No. 101.5 on SR 16 between the Madison County Line and SR 25, known as State Project No. BR-0024-03(014) / 100490302, in the County of Leake, State of Mississippi.					\$10,382,368.05			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0270	606-D012	Guard Rail, Bridge End Section, Type I	12.000	EA	2,200.00			
0280	606-E002	Guard Rail, Terminal End Section, Flared	12.000	EA	2,100.00			
0290	615-A018	Concrete Bridge End Barrier, 33.5"	120.000	LF	38.00			
0300	618-A001	Maintenance of Traffic	1.000	LS	50,000.00			
0310	619-A1001	Temporary Traffic Stripe, Continuous White	11,966.000	LF	0.22			
0320	619-A2001	Temporary Traffic Stripe, Continuous Yellow	11,966.000	LF	0.22			
0330	619-A2005	Temporary Traffic Stripe, Continuous Yellow, Type 1 or 2 Tap	3,900.000	LF	1.11			
0340	619-A5003	Temporary Traffic Stripe, Detail, Type 1 or 2 Tape	4,769.000	LF	1.11			
0350	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	139.000	EA	5.55			
0360	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	116.000	SF	9.25			
0370	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	714.000	SF	9.25			
0380	619-F3004	Delineators, Guard Rail, White	36.000	EA	20.00			
0390	619-G4001	Barricades, Type III, Single Faced	98.000	LF	30.00			
0400	619-G4005	Barricades, Type III, Double Faced	24.000	LF	35.00			
0410	619-G5001	Free Standing Plastic Drums	42.000	EA	75.00			
0420	619-G7001	Warning Lights, Type "B"	4.000	EA	925.00			
0430	620-A001	Mobilization	1.000	LS	630,000.00			
0440	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	180.000	EA	5.55			
0450	628-J002	6" High Performance Cold Plastic Traffic Stripe, Continuous	2,624.000	LF	5.55			
0460	628-M002	6" High Performance Cold Plastic Traffic Stripe, Continuous	2,624.000	LF	5.55			
0470	630-F001	Delineators, Guard Rail, White	66.000	EA	19.80			
0480	630-G002	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	12.000	EA	83.00			
0490	699-A001	Roadway Construction Stakes	1.000	LS	265,000.00			
0500	815-A006	Loose Riprap, Size 100	1,000.000	TON	41.50			
0510	815-A009	Loose Riprap, Size 300	1,721.000	TON	42.20			
0520	815-E001	Geotextile under Riprap	1,384.000	SY	2.20			

LEAKE (40)					Malouf Construction, LLC			
Replacement of Bridges No. 98.7, No. 101.0 and No. 101.5 on SR 16 between the Madison County Line and SR 25, known as State Project No. BR-0024-03(014) / 100490302, in the County of Leake, State of Mississippi.					\$10,382,368.05			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0530	815-F002	Sediment Control Stone	1,000.000	TON	40.00			
0540	907-225-A001	Grassing	75.000	ACRE	800.00			
0550	907-225-B001	Agricultural Limestone	109.000	TON	86.00			
0560	907-226-A001	Temporary Grassing	27.000	ACRE	800.00			
0570	907-237-A003	Wattles, 20"	1,000.000	LF	4.00			
0580	907-245-A001	Triangular Silt Dike	500.000	LF	10.00			
0590	907-246-A001	Sandbags	500.000	LF	3.00			
0600	907-304-B001	Granular Material, Class 5, Group C	8,652.000	TON	23.00			
0610	907-304-B005	Granular Material, Class 9, Group C	22,830.000	TON	12.50			
0620	907-307-C003	6" Soil-Lime-Water Mixing, Class C	1,914.000	SY	4.90			
0630	907-307-D001	Lime	26.000	TON	250.00			
0640	907-407-A001	Asphalt for Tack Coat	3,743.000	GAL	3.25			
0650	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	291.000	LF	34.60			
0660	907-601-B003	Class "B" Structural Concrete, Minor Structures	1.000	CY	1,700.00			
0670	907-603-ALT01	18" Type A Alternate Pipe	52.000	LF	61.00			
0680	907-603-ALT05	42" Type A Alternate Pipe	48.000	LF	132.00			
0690	907-617-A001	Right-of-Way Marker	25.000	EA	235.00			
0700	907-618-D001	Construction and Removal of Detour Road	1.000	LS	2,700,000.00			
0702	907-618-E001	Detour Bridge Piling	3,250.000	LF	51.90			
0704	907-618-F001	Detour Bridge Test Pile	1.000	LS	65,000.00			
0710	907-626-C007	6" Thermoplastic Double Drop Edge Stripe, Continuous White	11,780.000	LF	0.61			
0720	907-626-D005	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	4,250.000	LF	0.22			
0730	907-626-E005	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yell	3,360.000	LF	0.61			
0740	907-308-A001	Portland Cement	96.000	TON	166.00			
0750	907-308-B002	Soil-Cement-Water Mixing, Optional Mixers, Design Soil	11,310.000	SY	1.85			
0760	907-311-A003	Processing Lime and Fly Ash Treated Course, 6" Thick	11,310.000	SY				

LEAKE (40)					Malouf Construction, LLC			
Replacement of Bridges No. 98.7, No. 101.0 and No. 101.5 on SR 16 between the Madison County Line and SR 25, known as State Project No. BR-0024-03(014) / 100490302, in the County of Leake, State of Mississippi.					\$10,382,368.05			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0770	907-311-B001	Lime	82.000	TON				
0780	907-311-C002	Fly Ash, Class C or F	326.000	TON				
0790	907-403-A006	Hot Mix Asphalt, MT, 12.5-mm mixture	2,055.000	TON				
0800	907-403-A007	Hot Mix Asphalt, MT, 19-mm mixture	1,206.000	TON				
0810	907-403-C003	Hot Mix Asphalt, MT, 19-mm mixture, Trench Widening	489.000	TON				
0820	907-403-M002	Warm Mix Asphalt, MT, 12.5-mm mixture	2,055.000	TON	95.00			
0830	907-403-M007	Warm Mix Asphalt, MT, 19-mm mixture	1,206.000	TON	100.00			
0840	907-403-O003	Warm Mix Asphalt, MT, 19-mm mixture, Trench Widening	489.000	TON	105.00			
0850	501-K001	Transverse Grooving	5,311.000	SY	2.70			
0860	803-B002	Conventional Static Pile Load Test	6.000	EA	5,000.00			
0870	803-C002	14" x 14" Prestressed Concrete Piling	2,375.000	LF	50.00			
0880	803-C003	16" x 16" Prestressed Concrete Piling	4,425.000	LF	54.00			
0890	803-D003	HP 14 x 73 Steel Piling	2,280.000	LF	64.40			
0900	803-D007	HP 14 x 89 Steel Piling	1,755.000	LF	73.95			
0910	803-I001	PDA Test Pile	13.000	EA	14,000.00			
0920	803-J001	Pile Restrike	6.000	EA	1.00			
0930	805-A001	Reinforcement	513,883.000	LBS	0.84			
0940	813-A001	Concrete Railing	2,390.000	LF	42.45			
0950	815-A009	Loose Riprap, Size 300	1,170.000	TON	42.00			
0960	815-E001	Geotextile under Riprap	1,108.000	SY	2.50			
0970	907-804-A001	Bridge Concrete, Class AA	756.000	CY	826.00			
0980	907-804-A012	Bridge Concrete, Class BD	1,568.000	CY	766.00			
0990	907-804-C016	40' Prestressed Concrete Beam, Type I+2	4,956.000	LF	65.00			
1000	907-804-C030	80' Prestressed Concrete Beam, Type III	1,436.000	LF	101.00			
1010	907-804-C150	110' Prestressed Concrete Beam, Type IV	768.000	LF	148.00			