

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) further propose to execute the attached contract agreement (Section 902) as soon as the work is awarded to me (us), and to begin and complete the work within the time limit(s) provided for in the Specifications and Advertisement. I (We) also propose to execute the attached contract bond (Section 903) in an amount not less than one hundred (100) percent of the total of my (our) part, but also to guarantee the excellence of both workmanship and materials until the work is finally accepted.

I (We) enclose a certified check, cashier's check or bid bond for **five percent (5%) of total bid** and hereby agree that in case of my (our) failure to execute the contract and furnish bond within Ten (10) days after notice of award, the amount of this check (bid bond) will be forfeited to the State of Mississippi as liquidated damages arising out of my (our) failure to execute the contract as proposed. It is understood that in case I am (we are) not awarded the work, the check will be returned as provided in the Specifications.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. 1 DATED 4/19/2011 ADDENDUM NO. DATED
 ADDENDUM NO. DATED ADDENDUM NO. DATED

Number	Description
1	Revised Table of Contents, replace same; Revised NTB Nos. 3422 & 3434, replace same; Added NTB Nos. 3496 & 3497; Bidsheets, replace same; Revised or Add Plan Sheet Nos. 2, 4-9, 12, 13, 15, 18, 30.01, & 205; Amendment EBS Download required.

TOTAL ADDENDA: 1
 (Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

 Contractor

BY _____
 Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

_____ President	_____ Address
_____ Secretary	_____ Address
_____ Treasurer	_____ Address

The following is my (our) itemized proposal.

IM-0055-04(087) / 105073301

Panola County(ies)

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

TABLE OF CONTENTS

PROJECT: IM-0055-04(087) / 105073301 – Panola County

901--Advertisement

904--Notice to Bidders:

- Governing Specs. - # 1
- Final Cleanup - # 3
- Fiber Reinforced Concrete - # 640
- Disadvantage Business Enterprise, W/ Supplement - # 696
- On-The-Job Training Program - # 777
- Payroll Requirements - # 883
- Use of Fly Ash in Stone Matrix Asphalt (SMA) - # 927
- Rumble Stripe - # 1312
- Errata & Modifications to 2004 Standard Specifications - # 1405
- Safety Apparel - # 1808
- Federal Bridge Formula - # 1928
- Department of Labor Ruling - # 2239
- Status of ROW, W/ Attachments - # 2382
- DBE Forms, Participation and Payment - # 2596
- Non-Quality/Quality Assurance Concrete - # 2818
- Petroleum Products Base Price - # 2858
- Storm Water Discharge Associated with Construction Activities (≥ 5 Acres) - # 2905
- Reduce Speed Limit Signs - # 2937
- Alternate Asphalt Mixture Bid items - # 3039
- Temporary Traffic Paint - # 3131
- Warm Mix Asphalt (WMA) - # 3242
- Shoulder Wedge - # 3367
- Additional Erosion Control Requirements - # 3411
- DUNS Requirement for Federal Projects - # 3414
- Contract Time - # 3420
- Specialty Items - # 3421
- Lane Closure Restrictions - # 3422
- Early Strength Concrete Testing - # 3423
- Sawing and Sealing Joints - # 3424
- Questions Regarding Bidding - # 3425
- Milling Material - # 3434
- Cold Milling Plan – # 3496
- Silt Fence Reinforcement - # 3497

906: Required Federal Contract Provisions -- FHWA-1273, W/ Supplements

907-101-4: Definitions

907-102-8: Bidding Requirements and Conditions

907-103-8: Award and Execution of Contract

907-104-1: Partnering Process

907-104-4: Disposal of Materials

907-105-6: Control of Work, W/ Supplement

907-107-9: Legal Relations & Responsibility to Public

907-107-10: Contractor's Erosion Control Plan

-- CONTINUED ON NEXT PAGE --

- 907-108-24: Prosecution and Progress
- 907-109-5: Measurement and Payment
- 907-110-2: Wage Rates
- 907-225-2: Grassing
- 907-237-3: Wattles
- 907-246-3: Sandbags & Rockbags
- 907-304-12: Granular Courses
- 907-401-2: Hot Mix Asphalt (HMA), W/ Supplement
- 907-401-3: Stone Matrix Asphalt (SMA)
- 907-401-4: Warm Mix Asphalt (WMA), W/ Supplement
- 907-402-3: Open Graded Friction Course (OGFC)
- 907-403-4: Hot Mix Asphalt (HMA), W/ Supplement
- 907-403-5: Stone Matrix Asphalt (SMA), W/ Supplement
- 907-403-9: Warm Mix Asphalt (WMA), W/ Supplement
- 907-407-1: Tack Coat
- 907-413-1: Cleaning and Filling Joints in PCC (Portland Cement Concrete) Pavement
- 907-413-2: Sawing & Sealing Transverse Joints in Asphalt Pavement
- 907-605-3: Underdrains
- 907-606-4: High Tension Cable Barrier
- 907-618-4: Placement of Temporary Traffic Stripe
- 907-619-5: Changeable Message Sign
- 907-626-15: Thermoplastic Traffic Marking
- 907-631-1: Flowable Fill
- 907-701-4: Hydraulic Cement
- 907-703-9: Aggregates, W/ Supplement
- 907-707-2: Joint Material
- 907-710-1: Fast Dry Solvent Traffic Paint
- 907-711-4: Synthetic Structural Fiber Reinforcement
- 907-713-2: Admixtures for Concrete
- 907-714-3: Stabilizing Fibers
- 907-714-6: Miscellaneous Materials
- 907-715-3: Roadside Development Materials
- 907-720-1: Pavement Marking Materials
- 907-804-13: Concrete Bridges and Structures

- 906-3: MDOT On-the-Job Training Program
- 906-6: MDOT On-the-Job Training Program - Alternate Program

SECTION 905 - PROPOSAL,
PROPOSAL BID SHEETS,
COMBINATION BID PROPOSAL,
CERTIFICATION OF PERFORMANCE - PRIOR FEDERAL-AID CONTRACTS,
CERTIFICATION REGARDING NON-COLLUSION, DEBARMENT AND SUSPENSION,
SECTION 902 - CONTRACT FORM, AND SECTION 903 - CONTRACT BOND FORMS,
OCR-485.

(REVISIONS TO THE ABOVE WILL BE INDICATED ON THE SECOND SHEET
OF SECTION 905 AS ADDENDA)

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904- NOTICE TO BIDDERS NO. 3422

CODE: (SP)

DATE: 4/18//2011

SUBJECT: Lane Closure Restrictions

PROJECT: IM-0055-04-(087) / 105073301 – Panola County

Bidders are hereby advised of the following lane closure restrictions:

- 1) Lane closures will not be permitted in the following areas at the listed times:

I-55 INTERCHANGE AT SR 6/ US 278 (RAMPS/LOOPS & SR 6/ US278 ONLY)

NO LANE CLOSURES WILL BE PERMITTED MONDAY THROUGH FRIDAY 7:00 A.M. TO 10:00 A.M AND FROM 3:00 PM TO 6:00 PM IN EITHER TRAVEL DIRECTION OF SR 6/US 278 FROM 1 MILE EAST OF THE EASTERNMOST ON/OFF RAMPS/LOOPS TO 1 MILE WEST OF THE WESTERNMOST RAMPS/LOOPS INCLUDING RAMPS AND LOOPS CONNECTING I-55 AND SR 6/US 278. NO EXCUSES WILL BE ACCEPTED BY THE DEPARTMENT AND THE CONTRACTOR WILL BE CHARGED A FEE OF \$400.00 FOR EACH FULL OR PARTIAL FIVE MINUTE PERIOD DURING WHICH LESS THAN THE PRESENTLY AVAILABLE RAMPS/LOOPS AND ROADWAY ARE NOT AVAILABLE TO THE TRAVELING PUBLIC.

- 2) Lane closures may remain in place overnight for the following excepting Interchange Ramps/Loops:
 - A.) To allow for cooling of a lift of hot/warm mix asphalt.
 - B.) To restrict public access to a section of roadway that has been cold milled resulting in a longitudinal drop off that exceeds the Department's allowable drop –off policy.
 - C.) To restrict public access to a section of roadway that is undergoing full depth concrete repair.
- 3) Lane closures that remain in place overnight shall comply with the requirements of the plans for Extended Period lane closures.
- 4) If the lane closure restrictions listed above are violated, the Contractor will be charged a fee according to the corresponding location listed above until the roadway is back in compliance with the applicable lane closure restriction requirement. In the below items 3 through 6, the notes are considered as project wide and fees will be charged as noted above for nonconformance.
- 3.) No lane closures will be allowed on holidays such as New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Christmas Day and the day preceding each holiday. In the event that any of the afore mentioned holidays occurs during a weekend or on a Monday, lane closures will not be allowed during that weekend or on the Friday immediately preceding the holiday. For Thanksgiving Day, lane closures will not be allowed the Wednesday preceding through the Sunday following the holiday.

- 4) Approval for work on Saturdays requiring a lane closure shall be requested by the Contractor by letter to the Project Engineer no later than 48 hours preceding the Saturday of the proposed closure. **No closures** will be permitted on University of Mississippi (Ole Miss) Football Home game weekends held in Oxford, MS.
- 5) Work requiring a lane closure shall begin within the limits of the closure within one (1) hour of the closure set-up. The Contractor will be assessed a lane rental fee at the rate of \$400.00 per closure for each full or partial five (5) minute period should failure to begin work within the allotted time occur.
- 6) Sunday Work **will not** be permitted.
- 7.) For the purpose for this contract, the official time is considered to be the announced time available at Batesville area telephone number (662) 563-1000.

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904 -NOTICE TO BIDDERS NO. 3434

CODE: (SP)

DATE: 04/18/2011

SUBJECT: Milling Material

PROJECT: IM-0055-04(087) / 105073301 ---- PANOLA COUNTY

Bidders are hereby advised that the following conditions apply to the Cold Milling required by the contract:

Cold Milling material shall be stockpiled by the contractor for MDOT as shown below:

0.25 miles full lane width (12 feet) at full depth (4") --- Stockpiled at the Batesville Maintenance Headquarters on Dettor Street in Batesville, MS.

0.50 miles full lane width (12 feet) at full depth (4") --- Stockpiled at the Oxford Maintenance Headquarters on Hwy 7 South in Oxford, MS.

1.0 mile full lane width (12 feet) at full depth (4") --- Stockpiled at the Senatobia Maintenance Headquarters on Shands Bottom Road near SR 740 in Senatobia, MS.

1.0 mile full lane width (12 feet) at full depth (4") --- Stockpiled at the Marks Maintenance Headquarters on Hwy 6 (US Hwy 278) in Marks, MS.

Adequate equipment must be available to properly stockpile this material (A front-end loader and/or dozer will be the required minimum). The remainder of the Cold Milling Material shall become the property of the contractor. Payment for Cold Milling of Pavement will be made under Pay Item No. 406-A, per square yard, and shall include all cost associated with the milling operation.

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

| SECTION 904 -NOTICE TO BIDDERS NO. 3496

CODE: (SP)

| DATE: 04/18/2011

SUBJECT: Cold Milling Plan

| PROJECT: IM-0055-04(087) / 105073301 - Panola County

Bidders are hereby advised of the following:

A minimum of one traffic lane in each direction shall remain open at all times. In the event that the contractor exceeds the time allotted in the below Note 5, a fee in the amount of \$400.00 for each five minute interval or part thereof shall be assessed until the roadway is open and in compliance with this Notice To Bidders.

The contractor shall submit for approval a plan to mill the existing asphalt to the existing concrete surface, complete any punchout repairs, and clean and fill the existing concrete pavement joints at the preconstruction conference for this project.

The following must be addressed in this plan:

1. The number of passes the milling machine will make, including the shoulders.
2. The depth of the cold milling that each pass will make.
3. The width of each pass of the cold milling machine.
4. The conformity of the plan to the MDOT Drop Off Policy.
5. The estimated time frame for traffic to use a milled surface.
The maximum time allowed will be ten (10) days.
6. The sequence of operations and timelines to complete punchout repairs, cleaning and filling of concrete pavement joints.

Work on the milling phase of this project shall not commence until the Engineer approves this Milling Plan.

Cold Milling will be measured and paid based on a 4" and variable mill thickness.

Pay Item No 615-B001, Precast Concrete Median Barrier, provided in the contract is not intended for the milling phase of this contract. No payment for Precast Concrete Median Barrier (if made a part of this plan) will be permitted for the milling phase of this contract.

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904- NOTICE TO BIDDERS NO. 3497

CODE: (SP)

DATE: 04/18/2011

SUBJECT: Silt Fence Reinforcement

PROJECT: IM-0055-04 (087)/ 105073301 – Panola County

The Contractor is hereby advised that all silt fence applications on this project will require wire backing. Standard Drawings in the plans show applications with or without wire backing; however, it will be a requirement to include wire backing on all applications and payment for the wire backing will be considered absorbed in the temporary silt fence pay item.

Mill and Overlay I-55 from SR 6 to Cobb Road, known as Federal Aid Project No. IM-0055-04(087) / 105073301, in the County of Panola, State of Mississippi.

I (We) agree to complete the entire project within the specified contract time.

*** SPECIAL NOTICE TO BIDDERS ***

**BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED.
 BIDS WILL NOT BE CONSIDERED UNLESS THE BID CERTIFICATION LOCATED AT THE END OF THE BID SHEETS IS SIGNED**

BID SCHEDULE

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Item Amount	
						Dollar	Ct	Dollar	Ct
Roadway Items									
0010	201-A001		1	Lump Sum	Clearing and Grubbing	XXXXXXXXXX	XXX		
0020	202-B005		450	Square Yard	Removal of Asphalt Pavement, All Depths				
0025	202-B030 Added 04/18/2011		1,100	Square Yard	Removal of Concrete Pavement, All Depths				
0030	202-B043		13	Each	Removal of Guard Rail Bridge End Section				
0040	202-B076		10,500	Linear Feet	Removal of Traffic Stripe				
0050	202-B097 Changed 04/18/2011		450	Square Yard	Removal of Concrete Overlayed w/ Asphalt Pavement, All Depths				
0060	202-B102		2,125	Linear Feet	Removal of Guard Rail				
0070	202-B113		4	Each	Removal of Box Culvert Wingwall, All Sizes				

Section 905
 Proposal (Sheet 2 - 2)

IM-0055-04(087) / 105073301
 Panola County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0080	203-A003	(E)	3,000	Cubic Yard	Unclassified Excavation, FM, AH		
0090	203-G003	(E)	30,000	Cubic Yard	Excess Excavation, FM, AH		
0100	209-A004		5,500	Square Yard	Geotextile Stabilization, Type V, Non-Woven		
0110	213-C001		2	Ton	Superphosphate		
0120	217-A001		100	Square Yard	Ditch Liner		
0130	220-A001		2	Acre	Insect Pest Control	30.00	60.00
0140	221-A001	(S)	185	Cubic Yard	Portland Cement Concrete Paved Ditch		
0150	223-A001		4	Acre	Mowing	40.00	160.00
0160	234-A001		3,000	Linear Feet	Temporary Silt Fence		
0170	406-A001		350,000	Square Yard	Cold Milling of Bituminous Pavement, All Depths		
0180	423-A001		24	Mile	Rumble Strips, Ground In		
0190	501-G001		1,500	Each	Dowels, Drilled and Installed		

Section 905
 Proposal (Sheet 2 - 3)

IM-0055-04(087) / 105073301
 Panola County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0200	503-A016	(C)	900	Square Yard	9" and Variable Plain Concrete Pavement, Broom Finish		
0210	503-B001		800	Linear Feet	Saw Cut, Longitudinal Joints		
0220	503-C002		100	Linear Feet	Saw Cut, 3-inch		
0230	503-C007		1,500	Linear Feet	Saw Cut, Full Depth		
0240	503-D001		30	Cubic Yard	Concrete for Base Repair		
0250	606-B001 Changed 04/18/2011		2,200	Linear Feet	Guard Rail, Class A, Type 1		
0260	606-C003		4	Each	Guard Rail, Cable Anchor, Type 1		
0270	606-D001		12	Each	Guard Rail, Bridge End Section, Type A		
0280	606-D008		2	Each	Guard Rail, Bridge End Section, Type H		
0290	606-D012		4	Each	Guard Rail, Bridge End Section, Type I		
0300	606-E001		17	Each	Guard Rail, Terminal End Section		
0310	615-A012	(S)	137	Linear Feet	Concrete Type IV Modified, 42" Height, Cast-in-Place Median Barrier		

Section 905
 Proposal (Sheet 2 - 4)

IM-0055-04(087) / 105073301
 Panola County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0320	615-B001	(S)	1,000	Linear Feet	Precast Concrete Median Barrier		
0330	618-A001		1	Lump Sum	Maintenance of Traffic	XXXXXXXXXX	XXXX
0340	619-A1002 Changed 04/18/2011		45	Mile	Temporary Traffic Stripe, Continuous White		
0350	619-A2002 Changed 04/18/2011		45	Mile	Temporary Traffic Stripe, Continuous Yellow		
0360	619-A3006 Changed 04/18/2011		45	Mile	Temporary Traffic Stripe, Skip White		
0370	619-A5001		15,000	Linear Feet	Temporary Traffic Stripe, Detail		
0380	619-A6001		600	Linear Feet	Temporary Traffic Stripe, Legend		
0390	619-D1001		48	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet		
0400	619-D2001		176	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More		
0410	619-F2001		1,000	Linear Feet	Remove and Reset Concrete Median Barrier, Precast		
0420	619-G4001		72	Linear Feet	Barricades, Type III, Single Faced		
0430	619-G4005		24	Linear Feet	Barricades, Type III, Double Faced		

Section 905
 Proposal (Sheet 2 - 5)

IM-0055-04(087) / 105073301
 Panola County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0440	619-G5001		250	Each	Free Standing Plastic Drums		
0450	620-A001		1	Lump Sum	Mobilization	XXXXXXXXXX	XXXX
0460	627-K001		3,750	Each	Red-Clear Reflective High Performance Raised Markers		
0470	627-L001		500	Each	Two-Way Yellow Reflective High Performance Raised Markers		
0480	630-F001		82	Each	Delineators, Guard Rail, White		
0490	630-F002		75	Each	Delineators, Guard Rail, Yellow		
0500	630-F008		320	Each	Delineators, Post Mounted, Double White		
	Changed 04/18/2011						
0510	630-F006		60	Each	Delineators, Post Mounted, Single White		
0520	630-F007		35	Each	Delineators, Post Mounted, Single Yellow		
0530	630-F009		100	Each	Delineators, Post Mounted, Double Yellow		
0540	630-G002		24	Each	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted		
0550	635-A001		48	Linear Feet	Vehicle Loop Assemblies		

Section 905
 Proposal (Sheet 2 - 6)

IM-0055-04(087) / 105073301
 Panola County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0560	699-A001		1	Lump Sum	Roadway Construction Stakes	XXXXXXXXXX XXXX	
0570	907-225-A001		4	Acre	Grassing		
0580	907-225-B001		12	Ton	Agricultural Limestone		
0590	907-237-A003		300	Linear Feet	Wattles, 20"		
0600	907-246-A002		50	Each	Sandbags		
0610	907-304-B009	(GT)	20,000	Ton	Granular Material, Class 3, Group D		
0620	907-304-F002	(GT)	4,000	Ton	Size 610 Crushed Stone Base		
0630	907-402-A002	(BA1)	11,000	Ton	Hot Mix Asphalt, Open Graded Friction Course, 9.5mm Mixture		
0640	907-402-B001	(A3)	12,700	Gallon	Bituminous Tack Coat		
0650	907-403-AA002	(BA1)	40,000	Ton	Stone Matrix Asphalt, 12.5 mm Mixture		
0660	907-403-S002		30	Mile	Joint Sealant for HMA		
	Changed 04/18/2011						
0670	907-407-A001	(A2)	80,000	Gallon	Asphalt for Tack Coat		

Section 905
 Proposal (Sheet 2 - 7)

IM-0055-04(087) / 105073301
 Panola County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0680	907-413-D001		96,000	Linear Feet	Cleaning and Filling Joints in PCC Pavement		
0690	907-413-E001		96,000	Linear Feet	Sawing and Sealing Transverse Joints in Asphalt Pavement		
0700	907-605-H001 (S)		80	Linear Feet	Edge Drain		
0710	907-605-I001 (S)		80	Linear Feet	Edge Drain Outlets/Vents		
0720	907-606-G001		4,925	Linear Feet	Cable Barrier		
0730	907-606-H001		12	Each	Cable Barrier Terminal Section		
0740	907-606-I001		100	Each	Cable Barrier Post Repair		
0750	907-619-E3001		2	Each	Changeable Message Sign		
0760	907-626-A003		12	Mile	6" Thermoplastic Traffic Stripe, Skip White		
0770	907-626-C004		12	Mile	6" Thermoplastic Edge Stripe, Continuous White		
0780	907-626-E003		5,000	Linear Feet	6" Thermoplastic Traffic Stripe, Continuous Yellow		
0790	907-626-F004		12	Mile	6" Thermoplastic Edge Stripe, Continuous Yellow		

Section 905
Proposal (Sheet 2 - 8)

IM-0055-04(087) / 105073301
Panola County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0800	907-626-G004		5,000	Linear Feet	Thermoplastic Detail Stripe, White		
0810	907-626-G005		5,000	Linear Feet	Thermoplastic Detail Stripe, Yellow		
0820	907-626-H004		200	Linear Feet	Thermoplastic Legend, White		
0830	907-631-A001		2,600	Cubic Yard	Flowable Fill, Excavatatable		
ALTERNATE GROUP AA NUMBER 1							
0840	907-403-A002 (BA1)		6,500	Ton	Hot Mix Asphalt, HT, 19-mm mixture		
0850	907-403-A005 (BA1)		4,000	Ton	Hot Mix Asphalt, HT, 9.5-mm mixture		
0860	907-403-A011 (BA1)		13,000	Ton	Hot Mix Asphalt, ST, 12.5-mm mixture		
0870	907-403-A012 (BA1)		6,500	Ton	Hot Mix Asphalt, ST, 19-mm mixture		
0880	907-403-D004 (BA1)		3,000	Ton	Hot Mix Asphalt, HT, 9.5-mm mixture, Polymer Modified		
ALTERNATE GROUP AA NUMBER 2							
0890	907-403-M003 (BA1)		13,000	Ton	Warm Mix Asphalt, ST, 12.5-mm mixture		
0900	907-403-M004 (BA1)		6,500	Ton	Warm Mix Asphalt, ST, 19-mm mixture		

Section 905
 Proposal (Sheet 2 - 9)

IM-0055-04(087) / 105073301
 Panola County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0910	907-403-M009	(BA1)	4,000	Ton	Warm Mix Asphalt, HT, 9.5-mm mixture		
0920	907-403-M011	(BA1)	6,500	Ton	Warm Mix Asphalt, HT, 19-mm mixture		
0930	907-403-P001	(BA1)	3,000	Ton	Warm Mix Asphalt, HT, 9.5-mm mixture, Polymer Modified		
ALTERNATE GROUP BB NUMBER 1							
0940	907-626-I003		3,500	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Skip White		
0950	907-626-I003		3,500	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White		
0960	907-626-L001		3,500	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow		
ALTERNATE GROUP BB NUMBER 2							
0970	628-I002		3,500	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Skip White		
0980	628-I002		3,500	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Continuous White		
0990	628-M002		3,500	Linear Feet	6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow		

*** BID CERTIFICATION ***

TOTAL BID \$ _____

*** DBE/WBE SECTION ***

Complete item nos. 1, 2, and/or 3 as appropriate. See Notice to Bidders addressing Disadvantaged Business Enterprises in Highway Construction.

1. I/We agree that no less than _____ percent shall be expended with small business concerns owned and controlled by socially and economically disadvantaged individuals (DBE and WBE).
2. Classification of Bidder: Small Business (DBE) _____ Small Business (WBE) _____
3. A joint venture with a Small Business (DBE/WBE): _____

*** SIGNATURE STATEMENT ***

BIDDER ACKNOWLEDGES THAT HE/SHE HAS CHECKED ALL ITEMS IN THIS PROPOSAL FOR ACCURACY AND CERTIFIED THAT THE FIGURES SHOWN THEREIN CONSTITUTE THEIR OFFICIAL BID.

BIDDER'S SIGNATURE

BIDDER'S COMPANY

BIDDER'S FEDERAL TAX ID NUMBER