

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) further propose to execute the attached contract agreement (Section 902) as soon as the work is awarded to me (us), and to begin and complete the work within the time limit(s) provided for in the Specifications and Advertisement. I (We) also propose to execute the attached contract bond (Section 903) in an amount not less than one hundred (100) percent of the total of my (our) part, but also to guarantee the excellence of both workmanship and materials until the work is finally accepted.

I (We) enclose a certified check, cashier's check or bid bond for **five percent (5%) of total bid** and hereby agree that in case of my (our) failure to execute the contract and furnish bond within Ten (10) days after notice of award, the amount of this check (bid bond) will be forfeited to the State of Mississippi as liquidated damages arising out of my (our) failure to execute the contract as proposed. It is understood that in case I am (we are) not awarded the work, the check will be returned as provided in the Specifications.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. 1 DATED 4/19/2011 ADDENDUM NO. DATED
 ADDENDUM NO. DATED ADDENDUM NO. DATED

Number	Description
1	Revised Table of Contents, replace same; NTB No. 3481 replaces 883; Revised NTB No. 3450, replaces same; Add NTB No. 3505; Bidsheets, replace same; Amendment EBS Download required.

TOTAL ADDENDA: 1
 (Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

 Contractor

BY _____
 Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

_____ President	_____ Address
_____ Secretary	_____ Address
_____ Treasurer	_____ Address

The following is my (our) itemized proposal.

Revised 09/21/2005

BR-6962-00(006) / 105414301

Rankin County(ies)

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

TABLE OF CONTENTS

PROJECT: BR-6962-00(006) / 105414301 -- Rankin County

904--Notice to Bidders:	Governing Specs. - # 1
	Final Cleanup - # 3
	Fiber Reinforced Concrete - # 640
	On-The-Job Training Program - # 777
	Rumble Stripes _ # 1312
	Errata & Modifications to 2004 Standard Specifications - # 1405
	Safety Apparel - # 1808
	Federal Bridge Formula - # 1928
	Exposure to Severe Sulfate Areas Below Ground Level - # 2366
	Status of ROW, <u>W/Attachments</u> - # 2382
	Non-Quality Control/Quality Assurance Concrete - # 2818
	Petroleum Products Base Price - # 2858
	Storm Water Discharge Associated with Construction Activities (≥ 5 Acres) - # 2905
	Reduced Speed Limit Signs - # 2937
	Alternate Asphalt Mixture Bid items - # 3039
	Temporary Traffic Paint - # 3131
	Warm Mix Asphalt (WMA) - # 3242
	Contract Time - # 3362
	Specialty Items - # 3363
	Placement of Fill Material in Federally Regulated Areas - # 3364
	Shoulder Wedge - # 3367
	Detour Bridge Railing - # 3404
	Additional Erosion Control Requirements - # 3411
	Questions Regarding Bidding - # 3425
	Lane Closure Restrictions - # 3449
	Bridge Deck Concrete - # 3450
	Payroll Requirements for General Obligation Bond Projects - # 3481
	Treated Courses - # 3505

906: Wage Rates

907-101-4:	Definitions
907-102-8:	Bidding Requirements and Conditions
907-103-8:	Award and Execution of Contract
907-104-4:	Disposal of Materials
907-105-6:	Control of Work, <u>W/Supplement</u>
907-107-9:	Legal Relations & Responsibility to Public
907-107-10:	Contractor's Erosion Control Plan
907-108-24:	Prosecution and Progress
907-109-5:	Measurement and Payment
907-225-2:	Grassing
907-226-1:	Temporary Grassing, <u>W/Supplement</u>
907-227-8:	Hydroseeding

PAGE 2 - PROJECT: BR-6962-00(006) / 105414301 -- Rankin County

- 907-234-5: Siltation Barriers
- 907-237-3: Wattles
- 907-246-3: Sandbags & Rockbags
- 907-304-12: Granular Courses
- 907-307-3: Lime Treated Courses
- 907-308-3: Cement Treated Courses
- 907-311-2: Lime-Fly Ash Treated Courses
- 907-401-2: Hot Mix Asphalt (HMA), W/ Supplement
- 907-401-4: Warm Mix Asphalt (WMA), W/ Supplement
- 907-403-4: Hot Mix Asphalt (HMA), W/ Supplement
- 907-403-9: Warm Mix Asphalt (WMA), W/Supplement
- 907-407-1: Tack Coat
- 907-603-8: Culverts & Storm Drains
- 907-617-2: Right-Of-Way Markers
- 907-618-4: Placement of Temporary Traffic Stripe
- 907-618-7: Construction and Removal of Detour Bridge
- 907-626-15: Thermoplastic Traffic Marking
- 907-626-22: Double Drop Thermoplastic Marking
- 907-701-4: Hydraulic Cement
- 907-703-9: Aggregates, W/Supplement
- 907-708-5: Non Metal Drainage Structures
- 907-709-1: Metal Pipe
- 907-710-1: Fast Dry Solvent Paint
- 907-711-4: Synthetic Structural Fiber Reinforcement
- 907-713-2: Admixtures for Concrete
- 907-714-6: Miscellaneous Materials
- 907-715-3: Roadside Development Materials
- 907-720-1: Pavement Marking Materials
- 907-804-12: Concrete Bridge Decks
- 907-804-13: Concrete Bridges and Structures

- 906-3: MDOT On-the-Job Training Program
- 906-6: MDOT On-the-Job Training Program - Alternate Program

SECTION 905 - PROPOSAL,
PROPOSAL SHEETS,
COMBINATION BID PROPOSAL,
STATE BOARD OF CONTRACTORS REQUIREMENTS,
CERTIFICATION REGARDING NON-COLLUSION, DEBARMENT AND SUSPENSION,
SECTION 902 - CONTRACT FORM, AND SECTION 903 - CONTRACT BOND FORM,
PILE DRIVING FORM.

(REVISIONS TO THE ABOVE WILL BE INDICATED ON THE SECOND SHEET
OF SECTION 905 AS ADDENDA)

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904 - NOTICE TO BIDDERS NO. 3481

CODE: (SP)

DATE: 04/12/2011

SUBJECT: Payroll Requirements for General Obligation Bond Projects

Bidders are hereby advised that the Contractor and Subcontractor(s) are required to submit payroll information to the Project Engineers on a weekly basis.

For this project, CAD-880, CAD-881 and certified payroll submissions are required each week the Contractor or a Subcontractor performs work on the project.

When no work is performed, the Contractor should only submit CAD-880 showing no work activities.

The Contractor shall make all efforts necessary to submit this information to the Project Engineer in a timely manner. The Engineer will have the authority to suspend the work wholly or in part and to withhold payments because of the Contractor's failure to submit the required information. Submission of forms and payrolls shall be current through the first full week of the month for the estimate period in order for the Project Engineer to process an estimate.

Bidders are advised to review the requirements regarding payroll submissions in Special Provision 907-110-3.

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904 - NOTICE TO BIDDERS NO. 3450

CODE: (SP)

DATE: 04/18/2011

SUBJECT: Bridge Deck Concrete

PROJECT: BR-6962-00(006) / 105414301 – Rankin County

Bidders are advised that this project has two special provisions for concrete structures. Special Provision No. 907-804-12 will be the governing specifications for all bridge deck concrete. All other concrete on the project must meet the requirements of Special Provision No. 907-804-13.

Bidders are also advised that MDOT will perform tests on the bridge deck concrete. MDOT will install maturity meters in the bridge deck prior to concrete placement by attaching each device to the deck reinforcing steel in the areas under the bridge rail. MDOT will also install internal humidity meters in the same area after concrete placement. Installing the devices should not interfere with any of the Contractor's operations. The devices shall not be disturbed by the Contractor for at least a month after placement. Additionally, the Department will need access to the devices during that time. For each maturity meter, only the wires will be visible and accessible after the concrete is placed. For each humidity meter, a PVC pipe, about 1½ inches OD will stick out of the deck surface about 1½ inches. Neither the maturity meters nor the PVC pipes will be removed. The bridge rail will cover up the devices once MDOT has completed taking measurements.

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904 - NOTICE TO BIDDERS NO. 3505

CODE: (SP)

DATE: 04/19/2011

SUBJECT: Treated Courses

PROJECT: BR-6962-00(006) / 105414301 - Rankin County

Bidders are advised that the pay items and quantities for removal of asphalt pavement and soil-cement treated courses shown on the Summary of Quantities sheets in the Plans are different than the pay items and quantities shown on the bid sheets in the proposal documents. The pay items and quantities on the plan sheets are in error. Bidders are advised to use the pay items and quantities listed on the bid sheets in the proposal when preparing their bids.

Construction necessary to Replace the Bridge on SR 468, across Terrapin Skin Creek, known as State Project No. BR-6962-00(006) / 105414301, in the County of Rankin, State of Mississippi.

I (We) agree to complete the entire project within the specified contract time.

SPECIAL NOTICE TO BIDDERS

**BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED.
 BIDS WILL NOT BE CONSIDERED UNLESS THE BID CERTIFICATION LOCATED AT THE END OF THE BID SHEETS IS SIGNED**

BID SCHEDULE

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Item Amount	
						Dollar	Ct	Dollar	Ct
Roadway Items									
0010	201-A001		1	Lump Sum	Clearing and Grubbing	XXXXXXXXXX	XXX		
0020	202-A001		1	Lump Sum	Removal of Obstructions	XXXXXXXXXX	XXX		
0030	202-B005 Changed 04/18/2011		7,021	Square Yard	Removal of Asphalt Pavement, All Depths				
0040	202-B064		331	Linear Feet	Removal of Pipe, 8" And Above				
0050	202-B076		300	Linear Feet	Removal of Traffic Stripe				
0060	203-A003 (E)		1,228	Cubic Yard	Unclassified Excavation, FM, AH				
0070	203-EX035 (E)		13,598	Cubic Yard	Borrow Excavation, AH, FME, Class B9-6				
0080	203-G003 (E)		7,105	Cubic Yard	Excess Excavation, FM, AH				

Section 905
 Proposal (Sheet 2 - 2)

BR-6962-00(006) / 105414301
 Rankin County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0090	206-A001	(S)	1,156	Cubic Yard	Structure Excavation		
0100	209-A001		3,460	Square Yard	Geotextile Stabilization, Type V		
0110	213-C001		2	Ton	Superphosphate		
0120	215-A001		12	Ton	Vegetative Materials for Mulch		
0130	216-A001		100	Square Yard	Solid Sodding		
0140	219-A001		2	Thousand Gallon	Watering	20. 00	40. 00
0150	220-A001		2	Acre	Insect Pest Control	30. 00	60. 00
0160	221-A001	(S)	6	Cubic Yard	Portland Cement Concrete Paved Ditch		
0170	223-A001		1	Acre	Mowing	40. 00	40. 00
0180	234-A001		6,000	Linear Feet	Temporary Silt Fence		
0190	235-A001		200	Bale	Temporary Erosion Checks		
0200	406-A001		1,600	Square Yard	Cold Milling of Bituminous Pavement, All Depths		

Section 905
 Proposal (Sheet 2 - 3)

BR-6962-00(006) / 105414301
 Rankin County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0210	408-A003	(A3)	1,449	Gallon	Asphalt for Prime Coat, Cut-Back MC-70 or Emulsified EA-1		
0220	501-E001		94	Linear Feet	Expansion Joints, Without Dowels		
0230	501-K001		198	Square Yard	Transverse Grooving		
0240	502-A001	(C)	204	Square Yard	Reinforced Cement Concrete Bridge End Pavement		
0250	606-B001		425	Linear Feet	Guard Rail, Class A, Type 1		
0260	606-D012		4	Each	Guard Rail, Bridge End Section, Type I		
0270	606-E001		4	Each	Guard Rail, Terminal End Section		
0280	615-A018	(S)	40	Linear Feet	Concrete Bridge End Barrier, 33.5"		
0290	618-A001		1	Lump Sum	Maintenance of Traffic	XXXXXXXXXX	XXXX
0300	619-A1004		1	Mile	Temporary Traffic Stripe, Continuous White, Paint		
0310	619-A2004		1	Mile	Temporary Traffic Stripe, Continuous Yellow, Paint		
0320	619-C7001		74	Each	Two-Way Yellow Reflective High Performance Raised Marker		

Section 905
 Proposal (Sheet 2 - 4)

BR-6962-00(006) / 105414301
 Rankin County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0330	619-D1001		96	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet		
0340	619-D2001		283	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More		
0350	619-G4001		48	Linear Feet	Barricades, Type III, Single Faced		
0360	619-G4005		24	Linear Feet	Barricades, Type III, Double Faced		
0370	619-G5001		27	Each	Free Standing Plastic Drums		
0380	619-G7001		6	Each	Warning Lights, Type "B"		
0390	619-K1001		100	Linear Feet	Installation and Removal of Guard Rail, Type I, Class A		
0400	619-K4001		4	Each	Installation and Removal of Guardrail, Terminal End Section		
0410	620-A001		1	Lump Sum	Mobilization	XXXXXXXXXX	XXXX
0420	627-J001		148	Each	Two-Way Clear Reflective High Performance Raised Markers		
0430	627-L001		26	Each	Two-Way Yellow Reflective High Performance Raised Markers		
0440	630-F001		34	Each	Delineators, Guard Rail, White		

Section 905
 Proposal (Sheet 2 - 5)

BR-6962-00(006) / 105414301
 Rankin County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0450	630-G002		4	Each	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted		
0460	699-A001		1	Lump Sum	Roadway Construction Stakes	XXXXXXXXXX	XXXX
0470	815-A006	(S)	200	Ton	Loose Riprap, Size 100		
0480	815-A009	(S)	440	Ton	Loose Riprap, Size 300		
0490	815-E001	(S)	200	Square Yard	Geotextile under Riprap		
0500	907-225-A001		4	Acre	Grassing		
0510	907-225-B001		8	Ton	Agricultural Limestone		
0520	907-226-A001		2	Acre	Temporary Grassing		
0530	907-234-F001		600	Linear Feet	Turbidity Barrier		
0540	907-237-A003		1,000	Linear Feet	Wattles, 20"		
0550	907-246-A002		100	Each	Sandbags		
0560	907-304-A001	(GY)	8,129	Cubic Yard	Granular Material, LVM, Class 5, Group C		

Section 905
 Proposal (Sheet 2 - 6)

BR-6962-00(006) / 105414301
 Rankin County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount	
0570	907-304-A005	(GY)	2,239	Cubic Yard	Granular Material, LVM, Class 9, Group C			
0580	907-307-C003	(M)	2,667	Square Yard	6" Soil-Lime-Water Mixing, Class C			
0590	907-307-D001		36	Ton	Lime			
0600	907-308-B002	(M)				XXXXXXXXXX	XXXXXXXXXX	
	Deleted 04/18/2011							XXXX
0610	907-407-A001	(A2)	930	Gallon	Asphalt for Tack Coat			
0620	907-603-ALT01	(S)	128	Linear Feet	18" Type A Alternate Pipe			
0630	907-603-ALT02	(S)	100	Linear Feet	24" Type A Alternate Pipe			
0640	907-603-ALT04	(S)	48	Linear Feet	36" Type A Alternate Pipe			
0650	907-617-A001		8	Each	Right-of-Way Marker			
0660	907-618-C001		1	Lump Sum	Construction and Removal of Detour Bridge	XXXXXXXXXX	XXXX	
0670	907-618-E001		1,920	Linear Feet	Detour Bridge Piling			
0680	907-618-F001		1	Lump Sum	Detour Bridge Test Pile	XXXXXXXXXX	XXXX	

Section 905
 Proposal (Sheet 2 - 7)

BR-6962-00(006) / 105414301
 Rankin County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0690	907-626-C006		1	Mile	6" Thermoplastic Double Drop Edge Stripe, Continuous White, 90 min		
0700	907-626-D006		1	Mile	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow		
ALTERNATE GROUP AA NUMBER 1							
0710	907-311-A003	(M)	6,934	Square Yard	Processing Lime and Fly Ash Treated Course, 6" Thick		
0720	907-311-B001		51	Ton	Lime		
0730	907-311-C002		203	Ton	Fly Ash, Class C or F		
ALTERNATE GROUP AA NUMBER 2							
0740	907-308-A001		73	Ton	Portland Cement		
0750	907-308-B001	(M)	6,934	Square Yard	Soil-Cement-Water Mixing, Optional Mixers, Base		
ALTERNATE GROUP BB NUMBER 1							
0760	907-403-A006	(BA1)	1,403	Ton	Hot Mix Asphalt, MT, 12.5-mm mixture		
0770	907-403-A007	(BA1)	1,599	Ton	Hot Mix Asphalt, MT, 19-mm mixture		
ALTERNATE GROUP BB NUMBER 2							
0780	907-403-M002	(BA1)	1,403	Ton	Warm Mix Asphalt, MT, 12.5-mm mixture		

Section 905
Proposal (Sheet 2 - 8)

BR-6962-00(006) / 105414301
Rankin County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0790	907-403-M007	(BA1)	1,599	Ton	Warm Mix Asphalt, MT, 19-mm mixture		
Bridge Items							
0800	501-K001		896	Square Yard	Transverse Grooving		
0810	803-B002	(S)	2	Each	Conventional Static Pile Load Test	5,000.00	10,000.00
0820	803-C003	(S)	1,605	Linear Feet	16" x 16" Prestressed Concrete Piling		
0830	803-C004	(S)	715	Linear Feet	18" x 18" Prestressed Concrete Piling		
0840	803-I001	(S)	3	Each	PDA Test Pile		
0850	803-J001	(S)	2	Each	Pile Restrike		
0860	805-A001	(S)	73,944	Pounds	Reinforcement		
0870	813-A001	(S)	403	Linear Feet	Concrete Railing		
0880	815-A009	(S)	495	Ton	Loose Riprap, Size 300		
0890	815-E001	(S)	484	Square Yard	Geotextile under Riprap		

Section 905
 Proposal (Sheet 2 - 9)

BR-6962-00(006) / 105414301
 Rankin County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0900	907-804-A001	(S)	109	Cubic Yard	Bridge Concrete, Class AA		
0910	907-804-A012	(S)	256	Cubic Yard	Bridge Concrete, Class BD		
0920	907-804-C016	(S)	1,179	Linear Feet	40' Prestressed Concrete Beam, Type I+2		

*** BID CERTIFICATION ***

TOTAL BID \$

*** SIGNATURE STATEMENT ***

BIDDER ACKNOWLEDGES THAT HE/SHE HAS CHECKED ALL ITEMS IN THIS PROPOSAL FOR ACCURACY AND CERTIFIED THAT THE FIGURES SHOWN THEREIN CONSTITUTE THEIR OFFICIAL BID.

BIDDER'S SIGNATURE

BIDDER'S COMPANY

BIDDER'S FEDERAL TAX ID NUMBER