

RANKIN (61)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Key, LLC	Southern Rock, LLC	N. L. Carson Construction Company, Inc.
Construction necessary to Replace the Bridge on SR 468, across Terrapin Skin Creek, known as State Project No. BR-6962-00(006) / 105414301, in the County of Rankin, State of Mississippi.					\$1,911,576.53	\$2,052,437.70	\$2,449,204.05	\$2,456,730.06
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS		25,000.00	180,000.00	100,000.00
0020	202-A001	Removal of Obstructions	1.000	LS		20,000.00	20,000.00	35,000.00
0030	202-B005	Removal of Asphalt Pavement, All Depths	7,021.000	SY		2.75	3.00	3.50
0040	202-B064	Removal of Pipe, 8" And Above	331.000	LF		7.00	12.00	5.00
0050	202-B076	Removal of Traffic Stripe	300.000	LF		5.00	4.00	5.25
0060	203-A003	Unclassified Excavation, FM, AH	1,228.000	CY		5.00	4.00	4.50
0070	203-EX035	Borrow Excavation, AH, FME, Class B9-6	13,598.000	CY		12.00	13.00	10.25
0080	203-G003	Excess Excavation, FM, AH	7,105.000	CY		6.00	5.50	6.00
0090	206-A001	Structure Excavation	1,156.000	CY		2.00	9.00	4.00
0100	209-A001	Geotextile Stabilization, Type V	3,460.000	SY		3.00	1.50	1.66
0110	213-C001	Superphosphate	2.000	TON		700.00	700.00	1,050.00
0120	215-A001	Vegetative Materials for Mulch	12.000	TON		220.00	220.00	420.00
0130	216-A001	Solid Sodding	100.000	SY		12.00	12.00	7.35
0140	219-A001	Watering	2.000	KGAL		20.00	20.00	20.00
0150	220-A001	Insect Pest Control	2.000	ACRE		30.00	30.00	30.00
0160	221-A001	Portland Cement Concrete Paved Ditch	6.000	CY		620.00	550.00	456.00
0170	223-A001	Mowing	1.000	ACRE		40.00	40.00	40.00
0180	234-A001	Temporary Silt Fence	6,000.000	LF		3.75	3.00	3.42
0190	235-A001	Temporary Erosion Checks	200.000	BALE		12.00	10.00	12.60
0200	406-A001	Cold Milling of Bituminous Pavement, All Depths	1,600.000	SY		5.00	4.72	4.96
0210	408-A003	Asphalt for Prime Coat, Cut-Back MC-70 or Emulsified EA-1	1,449.000	GAL		1.50	5.00	3.15
0220	501-E001	Expansion Joints, Without Dowels	94.000	LF		7.00	7.00	10.00
0230	501-K001	Transverse Grooving	198.000	SY		4.25	4.25	2.64
0240	502-A001	Reinforced Cement Concrete Bridge End Pavement	204.000	SY		122.00	122.00	110.00
0250	606-B001	Guard Rail, Class A, Type 1	425.000	LF		16.50	16.50	17.33
0260	606-D012	Guard Rail, Bridge End Section, Type I	4.000	EA		1,900.00	1,900.00	1,995.00

RANKIN (61)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Key, LLC	Southern Rock, LLC	N. L. Carson Construction Company, Inc.
Construction necessary to Replace the Bridge on SR 468, across Terrapin Skin Creek, known as State Project No. BR-6962-00(006) / 105414301, in the County of Rankin, State of Mississippi.					\$1,911,576.53	\$2,052,437.70	\$2,449,204.05	\$2,456,730.06
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0270	606-E001	Guard Rail, Terminal End Section	4.000	EA		1,950.00	1,950.00	2,042.50
0280	615-A018	Concrete Bridge End Barrier, 33.5"	40.000	LF		47.00	43.50	59.45
0290	618-A001	Maintenance of Traffic	1.000	LS		14,000.00	75,000.00	20,000.00
0300	619-A1004	Temporary Traffic Stripe, Continuous White, Paint	1.000	MI		500.00	500.00	525.00
0310	619-A2004	Temporary Traffic Stripe, Continuous Yellow, Paint	1.000	MI		500.00	500.00	525.00
0320	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	74.000	EA		10.00	10.00	10.50
0330	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	96.000	SF		6.50	8.00	6.83
0340	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	283.000	SF		6.50	8.00	6.83
0350	619-G4001	Barricades, Type III, Single Faced	48.000	LF		15.00	40.00	15.75
0360	619-G4005	Barricades, Type III, Double Faced	24.000	LF		16.00	40.00	16.80
0370	619-G5001	Free Standing Plastic Drums	27.000	EA		40.00	60.00	42.00
0380	619-G7001	Warning Lights, Type "B"	6.000	EA		350.00	100.00	367.50
0390	619-K1001	Installation and Removal of Guard Rail, Type I, Class A	100.000	LF		15.00	15.00	15.75
0400	619-K4001	Installation and Removal of Guardrail, Terminal End Section	4.000	EA		1,275.00	1,275.00	1,338.75
0410	620-A001	Mobilization	1.000	LS		175,000.00	230,000.00	237,000.00
0420	627-J001	Two-Way Clear Reflective High Performance Raised Markers	148.000	EA		10.00	8.00	10.50
0430	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	26.000	EA		10.00	40.00	10.50
0440	630-F001	Delineators, Guard Rail, White	34.000	EA		15.00	15.00	15.75
0450	630-G002	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	4.000	EA		65.00	65.00	68.25
0460	699-A001	Roadway Construction Stakes	1.000	LS		20,000.00	20,000.00	110,657.06
0470	815-A006	Loose Riprap, Size 100	200.000	TON		65.00	52.00	65.00
0480	815-A009	Loose Riprap, Size 300	440.000	TON		65.00	52.00	65.00
0490	815-E001	Geotextile under Riprap	200.000	SY		3.00	3.50	2.71
0500	907-225-A001	Grassing	4.000	ACRE		800.00	800.00	2,310.00
0510	907-225-B001	Agricultural Limestone	8.000	TON		75.00	75.00	105.00
0520	907-226-A001	Temporary Grassing	2.000	ACRE		800.00	800.00	1,050.00

RANKIN (61)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Key, LLC	Southern Rock, LLC	N. L. Carson Construction Company, Inc.
Construction necessary to Replace the Bridge on SR 468, across Terrapin Skin Creek, known as State Project No. BR-6962-00(006) / 105414301, in the County of Rankin, State of Mississippi.					\$1,911,576.53	\$2,052,437.70	\$2,449,204.05	\$2,456,730.06
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0530	907-234-F001	Turbidity Barrier	600.000	LF		7.00	15.00	12.00
0540	907-237-A003	Wattles, 20"	1,000.000	LF		5.00	5.00	7.35
0550	907-246-A002	Sandbags	100.000	EA		5.00	8.00	8.00
0560	907-304-A001	Granular Material, LVM, Class 5, Group C	8,129.000	CY		9.00	19.50	22.50
0570	907-304-A005	Granular Material, LVM, Class 9, Group C	2,239.000	CY		9.00	8.40	18.20
0580	907-307-C003	6" Soil-Lime-Water Mixing, Class C	2,667.000	SY		2.35	1.60	2.47
0590	907-307-D001	Lime	36.000	TON		185.00	170.00	194.25
0610	907-407-A001	Asphalt for Tack Coat	930.000	GAL		3.55	3.55	3.73
0620	907-603-ALT01	18" Type A Alternate Pipe	128.000	LF		35.00	50.00	23.25
0630	907-603-ALT02	24" Type A Alternate Pipe	100.000	LF		40.00	68.00	32.29
0640	907-603-ALT04	36" Type A Alternate Pipe	48.000	LF		50.00	120.00	52.95
0650	907-617-A001	Right-of-Way Marker	8.000	EA		250.00	100.00	262.50
0660	907-618-C001	Construction and Removal of Detour Bridge	1.000	LS		220,000.00	220,000.00	227,398.50
0670	907-618-E001	Detour Bridge Piling	1,920.000	LF		49.00	55.00	41.00
0680	907-618-F001	Detour Bridge Test Pile	1.000	LS		18,000.00	19,000.00	22,200.00
0690	907-626-C006	6" Thermoplastic Double Drop Edge Stripe, Continuous White,	1.000	MI		1,500.00	1,500.00	1,575.00
0700	907-626-D006	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	1.000	MI		550.00	500.00	577.50
0710	907-311-A003	Processing Lime and Fly Ash Treated Course, 6" Thick	6,934.000	SY				
0720	907-311-B001	Lime	51.000	TON				
0730	907-311-C002	Fly Ash, Class C or F	203.000	TON				
0740	907-308-A001	Portland Cement	73.000	TON		145.00	140.00	152.25
0750	907-308-B001	Soil-Cement-Water Mixing, Optional Mixers, Base	6,934.000	SY		2.35	1.60	2.47
0760	907-403-A006	Hot Mix Asphalt, MT, 12.5-mm mixture	1,403.000	TON				
0770	907-403-A007	Hot Mix Asphalt, MT, 19-mm mixture	1,599.000	TON				
0780	907-403-M002	Warm Mix Asphalt, MT, 12.5-mm mixture	1,403.000	TON		76.50	78.00	81.83
0790	907-403-M007	Warm Mix Asphalt, MT, 19-mm mixture	1,599.000	TON		72.00	73.25	76.85

RANKIN (61)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Key, LLC	Southern Rock, LLC	N. L. Carson Construction Company, Inc.
Construction necessary to Replace the Bridge on SR 468, across Terrapin Skin Creek, known as State Project No. BR-6962-00(006) / 105414301, in the County of Rankin, State of Mississippi.					\$1,911,576.53	\$2,052,437.70	\$2,449,204.05	\$2,456,730.06
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0800	501-K001	Transverse Grooving	896.000	SY		4.25	4.25	2.64
0810	803-B002	Conventional Static Pile Load Test	2.000	EA		5,000.00	5,000.00	5,000.00
0820	803-C003	16" x 16" Prestressed Concrete Piling	1,605.000	LF		49.00	55.00	47.06
0830	803-C004	18" x 18" Prestressed Concrete Piling	715.000	LF		63.00	68.00	59.45
0840	803-I001	PDA Test Pile	3.000	EA		9,000.00	9,000.00	9,246.34
0850	803-J001	Pile Restrike	2.000	EA		500.00	500.00	750.00
0860	805-A001	Reinforcement	73,944.000	LBS		0.90	0.90	0.87
0870	813-A001	Concrete Railing	403.000	LF		47.00	47.00	53.45
0880	815-A009	Loose Riprap, Size 300	495.000	TON		65.00	55.00	59.00
0890	815-E001	Geotextile under Riprap	484.000	SY		3.00	2.00	2.41
0900	907-804-A001	Bridge Concrete, Class AA	109.000	CY		570.00	570.00	575.00
0910	907-804-A012	Bridge Concrete, Class BD	256.000	CY		960.00	960.00	875.00
0920	907-804-C016	40' Prestressed Concrete Beam, Type I+2	1,179.000	LF		70.00	75.00	113.33

RANKIN (61)					Joe McGee Construction Company, Inc.			
Construction necessary to Replace the Bridge on SR 468, across Terrapin Skin Creek, known as State Project No. BR-6962-00(006) / 105414301, in the County of Rankin, State of Mississippi.					\$2,778,373.75			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0010	201-A001	Clearing and Grubbing	1.000	LS	275,000.00			
0020	202-A001	Removal of Obstructions	1.000	LS	25,000.00			
0030	202-B005	Removal of Asphalt Pavement, All Depths	7,021.000	SY	3.50			
0040	202-B064	Removal of Pipe, 8" And Above	331.000	LF	12.50			
0050	202-B076	Removal of Traffic Stripe	300.000	LF	5.00			
0060	203-A003	Unclassified Excavation, FM, AH	1,228.000	CY	7.00			
0070	203-EX035	Borrow Excavation, AH, FME, Class B9-6	13,598.000	CY	15.00			
0080	203-G003	Excess Excavation, FM, AH	7,105.000	CY	15.00			
0090	206-A001	Structure Excavation	1,156.000	CY	10.00			
0100	209-A001	Geotextile Stabilization, Type V	3,460.000	SY	4.00			
0110	213-C001	Superphosphate	2.000	TON	700.00			
0120	215-A001	Vegetative Materials for Mulch	12.000	TON	220.00			
0130	216-A001	Solid Sodding	100.000	SY	12.00			
0140	219-A001	Watering	2.000	KGAL	20.00			
0150	220-A001	Insect Pest Control	2.000	ACRE	30.00			
0160	221-A001	Portland Cement Concrete Paved Ditch	6.000	CY	750.00			
0170	223-A001	Mowing	1.000	ACRE	40.00			
0180	234-A001	Temporary Silt Fence	6,000.000	LF	4.00			
0190	235-A001	Temporary Erosion Checks	200.000	BALE	30.00			
0200	406-A001	Cold Milling of Bituminous Pavement, All Depths	1,600.000	SY	5.00			
0210	408-A003	Asphalt for Prime Coat, Cut-Back MC-70 or Emulsified EA-1	1,449.000	GAL	5.00			
0220	501-E001	Expansion Joints, Without Dowels	94.000	LF	10.00			
0230	501-K001	Transverse Grooving	198.000	SY	2.50			
0240	502-A001	Reinforced Cement Concrete Bridge End Pavement	204.000	SY	110.00			
0250	606-B001	Guard Rail, Class A, Type 1	425.000	LF	16.50			
0260	606-D012	Guard Rail, Bridge End Section, Type I	4.000	EA	1,900.00			

RANKIN (61)					Joe McGee Construction Company, Inc.			
Construction necessary to Replace the Bridge on SR 468, across Terrapin Skin Creek, known as State Project No. BR-6962-00(006) / 105414301, in the County of Rankin, State of Mississippi.					\$2,778,373.75			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0270	606-E001	Guard Rail, Terminal End Section	4.000	EA	1,950.00			
0280	615-A018	Concrete Bridge End Barrier, 33.5"	40.000	LF	43.50			
0290	618-A001	Maintenance of Traffic	1.000	LS	40,500.00			
0300	619-A1004	Temporary Traffic Stripe, Continuous White, Paint	1.000	MI	500.00			
0310	619-A2004	Temporary Traffic Stripe, Continuous Yellow, Paint	1.000	MI	500.00			
0320	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	74.000	EA	10.00			
0330	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	96.000	SF	8.50			
0340	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	283.000	SF	8.50			
0350	619-G4001	Barricades, Type III, Single Faced	48.000	LF	20.00			
0360	619-G4005	Barricades, Type III, Double Faced	24.000	LF	29.00			
0370	619-G5001	Free Standing Plastic Drums	27.000	EA	86.00			
0380	619-G7001	Warning Lights, Type "B"	6.000	EA	775.00			
0390	619-K1001	Installation and Removal of Guard Rail, Type I, Class A	100.000	LF	15.00			
0400	619-K4001	Installation and Removal of Guardrail, Terminal End Section	4.000	EA	1,275.00			
0410	620-A001	Mobilization	1.000	LS	207,100.00			
0420	627-J001	Two-Way Clear Reflective High Performance Raised Markers	148.000	EA	10.00			
0430	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	26.000	EA	10.00			
0440	630-F001	Delineators, Guard Rail, White	34.000	EA	15.00			
0450	630-G002	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	4.000	EA	65.00			
0460	699-A001	Roadway Construction Stakes	1.000	LS	15,000.00			
0470	815-A006	Loose Riprap, Size 100	200.000	TON	70.00			
0480	815-A009	Loose Riprap, Size 300	440.000	TON	70.00			
0490	815-E001	Geotextile under Riprap	200.000	SY	5.00			
0500	907-225-A001	Grassing	4.000	ACRE	800.00			
0510	907-225-B001	Agricultural Limestone	8.000	TON	75.00			
0520	907-226-A001	Temporary Grassing	2.000	ACRE	800.00			

RANKIN (61)					Joe McGee Construction Company, Inc.			
Construction necessary to Replace the Bridge on SR 468, across Terrapin Skin Creek, known as State Project No. BR-6962-00(006) / 105414301, in the County of Rankin, State of Mississippi.					\$2,778,373.75			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0530	907-234-F001	Turbidity Barrier	600.000	LF	10.00			
0540	907-237-A003	Wattles, 20"	1,000.000	LF	7.00			
0550	907-246-A002	Sandbags	100.000	EA	25.00			
0560	907-304-A001	Granular Material, LVM, Class 5, Group C	8,129.000	CY	25.25			
0570	907-304-A005	Granular Material, LVM, Class 9, Group C	2,239.000	CY	20.50			
0580	907-307-C003	6" Soil-Lime-Water Mixing, Class C	2,667.000	SY	2.35			
0590	907-307-D001	Lime	36.000	TON	185.00			
0610	907-407-A001	Asphalt for Tack Coat	930.000	GAL	3.75			
0620	907-603-ALT01	18" Type A Alternate Pipe	128.000	LF	20.00			
0630	907-603-ALT02	24" Type A Alternate Pipe	100.000	LF	30.00			
0640	907-603-ALT04	36" Type A Alternate Pipe	48.000	LF	45.00			
0650	907-617-A001	Right-of-Way Marker	8.000	EA	350.00			
0660	907-618-C001	Construction and Removal of Detour Bridge	1.000	LS	250,000.00			
0670	907-618-E001	Detour Bridge Piling	1,920.000	LF	60.00			
0680	907-618-F001	Detour Bridge Test Pile	1.000	LS	10,000.00			
0690	907-626-C006	6" Thermoplastic Double Drop Edge Stripe, Continuous White,	1.000	MI	1,500.00			
0700	907-626-D006	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	1.000	MI	550.00			
0710	907-311-A003	Processing Lime and Fly Ash Treated Course, 6" Thick	6,934.000	SY				
0720	907-311-B001	Lime	51.000	TON				
0730	907-311-C002	Fly Ash, Class C or F	203.000	TON				
0740	907-308-A001	Portland Cement	73.000	TON	145.00			
0750	907-308-B001	Soil-Cement-Water Mixing, Optional Mixers, Base	6,934.000	SY	2.35			
0760	907-403-A006	Hot Mix Asphalt, MT, 12.5-mm mixture	1,403.000	TON				
0770	907-403-A007	Hot Mix Asphalt, MT, 19-mm mixture	1,599.000	TON				
0780	907-403-M002	Warm Mix Asphalt, MT, 12.5-mm mixture	1,403.000	TON	80.35			
0790	907-403-M007	Warm Mix Asphalt, MT, 19-mm mixture	1,599.000	TON	75.60			

RANKIN (61)					Joe McGee Construction Company, Inc.			
Construction necessary to Replace the Bridge on SR 468, across Terrapin Skin Creek, known as State Project No. BR-6962-00(006) / 105414301, in the County of Rankin, State of Mississippi.					\$2,778,373.75			
Ref#	SM Item	Item Description	Item Qty	Units	4			
0800	501-K001	Transverse Grooving	896.000	SY	2.50			
0810	803-B002	Conventional Static Pile Load Test	2.000	EA	5,000.00			
0820	803-C003	16" x 16" Prestressed Concrete Piling	1,605.000	LF	49.75			
0830	803-C004	18" x 18" Prestressed Concrete Piling	715.000	LF	55.75			
0840	803-I001	PDA Test Pile	3.000	EA	12,500.00			
0850	803-J001	Pile Restrike	2.000	EA	500.00			
0860	805-A001	Reinforcement	73,944.000	LBS	1.05			
0870	813-A001	Concrete Railing	403.000	LF	43.50			
0880	815-A009	Loose Riprap, Size 300	495.000	TON	70.00			
0890	815-E001	Geotextile under Riprap	484.000	SY	5.00			
0900	907-804-A001	Bridge Concrete, Class AA	109.000	CY	800.00			
0910	907-804-A012	Bridge Concrete, Class BD	256.000	CY	975.00			
0920	907-804-C016	40' Prestressed Concrete Beam, Type I+2	1,179.000	LF	79.00			