

COAHOMA (14)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Lehman-Roberts Company		
Widen and Overlay approximately 9 miles of SR 1 from the Bolivar County Line to Sherard, known as Federal Aid Project No. STP-0052-01(007) / 106313301, in Coahoma County.					\$2,563,209.90	\$2,834,750.22		
Ref#	SM Item	Item Description	Item Qty	Units		1		
0002	234-A001	Temporary Silt Fence	250.000	LF		5.37		
0010	406-A001	Cold Milling of Bituminous Pavement, All Depths	1,100.000	SY		10.64		
0020	423-A001	Rumble Strips, Ground In	18.000	MI		564.79		
0022	609-D008	Combination Concrete Curb and Gutter Type 3A	510.000	LF		26.16		
0024	614-B002	Concrete Driveway, With Reinforcement, 6-inch Thickness	150.000	SY		43.61		
0026	616-A002	Concrete Median and/or Island Pavement, 6-inch	110.000	SY		43.61		
0030	618-A001	Maintenance of Traffic	1.000	LS		79,770.80		
0040	618-B001	Additional Construction Signs	1.000	SF		10.00		
0050	619-A1002	Temporary Traffic Stripe, Continuous White	37.000	MI		900.00		
0060	619-A2002	Temporary Traffic Stripe, Continuous Yellow	3.000	MI		900.00		
0070	619-A4006	Temporary Traffic Stripe, Skip Yellow	18.000	MI		900.00		
0080	619-A5001	Temporary Traffic Stripe, Detail	2,090.000	LF		0.25		
0090	619-A6001	Temporary Traffic Stripe, Legend	1,300.000	LF		1.00		
0100	620-A001	Mobilization	1.000	LS		93,670.00		
0110	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	705.000	EA		6.00		
0112	907-237-A003	Wattles, 20"	50.000	LF		13.42		
0120	907-304-B009	Granular Material, Class 3, Group D	6,300.000	TON		28.18		
0130	907-407-A001	Asphalt for Tack Coat	30,000.000	GAL		0.01		
0140	907-626-C004	6" Thermoplastic Edge Stripe, Continuous White	19.000	MI		2,600.00		
0150	907-626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	9.000	MI		1,100.00		
0160	907-626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	2.000	MI		2,600.00		
0170	907-626-G004	Thermoplastic Detail Stripe, White	1,450.000	LF		1.00		
0180	907-626-G005	Thermoplastic Detail Stripe, Yellow	640.000	LF		1.00		
0190	907-626-H004	Thermoplastic Legend, White	1,300.000	LF		3.00		
0200	907-403-A010	Hot Mix Asphalt, MT, 9.5-mm mixture	14,000.000	TON		86.50		
0210	907-403-B006	Hot Mix Asphalt, MT, 9.5-mm mixture, Leveling	9,300.000	TON		86.50		

COAHOMA (14)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Lehman-Roberts Company		
Widen and Overlay approximately 9 miles of SR 1 from the Bolivar County Line to Sherard, known as Federal Aid Project No. STP-0052-01(007) / 106313301, in Coahoma County.					\$2,563,209.90	\$2,834,750.22		
Ref#	SM Item	Item Description	Item Qty	Units		1		
0220	907-403-C005	Hot Mix Asphalt, ST, 19-mm mixture, Trench Widening	3,700.000	TON		78.57		
0230	907-403-M006	Warm Mix Asphalt, MT, 9.5-mm mixture	14,000.000	TON				
0240	907-403-N005	Warm Mix Asphalt, MT, 9.5-mm mixture, Leveling	9,300.000	TON				
0250	907-403-O001	Warm Mix Asphalt, ST, 19-mm mixture, Trench Widening	3,700.000	TON				