

ITAWAMBA (29)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	APAC - Mississippi, Inc.		
Overlay approximately 11 Miles of SR 178 From Old SR 25 to Near Alabama State Line, known as State Project No. MP-1178-29(004) / 304132301, in Itawamba County.					\$1,310,005.00	\$1,392,348.75		
Ref#	SM Item	Item Description	Item Qty	Units		1		
0010	202-B097	Removal of Concrete Overlaid w/ Asphalt Pavement, All Depth	145.000	SY		22.25		
0020	203-G003	Excess Excavation, FM, AH	50.000	CY		35.25		
0030	406-A001	Cold Milling of Bituminous Pavement, All Depths	105,000.000	SY		1.10		
0040	618-A001	Maintenance of Traffic	1.000	LS		90,000.00		
0050	618-B001	Additional Construction Signs	1.000	SF		10.00		
0060	619-A1002	Temporary Traffic Stripe, Continuous White	40.000	MI		700.00		
0070	619-A2002	Temporary Traffic Stripe, Continuous Yellow	20.000	MI		800.00		
0080	619-A4006	Temporary Traffic Stripe, Skip Yellow	15.000	MI		800.00		
0090	619-A5001	Temporary Traffic Stripe, Detail	4,600.000	LF		0.20		
0100	619-A6001	Temporary Traffic Stripe, Legend	4,000.000	LF		0.50		
0110	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	575.000	EA		5.00		
0120	907-304-A007	Granular Material, LVM, Class 3, Group D	900.000	CY		21.00		
0130	907-407-A001	Asphalt for Tack Coat	21,000.000	GAL		1.58		
0140	907-626-C004	6" Thermoplastic Edge Stripe, Continuous White	14.000	MI		2,100.00		
0150	907-626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	5.000	MI		900.00		
0160	907-626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	7.000	MI		2,400.00		
0170	907-626-G004	Thermoplastic Detail Stripe, White	1,800.000	LF		1.50		
0180	907-626-G005	Thermoplastic Detail Stripe, Yellow	850.000	LF		1.50		
0190	907-626-H004	Thermoplastic Legend, White	3,800.000	LF		2.00		
0200	907-403-A015	Hot Mix Asphalt, ST, 9.5-mm mixture	11,300.000	TON				
0210	907-403-M001	Warm Mix Asphalt, ST, 9.5-mm mixture	11,300.000	TON		89.00		