

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) further propose to execute the attached contract agreement (Section 902) as soon as the work is awarded to me (us), and to begin and complete the work within the time limit(s) provided for in the Specifications and Advertisement. I (We) also propose to execute the attached contract bond (Section 903) in an amount not less than one hundred (100) percent of the total of my (our) part, but also to guarantee the excellence of both workmanship and materials until the work is finally accepted.

I (We) enclose a certified check, cashier's check or bid bond for **five percent (5%) of total bid** and hereby agree that in case of my (our) failure to execute the contract and furnish bond within Ten (10) days after notice of award, the amount of this check (bid bond) will be forfeited to the State of Mississippi as liquidated damages arising out of my (our) failure to execute the contract as proposed. It is understood that in case I am (we are) not awarded the work, the check will be returned as provided in the Specifications.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. 1 DATED 7/10/2012 ADDENDUM NO. DATED
 ADDENDUM NO. 2 DATED 07/18/2012 ADDENDUM NO. DATED

Number	Description
1	Revised Table of Contents, replace same; Add Supplement to SP 907-102-8; Bidsheets, replace same; Amendment EBS Download Required.
2	Revised Bidsheets, replace same; Amendment EBS Download Required.

TOTAL ADDENDA: 2
 (Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

 Contractor

BY _____
 Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

_____ President	_____ Address
_____ Secretary	_____ Address
_____ Treasurer	_____ Address

The following is my (our) itemized proposal.

Revised 09/21/2005

MP-5501-62(006) / 304356301

Scott County(ies)

Overlay approximately 3 miles of SR 501 from I-20 to the RR Crossing in Forest, known as State Project No. MP-5501-62(006) / 304356301 in Scott County.

I (We) agree to complete the entire project within the specified contract time.

*** SPECIAL NOTICE TO BIDDERS ***

**BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED.
 BIDS WILL NOT BE CONSIDERED UNLESS THE BID CERTIFICATION LOCATED AT THE END OF THE BIDDING SHEETS IS SIGNED**

BID SCHEDULED

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price		Item Amount	
						Dollar	Ct	Dollar	Ct
Roadway Items									
0010	202-A001		1	Lump Sum	Removal of Obstructions	XXXXXXXXXX	XXX		
0020	202-B005		3,765	Square Yard	Removal of Asphalt Pavement, All Types				
0030	202-B035		8	Square Yard	Removal of Concrete Sidewalk				
0040	202-B038		175	Linear Feet	Removal of Curbs, all Types				
0050	202-B064		45	Linear Feet	Removal of Trench, 8" And Above				
0060	202-B084		3,765	Square Yard	Removal of Base				
0070	202-B142		1	Each	Removal of Junction Box				
0080	203-EX030	(E)	200	Cubic Yard	Borrow Excavation, AH, LVM, Class B15				

Section 905
 Proposal (Sheet 2 - 2)

MP-5501-62(006) / 304356301
 Scott County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0090	203-G004	(E)	25	Cubic Yard	Excess Excavation, LVM, AH		
0100	206-A001	(S)	150	Cubic Yard	Structure Excavation		
0110	206-B001	(E)	41	Cubic Yard	Select Material for Underdrains, Contractor Furnished, 1/4"		
0120	234-A001		50	Linear Feet	Temporary Silt Fence		
0130	305-B001	(GY)	90	Cubic Yard	Size 1 Stall Water Aggregate Coarse		
0140	406-A001		5,200	Square Yard	Cold Filling of Bituminous Pavement, All Depths		
0150	602-A001	(S)	514	Pounds	Reinforcing Steel		
0160	603-PA009	(S)		Linear Feet	12" x 6" Precast Concrete Box Culvert		
0170	603-SB028	(S)	1	Each	30" Branch Connections, Stub into Box Culvert		
0180	606-B004		50	Linear Feet	Guard Rail, Class A, Type 1, Metal Post		
0190	606-D014		3	Each	Guard Rail, Bridge End Section, Type 1, Metal Post		
0200	606-E003		3	Each	Guard Rail, Terminal End Section, Non-Flared		

Section 905
 Proposal (Sheet 2 - 3)

MP-5501-62(006) / 304356301
 Scott County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0210	608-A001	(S)	26	Square Yard	Concrete Sidewalk, Without Reinforcement		
0220	609-D001	(S)	68	Linear Feet	Combination Concrete Curb and Gutter Type 1		
0230	609-E001		38	Linear Feet	Bituminous Curb		
0240	613-A001		1	Lump Sum	Adjustment of Curbings, Gratings, & Utility Appearances	XXXXXXXXXX	XXXX
0250	615-A012	(S)	135	Linear Feet	Concrete Type IV Median 12" Height, Cast-in-Place Median Barrier		
0260	618-A001		1	Lump Sum	Maintenance of Traffic	XXXXXXXXXX	XXXX
0270	619-A1002		5	Mile	Temporary Traffic Stripe, Continuous White		
0280	619-A2002			Mile	Temporary Traffic Stripe, Continuous Yellow		
0290	619-A4007		1	Mile	Temporary Traffic Stripe, Skip Yellow, Paint		
0300	619-A5001		1,926	Linear Feet	Temporary Traffic Stripe, Detail		
0310	619-A6001		1,100	Linear Feet	Temporary Traffic Stripe, Legend		
0320	619-A6002		63	Square Feet	Temporary Traffic Stripe, Legend		

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0330	619-D1001		214	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet		
0340	619-D2001		260	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More		
0350	619-F3004		12	Each	Delineators, Guard Rail, Wh		
0360	619-G4001		48	Linear Feet	Barricades, Type I, Single Faced		
0370	619-G4005		24	Linear Feet	Barricades, Type III, Double Faced		
0380	619-G7001		4	Each	Warning Lights, Type "B"		
0390	620-A001		1	Lump Sum	Mobile Sign	XXXXXXXXXX	XXXX
0400	627-I001		200	Each	Two-Way Arrow Reflective High Performance Raised Markers		
0410	627-L001		371	Each	Two-Way Yellow Reflective High Performance Raised Markers		
0420	815-B001		75	Square Yards	Grouted Riprap		
0430	907-225-A001		1	Area	Grassing		
0435	907-265-PP002		1	Lump Sum	Relocation of Existing Water Line	XXXXXXXXXX	XXXX

These bids are for informational purposes only. Do not bid on these sheets until notified by the project engineer.

Section 905
 Proposal (Sheet 2 - 5)

MP-5501-62(006) / 304356301
 Scott County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0440	907-304-A001	(GY)	1,150	Cubic Yard	Granular Material, LVM, Class 5, Group C		
0450	907-304-H001	(GY)	50	Cubic Yard	Size 825 Crushed Stone Base, LVM		
0460	907-407-A001	(A2)	4,500	Gallon	Asphalt for Tack Coat		
0470	907-601-A001	(S)	10	Cubic Yard	Class "B" Structural Concrete		
0480	907-601-B003	(S)	2	Cubic Yard	Class "B" Structural Concrete, Minor Structures		
0490	907-603-PE207	(S)	40	Linear Feet	50' Corrugated Polyethylene Pipe		
0500	907-626-C006		5	Mile	6" Thermoplastic Double Drop Edge Stripe, Continuous White, 90 mi		
0510	907-626-D006			Mile	6" Thermoplastic Double Drop Edge Traffic Stripe, Skip Yellow		
0520	907-626-E006		5	Mile	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow		
0530	907-626-G006		1,286	Linear Feet	Thermoplastic Double Drop Detail Stripe, White		
0540	907-626-G007		60	Linear Feet	Thermoplastic Double Drop Detail Stripe, Yellow		
0550	907-626-H009		1,160	Linear Feet	Thermoplastic Double Drop Legend, White		

Section 905
 Proposal (Sheet 2 - 6)

MP-5501-62(006) / 304356301
 Scott County

Line No.	Item Code	Adj Code	Quantity	Units	Description	Unit Price	Bid Amount
0560	907-626-H010		63	Square Feet	Thermoplastic Double Drop Legend, White		
0570	907-631-B001		5	Cubic Yard	Flowable Fill, Non-Excavatable		
ALTERNATE GROUP CC NUMBER 1							
0580	907-403-A011 (BA1)		4,200	Ton	Hot Mix Asphalt, ST, 12.5-mm mixture		
ALTERNATE GROUP CC NUMBER 2							
0590	907-403-M003 (BA1)		4,200	Ton	Warm Mix Asphalt, ST, 12.5-mm mixture		
ALTERNATE GROUP CC NUMBER 1							
0600	907-403-B007 (BA1)		3,350	Ton	Hot Mix Asphalt, ST, 12.5-mm mixture, leveling		
ALTERNATE GROUP CC NUMBER 2							
0610	907-403-N002 (BA1) Changed 07/10/2012		3,350	Ton	Warm Mix Asphalt, ST, 12.5-mm mixture, Leveling		
ALTERNATE GROUP CC NUMBER 1							
0620	907-403-A012 (BA1)		25	Ton	Hot Mix Asphalt, ST, 19-mm mixture		
ALTERNATE GROUP CC NUMBER 2							
0630	907-403-M004 (BA1)		25	Ton	Warm Mix Asphalt, ST, 19-mm mixture		

NOT FOR CONSTRUCTION

*** BID CERTIFICATION ***

TOTAL BID.....\$

*** SIGNATURE STATEMENT ***

BIDDER ACKNOWLEDGES THAT HE/SHE HAS CHECKED ALL ITEMS IN THIS PROPOSAL FOR ACCURACY AND CERTIFIED THAT THE FIGURES SHOWN THEREIN CONSTITUTE THEIR OFFICIAL BID.

BIDDER'S SIGNATURE

BIDDER'S COMPANY

BIDDER'S FEDERAL TAX ID NUMBER

These Bid Sheets Are Not For
Generate Expedite Bid Sheets Using