

Call 09 Cable Barrier Installation on I-55, known as Federal Aid Project No. HSIP-0055-02(231) / 106417301 & 302 in Yazoo and Holmes Counties.

Q1. Please provide soil boring information for end terminal design.

A1. Soil boring information is not available for this project through the Department as per special provision 907-606-4 in subsection 907-606.03.3 when such boring information is not available and is stated as follows: "The contract documents may include information regarding the existing soil, but is the Contractor's responsibility to supply the designer of the cable barrier with all the soil information needed to design the cable system."

Q2. Are there any time restrictions for lane closures?

A2. No, time restrictions are not a part of this project. However, the contractor should be familiar with the 2004 Mississippi Standard Specifications for Road and Bridge Construction as certain days will not be allowable work days.

Q3. The vegetation Control Pad (under the High Tension Cable Barrier) is typically 4'W x 4'D. Should it be 4'W?

A3. For this project, the vegetation control pad will be 3' (feet) wide.