

Call 15 Replace Bridge Nos. 40.2, 41.2, and 41.4 on SR 178 Over Chewallah Creek and Tippah River, known as Federal Aid Project No. BR-2910-00(002) / 103162301 in Marshall County.

Q1. How are the message boards and barricades shown on Sheets DCS-1 and DCS-2 of the plans to be paid?

A1. See the fax letter for this project.

Q2. Does MDOT plan to keep the Changeable Message Signs (4 each) and Barricades, Type III, Double Face (96 LF) mentioned in Fax 1?

A2. The changeable message boards and barricades will become the property of the contractor at completion of the project.

Q3. Section 904 – Notice to Bidders No. 2367 lists a spread footing item of work requiring restrictions. Does this item include any concrete used in a box structure, curb and gutter, ditch paving, or bridge approach slabs? What pay items would be included in the spread footing listing?

A3. Yes, box culvert concrete is included, but not curb and gutter, ditch paving and bridge approach slabs.

Q4. 1. Do I need to include styrofoam fillers in my S.I.P. bridge decking if my deadload is less than 20 p.s.f? 2. Do I need to match my S.I.P. Bridge Decking flutes to the re-bar spacing if the dead load is less than 20 p.s.f?

A4. 1. Styrofoam fillers are not required if the dead load is less than 20 psf but it is an option.
2. Matching flutes are not required if the dead load is less than 20 psf but it is an option.

Q5. Will maintenance of traffic be added to the proposal?

A5. Yes, see addendum No. 2 for this project.