

**SECTION 905 -- PROPOSAL (CONTINUED)**

I (We) further propose to execute the attached contract agreement (Section 902) as soon as the work is awarded to me (us), and to begin and complete the work within the time limit(s) provided for in the Specifications and Advertisement. I (We) also propose to execute the attached contract bond (Section 903) in an amount not less than one hundred (100) percent of the total of my (our) part, but also to guarantee the excellence of both workmanship and materials until the work is finally accepted.

I (We) enclose a certified check, cashier's check or bid bond for **five percent (5%) of total bid** and hereby agree that in case of my (our) failure to execute the contract and furnish bond within Ten (10) days after notice of award, the amount of this check (bid bond) will be forfeited to the State of Mississippi as liquidated damages arising out of my (our) failure to execute the contract as proposed. It is understood that in case I am (we are) not awarded the work, the check will be returned as provided in the Specifications.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO.   1   DATED   1/15/2013   ADDENDUM NO.   3   DATED   02/15/2013    
 ADDENDUM NO.   2   DATED   02/12/2013   ADDENDUM NO.            DATED           

- | Number | Description   |
|--------|---|
| 1      | Table of Contents, replace same; Add NTB Nos. 4284 & 4285; Wage Rates, replace same; Revised Supplement to SP 907-403-4, replaces same; Add Supplement to SP 907-703-10; BidItems, replace same; Revised Plan Sheet Nos. 2 & 14, replace same; Amendment EBS Download Required.   |
| 2      | Revised Table of Contents, replace same; Revised Advertisement, replaces same; Revised NTB Nos. 4163 & 4167, replace same; Delete SP 907-804-12; Revised BidItems, replace same; Revised or Added Plan Sht. Nos. 1, 2, 15, 16, 24, 35, 37, 41, 8001-8005, 8007-8014, 8031-8034, 8036-8047, 8064-8066, 8068-8075, 8092-8094, 8120, 8121, 8123-8130, 8143; Amendment EBS Download Required. |
| 3      | Table of Contents, replace same; Add NTB Nos. 4341, 4342, & 4343; BidItems, replace same; Revised or Added Plan Sht. Nos. 1, 2, 14, 21, 32, 34, & 37; Amendment EBS Download Required.  |

TOTAL ADDENDA:   3    
 (Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE \_\_\_\_\_

\_\_\_\_\_ Contractor

BY \_\_\_\_\_ Signature

TITLE \_\_\_\_\_

ADDRESS \_\_\_\_\_

CITY, STATE, ZIP \_\_\_\_\_

PHONE \_\_\_\_\_

FAX \_\_\_\_\_

E-MAIL \_\_\_\_\_

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of \_\_\_\_\_ and the names, titles and business addresses of the executives are as follows:

_____	_____
President	Address
_____	_____
Secretary	Address
_____	_____
Treasurer	Address

The following is my (our) itemized proposal.

# MISSISSIPPI DEPARTMENT OF TRANSPORTATION

## TABLE OF CONTENTS

### PROJECT: STP-0029-02(013) / 102556310 – Desoto County

901--Advertisement

904--Notice to Bidders:	Governing Specs. - # 1
	Final Cleanup - # 3
	Quantity for Fillet Concrete - # 6
	Fiber Reinforced Concrete - # 640
	Payroll Requirements - # 883
	Errata & Modifications to 2004 Standard Specifications - # 1405
	Federal Bridge Formula - # 1928
	Exposure to Moderate Sulfate Areas Below Ground Level - # 2367
	Status of ROW, <u>W/Attachments</u> - # 2382
	Clearing and/or Grubbing - # 2418
	DBE Forms, Participation, and Payment - # 2596
	Non-Quality Control/Quality Assurance Concrete - # 2818
	Reduced Speed Limit Signs - # 2937
	Alternate Asphalt Mixture Bid Items - # 3039
	Temporary Traffic Paint - # 3131
	Warm Mix Asphalt (WMA) - # 3242
	DUNS Requirement for Federal Funded Projects - # 3414
	Storm Water Discharge Associated with Construction Activities ( $\geq 5$ Acres) - # 3581
	Additional Erosion Control Requirements - # 3612
	Type III Barricade Rails - # 3655
	Use of Precast Drainage Units - # 3704
	Petroleum Products Base Price - # 3893
	Questions Regarding Bidding - # 3980
	Stay-In-Place Metal Forms – # 4084
	Temporary Steel Bracing - # 4085
	Disadvantaged Business Enterprise, <u>W/Supplement</u> - # 4103
	Contract Time - # 4163
	Specialty Items - # 4164
	Placement of Fill Material in Federally Regulated Areas - # 4165
	Cooperation Between Contractors - # 4166
	Memphis Stone & Gravel Conveyor - # 4167
	Geotechnical Investigation - # 4168
	Site Access from I-55 - # 4169
	Finish Grades - # 4170
	Seismic Piling - # 4171
	Silt Fence Reinforcement - # 4172
	Contract Time Determination - # 4173
	Steel Pile Grade - # 4185
	Safety Apparel - # 4214
	Class “B” Structural Concrete and Reinforcing - # 4284
	Disturbed Areas - # 4285
	Change in Borrow Classification - # 4341
	Excess Excavation - # 4342
	Additional Site Access - # 4343

-- CONTINUED ON NEXT PAGE --

- 906: Required Federal Contract Provisions -- FHWA-1273, W/ Supplement
  
- 907-101-4: Definitions
- 907-102-8: Bidding Requirements and Conditions, W/ Supplement
- 907-103-8: Award and Execution of Contract
- 907-104-1: Partnering Process
- 907-104-4: Disposal of Materials
- 907-105-6: Control of Work, W/ Supplement
- 907-107-9: Legal Relations & Responsibility to Public, W/ Supplement
- 907-107-10: Contractor's Erosion Control Plan, W/ Supplement
- 907-108-24: Prosecution and Progress, W/ Supplement
- 907-109-5: Measurement and Payment, W/ Supplement
- 907-110-2: Wage Rates
- 907-225-3: Grassing
- 907-226-2: Temporary Grassing
- 907-227-10: Hydroseeding
- 907-234-5: Siltation Barriers
- 907-237-4: Wattles
- 907-245-2: Triangular Silt Dikes
- 907-246-3: Sandbags & Rockbags
- 907-247-1: Temporary Stream Diversion
- 907-249-1: Riprap for Erosion Control
- 907-304-13: Granular Courses
- 907-308-3: Cement Treated Courses, W/ Supplement
- 907-310-1: Stabilizer Aggregate
- 907-311-2: Lime-Fly Ash Treated Courses, W/ Supplement
- 907-401-2: Hot Mix Asphalt (HMA), W/ Supplement
- 907-401-6: Warm Mix Asphalt (WMA)
- 907-403-4: Hot Mix Asphalt (HMA), W/ Supplement
- 907-403-12: Warm Mix Asphalt (WMA)
- 907-407-1: Tack Coat
- 907-413-2: Sawing & Sealing Transverse Joints in Asphalt Pavement
- 907-601-1: Structural Concrete
- 907-603-8: Culverts and Storm Drains
- 907-605-3: Underdrains
- 907-617-2: Right-Of-Way Markers
- 907-618-9: Placement of Temporary Traffic Stripe
- 907-626-5: Inverted Profile Thermoplastic Traffic Stripe
- 907-626-25: Thermoplastic Traffic Marking
- 907-699-4: Construction Stakes
- 907-701-4: Hydraulic Cement
- 907-702-3: Polyphosphoric Acid (PPA) Modification of Petroleum Asphalt Cement
- 907-703-10: Aggregates, W/ Supplement
- 907-708-5: Non Metal Drainage Structures, W/ Supplement
- 907-709-1: Metal Pipe
- 907-710-1: Fast Drying Solvent Traffic Paint
- 907-711-4: Synthetic Structural Fiber Reinforcement
- 907-713-2: Admixtures for Concrete, W/ Supplement
- 907-714-6: Miscellaneous Materials
- 907-715-3: Roadside Development Materials, W/ Supplement

**PAGE 3 - PROJECT: STP-0029-02(013) / 102556310 – Desoto County**

907-720-1: Pavement Marking Materials, W/ Supplement  
907-803-2: Maturity Meters in Drilled Shafts, W/ Supplement  
907-804-13: Concrete Bridges and Structures, W/ Supplement

906-7: Training Special Provision

SECTION 905 - PROPOSAL,  
PROPOSAL BID ITEMS,  
COMBINATION BID PROPOSAL,  
CERTIFICATION OF PERFORMANCE - PRIOR FEDERAL-AID CONTRACTS,  
CERTIFICATION REGARDING NON-COLLUSION, DEBARMENT AND SUSPENSION,  
SECTION 902 - CONTRACT FORM, AND SECTION 903 - CONTRACT BOND FORMS,  
PILE DRIVING FORM,  
OCR-485.

(REVISIONS TO THE ABOVE WILL BE INDICATED ON THE SECOND SHEET  
OF SECTION 905 AS ADDENDA)

**MISSISSIPPI DEPARTMENT OF TRANSPORTATION**

**SECTION 904- NOTICE TO BIDDERS NO. 4341**

**CODE: (SP)**

**DATE: 2/15/2013**

**SUBJECT: Change in Borrow Classification**

**PROJECT: STP-0029-02(013) / 102556310 – Desoto County**

Bidders are hereby advised that Pay Item 203-EX017 Borrow Excavation, AH, FME, Class B9 replaces previously listed Pay Item 203-EX035 Borrow Excavation, AH, FME, Class B9-6. The Pay Item and quantity shown in the Proposal Bid Sheets is correct.

**MISSISSIPPI DEPARTMENT OF TRANSPORTATION**

**SECTION 904- NOTICE TO BIDDERS NO. 4342**

**CODE: (SP)**

**DATE: 2/15/2013**

**SUBJECT: Excess Excavation**

**PROJECT: STP-0029-02(013) / 102556310 – Desoto County**

Bidders are hereby advised that Excess Excavation found on the project that meets the requirements of Unclassified Excavation can be used as and paid for as Unclassified Excavation but will not be paid for as both Excess Excavation and Unclassified Excavation.

**MISSISSIPPI DEPARTMENT OF TRANSPORTATION**

**SECTION 904 - NOTICE TO BIDDERS NO. 4343**

**CODE: (SP)**

**DATE: 02/15/2013**

**SUBJECT: Additional Site Access**

**PROJECT: STP-0029-02(013) / 102556310 – Desoto County**

Bidders are hereby advised that the contractor will be allowed to construct a haul road adjacent to the right-of-way line from the EOP to Laughter Road under the following conditions:

1. The contractor shall be responsible for all cost associated with the haul road, which includes all erosion control measures. Grassing will also be required upon completion.
2. The contractor shall be responsible for obtaining permission from local officials for construction traffic to access the haul road from Laughter Road and any adjacent connections to Laughter Road. MDOT will not be held liable for any damage to Laughter Road and any of its connectors.
3. The haul road should stay within 25 feet of the right-of-way line.
4. The access period for the haul road will terminate on May 13, 2014.

If any further access is allowed, it will have to be agreed upon and coordinated with the Contractor of the upcoming project.

Grade, Drain, & Bridge on SR 304/I-269 from I-55 to STA. 240+00, known as Federal Aid Project No. STP-0029-02(013) / 102556310 in DeSoto County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
					Roadway Items
0010	201-A001		1	Lump Sum	Clearing and Grubbing
0020	202-B002		1,883	Square Yard	Removal of Asphalt Driveways, All Depths
0030	202-B018		870	Square Yard	Removal of Concrete Driveways, All Depths
0040	202-B064		724	Linear Feet	Removal of Pipe, 8" And Above
0050	202-B078		27,369	Square Yard	Removal of Pavement, All Types and Depths
0060	202-B079		2	Each	Removal of Headwall
0070	202-B276		312	Cubic Yard	Remove and Reset Riprap
0080	202-B292		6	Each	Removal of Septic Tank, All Sizes
0090	203-A003	(E)	1,518,791	Cubic Yard	Unclassified Excavation, FM, AH
0095	203-D001	(E)	10,000	Cubic Yard	Muck Excavation, FM
	Added 02/15/2013				
0100	203-EX017	(E)	843,714	Cubic Yard	Borrow Excavation, AH, FME, Class B9
	Changed 02/15/2013				
0110	203-G003	(E)	44,329	Cubic Yard	Excess Excavation, FM, AH
	Changed 02/15/2013				
0120	206-A001	(S)	25,222	Cubic Yard	Structure Excavation
0130	206-B001	(E)	317	Cubic Yard	Select Material for Undercuts, Contractor Furnished, FM
0140	209-A004		3,417	Square Yard	Geotextile Stabilization, Type V, Non-Woven
0150	211-B001	(E)	10,000	Cubic Yard	Topsoil for Slope Treatment, Contractor Furnished
0160	212-B001		5,084	Square Yard	Standard Ground Preparation
0170	213-B001		1	Ton	Combination Fertilizer, 13-13-13
0180	213-C001		155	Ton	Superphosphate
0190	216-A001		5,084	Square Yard	Solid Sodding
0200	217-A001		11,367	Square Yard	Ditch Liner
0210	219-A001		102	Thousand Gallon	Watering [\$20.00]
0220	220-A001		155	Acre	Insect Pest Control [\$30.00]
0230	221-A001	(S)	348	Cubic Yard	Portland Cement Concrete Paved Ditch
0240	223-A001		310	Acre	Mowing [\$40.00]
0250	224-A001		6,433	Square Yard	Soil Reinforcing Mat
0260	234-A001		10,300	Linear Feet	Temporary Silt Fence
	Changed 01/14/2013				
0270	235-A001		1,900	Bale	Temporary Erosion Checks
	Changed 01/14/2013				



Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0280	236-A004		41	Each	Silt Basin, Type D
0290	236-B004		41	Each	Maintenance and Removal of Existing Silt Basins, Type D
0300	239-A001		11,000	Linear Feet	Temporary Slope Drains
0310	406-A001		3,700	Square Yard	Cold Milling of Bituminous Pavement, All Depths
0320	423-A001		1	Mile	Rumble Strips, Ground In
0330	501-E001		1,015	Linear Feet	Expansion Joints, Without Dowels
0340	502-A001	(C)	2,254	Square Yard	Reinforced Cement Concrete Bridge End Pavement
0350	602-A001	(S)	212,767	Pounds	Reinforcing Steel
Changed 01/14/2013					
0360	603-CA002	(S)	3,830	Linear Feet	18" Reinforced Concrete Pipe, Class III
0370	603-CA003	(S)	616	Linear Feet	24" Reinforced Concrete Pipe, Class III
0380	603-CA004	(S)	68	Linear Feet	30" Reinforced Concrete Pipe, Class III
0390	603-CA005	(S)	1,140	Linear Feet	36" Reinforced Concrete Pipe, Class III
0400	603-CA007	(S)	400	Linear Feet	48" Reinforced Concrete Pipe, Class III
0410	603-CA011	(S)	44	Linear Feet	72" Reinforced Concrete Pipe, Class III
0420	603-CB001	(S)	35	Each	18" Reinforced Concrete End Section
0430	603-CB002	(S)	10	Each	24" Reinforced Concrete End Section
0440	603-CB003	(S)	2	Each	30" Reinforced Concrete End Section
0450	603-CB004	(S)	9	Each	36" Reinforced Concrete End Section
0460	603-CB006	(S)	6	Each	48" Reinforced Concrete End Section
0470	603-CB010	(S)	2	Each	72" Reinforced Concrete End Section
0480	603-CE003	(S)	48	Linear Feet	36" x 23" Concrete Arch Pipe, Class A III
0490	603-CE004	(S)	716	Linear Feet	44" x 27" Concrete Arch Pipe, Class A III
0500	603-CE006	(S)	116	Linear Feet	58" x 36" Concrete Arch Pipe, Class A III
0510	603-CF003	(S)	2	Each	36" x 23" Concrete Arch Pipe End Section
0520	603-CF004	(S)	6	Each	44" x 27" Concrete Arch Pipe End Section
0530	603-CF006	(S)	2	Each	58" x 36" Concrete Arch Pipe End Section
0540	604-A001		790	Pounds	Castings
0550	604-B001		8,750	Pounds	Gratings
0560	606-B001		625	Linear Feet	Guard Rail, Class A, Type 1
Changed 02/12/2013					
0570	606-D012		4	Each	Guard Rail, Bridge End Section, Type I
0580	606-E003		4	Each	Guard Rail, Terminal End Section, Non-Flared
0590	607-A001		32,540	Linear Feet	31.5" Type"A" Woven Wire Fence, w/ Barbed Wire as Shown
0600	607-B005		16,826	Linear Feet	60" Type I Chain Link Fence, Class II

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0610	607-G119		6	Each	Gate, 3' x 52" Chain Link
0620	607-P1002		232	Each	Line Post, 10' x 4" Timber
0630	607-P1009		173	Each	Line Post, 9' x 2" Galvanized Steel
0640	607-P1010		115	Each	Line Post, 10' x 2" Galvanized Steel
0650	607-P1020		1,734	Each	Line Post, 7' x 4" Timber
0660	607-P1021		347	Each	Line Post, 9' x 4" Timber
0670	607-P1027		861	Each	Line Post, 7' x 2" Galvanized Steel
0680	607-P2001		300	Each	Brace Post, 8' x 6" Timber
0690	607-P2002		60	Each	Brace Post, 10' x 6" Timber
0700	607-P2003		40	Each	Brace Post, 12' x 6" Timber
0710	607-P2009		192	Each	Brace Post, 8' x 2 1/2" Galvanized Steel
0720	607-P2011		39	Each	Brace Post, 10' x 2 1/2" Galvanized Steel
0730	607-P2012		26	Each	Brace Post, 12' x 2 1/2" Galvanized Steel
0740	607-P3003		12	Each	Gate Post, 8' x 2 1/2" Galvanized Steel
0750	608-A001	(S)	1,640	Square Yard	Concrete Sidewalk, Without Reinforcement
0760	609-D003	(S)	4,151	Linear Feet	Combination Concrete Curb and Gutter Type 3 Changed 02/12/2013
0770	614-B001	(S)	915	Square Yard	Concrete Driveway, With Reinforcement
0780	615-A018	(S)	320	Linear Feet	Concrete Bridge End Barrier, 33.5"
0790	618-A001		1	Lump Sum	Maintenance of Traffic
0800	619-A1003		5,442	Linear Feet	Temporary Traffic Stripe, Continuous White, Paint
0810	619-A2003		5,860	Linear Feet	Temporary Traffic Stripe, Continuous Yellow, Paint
0820	619-A2007		3,900	Linear Feet	Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape
0830	619-A3002		920	Linear Feet	Temporary Traffic Stripe, Skip White, Paint
0840	619-A5004		15,680	Linear Feet	Temporary Traffic Stripe, Detail, Type 1 Tape
0850	619-A6003		120	Linear Feet	Temporary Traffic Stripe, Legend, Paint
0860	619-C6001		72	Each	Red-Clear Reflective High Performance Raised Marker
0870	619-D1001		188	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet
0880	619-D2001		984	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More
0890	619-G4001		384	Linear Feet	Barricades, Type III, Single Faced
0900	619-G4004		108	Linear Feet	Barricades, Type III, Single Faced, Permanent, Red/White
0910	619-G5001		86	Each	Free Standing Plastic Drums
0920	619-G7001		12	Each	Warning Lights, Type "B"
0930	620-A001		1	Lump Sum	Mobilization
0940	621-A001		1	Each	Field Laboratory

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0950	627-L001		723	Each	Two-Way Yellow Reflective High Performance Raised Markers
0955	628-H002		66	Square Feet	Cold Plastic Legend, White
	Added 02/15/2013				
0960	630-A001		41	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness
0970	630-A002		45	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness
0980	630-C004		112	Linear Feet	Steel U-Section Posts, 3.0 to 3.5 lb/ft
0990	630-F001		44	Each	Delineators, Guard Rail, White
1000	630-G006		8	Each	Type 3 Object Markers, OM-3R or OM-3L
1010	815-A006	(S)	2,500	Ton	Loose Riprap, Size 100
1020	815-A009	(S)	19,077	Ton	Loose Riprap, Size 300
1030	815-E001	(S)	3,417	Square Yard	Geotextile under Riprap
1040	815-F002	(S)	2,142	Ton	Sediment Control Stone
	Changed 02/15/2013				
1050	907-225-A001		310	Acre	Grassing
1060	907-225-B001		622	Ton	Agricultural Limestone
1070	907-225-C001		663	Ton	Mulch, Vegetative Mulch
1080	907-226-A001		310	Acre	Temporary Grassing
1090	907-234-D001		26	Each	Inlet Siltation Guard
1100	907-234-F001		400	Linear Feet	Turbidity Barrier
1110	907-237-A002		600	Linear Feet	Wattles, 12"
	Changed 01/14/2013				
1120	907-237-A003		2,800	Linear Feet	Wattles, 20"
	Changed 01/14/2013				
1130	907-245-A001		2,800	Linear Feet	Triangular Silt Dike
	Changed 01/14/2013				
1140	907-246-A001		5,000	Linear Feet	Sandbags
	Changed 01/14/2013				
1150	907-247-A001		1	Each	Temporary Stream Diversion
1160	907-249-A001		500	Ton	Riprap for Erosion Control
1170	907-304-B009	(GT)	5,660	Ton	Granular Material, Class 3, Group D
1180	907-304-B011	(GT)	12,535	Ton	Granular Material, Class 9, Group B
1190	907-304-F002	(GT)	1,514	Ton	Size 610 Crushed Stone Base
1200	907-310-B001	(GT)	650	Ton	Size III Stabilizer Aggregate, Coarse
1210	907-407-A001	(A2)	12,450	Gallon	Asphalt for Tack Coat
1220	907-413-E001		483	Linear Feet	Sawing and Sealing Transverse Joints in Asphalt Pavement

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
1230	907-601-A001	(S)	1,333	Cubic Yard	Class "B" Structural Concrete
Changed 01/14/2013					
1240	907-601-B003	(S)	70	Cubic Yard	Class "B" Structural Concrete, Minor Structures
1250	907-603-ALT01	(S)	376	Linear Feet	18" Type A Alternate Pipe
1260	907-603-ALT02	(S)	232	Linear Feet	24" Type A Alternate Pipe
1270	907-603-ALT04	(S)	100	Linear Feet	36" Type A Alternate Pipe
1280	907-605-O002	(S)	1,920	Linear Feet	6" Perforated Sewer Pipe for Underdrains, SDR 35
1290	907-617-A001		240	Each	Right-of-Way Marker
1300	907-626-A003		1	Mile	6" Thermoplastic Traffic Stripe, Skip White
1310	907-626-B004		1	Mile	6" Thermoplastic Traffic Stripe, Continuous White
1320	907-626-C004		2	Mile	6" Thermoplastic Edge Stripe, Continuous White
1330	907-626-D003		1	Mile	6" Thermoplastic Traffic Stripe, Skip Yellow
1340	907-626-E004		2	Mile	6" Thermoplastic Traffic Stripe, Continuous Yellow
1350	907-626-G004		9,097	Linear Feet	Thermoplastic Detail Stripe, White
1360	907-626-G005		8,841	Linear Feet	Thermoplastic Detail Stripe, Yellow
1370	907-626-H005		66	Square Feet	Thermoplastic Legend, White
1380	907-699-A002		1	Lump Sum	Roadway Construction Stakes
1390	907-906001		2,080	Hours	Trainees [\$5.00]
<b>ALTERNATE GROUP AA NUMBER 1</b>					
1400	907-308-A001		372	Ton	Portland Cement
1410	907-308-B002	(M)	32,013	Square Yard	Soil-Cement-Water Mixing, Optional Mixers, Design Soil
1420	907-308-S001	(A3)	7,564	Gallon	Bituminous Curing Seal
<b>ALTERNATE GROUP AA NUMBER 2</b>					
1430	907-311-A003	(M)	32,013	Square Yard	Processing Lime and Fly Ash Treated Course, 6" Thick
1440	907-311-B001		246	Ton	Lime
1450	907-311-C002		985	Ton	Fly Ash, Class C or F
1460	907-311-S001	(A3)	7,564	Gallon	Bituminous Curing Seal
<b>ALTERNATE GROUP BB NUMBER 1</b>					
1470	907-403-A006	(BA1)	2,308	Ton	Hot Mix Asphalt, MT, 12.5-mm mixture
<b>ALTERNATE GROUP BB NUMBER 2</b>					
1480	907-403-M002	(BA1)	2,308	Ton	Warm Mix Asphalt, MT, 12.5-mm mixture
<b>ALTERNATE GROUP CC NUMBER 1</b>					
1490	907-403-A007	(BA1)	2,498	Ton	Hot Mix Asphalt, MT, 19-mm mixture
<b>ALTERNATE GROUP CC NUMBER 2</b>					
1500	907-403-M007	(BA1)	2,498	Ton	Warm Mix Asphalt, MT, 19-mm mixture
<b>ALTERNATE GROUP DD NUMBER 1</b>					

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
1510	907-403-A010	(BA1 )	1,731	Ton	Hot Mix Asphalt, MT, 9.5-mm mixture <b>ALTERNATE GROUP DD NUMBER 2</b>
1520	907-403-M006	(BA1 )	1,731	Ton	Warm Mix Asphalt, MT, 9.5-mm mixture <b>ALTERNATE GROUP EE NUMBER 1</b>
1530	907-403-A011	(BA1 )	3,044	Ton	Hot Mix Asphalt, ST, 12.5-mm mixture <b>ALTERNATE GROUP EE NUMBER 2</b>
1540	907-403-M003	(BA1 )	3,044	Ton	Warm Mix Asphalt, ST, 12.5-mm mixture <b>ALTERNATE GROUP FF NUMBER 1</b>
1550	907-403-A012	(BA1 )	6,768	Ton	Hot Mix Asphalt, ST, 19-mm mixture <b>ALTERNATE GROUP FF NUMBER 2</b>
1560	907-403-M004	(BA1 )	6,768	Ton	Warm Mix Asphalt, ST, 19-mm mixture <b>ALTERNATE GROUP GG NUMBER 1</b>
1570	907-403-A015	(BA1 )	2,447	Ton	Hot Mix Asphalt, ST, 9.5-mm mixture <b>ALTERNATE GROUP GG NUMBER 2</b>
1580	907-403-M001	(BA1 )	2,447	Ton	Warm Mix Asphalt, ST, 9.5-mm mixture <b>ALTERNATE GROUP HH NUMBER 1</b>
1590	628-A001		850	Linear Feet	6" Cold Plastic Traffic Stripe, Skip White
1600	628-B001		4,031	Linear Feet	6" Cold Plastic Traffic Stripe, Continuous White
1610	628-D001		850	Linear Feet	6" Cold Plastic Traffic Stripe, Skip Yellow
1620	628-E002		2,915	Linear Feet	6" Cold Plastic Traffic Stripe, Continuous Yellow <b>ALTERNATE GROUP HH NUMBER 2</b>
1630	907-626-I003		850	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Skip White
1640	907-626-J003		4,031	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White
1650	907-626-K003		850	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Skip Yellow
1660	907-626-L001		2,915	Linear Feet	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow <b>Bridge Items</b>
1670	501-K001		14,522	Square Yard	Transverse Grooving
1680	602-A001	(S )	95,106	Pounds	Reinforcing Steel
1690	801-A001	(S )	4,449	Cubic Yard	Foundation Excavation for Bridges
1700	803-B002	(S )	8	Each	Conventional Static Pile Load Test [\$5,000.00]
1710	803-C002	(S )	4,745	Linear Feet	14" x 14" Prestressed Concrete Piling Changed 02/12/2013
1720	803-C003	(S )			Deleted 02/15/2013
1730	803-D007	(S )	54,145	Linear Feet	HP 14 x 89 Steel Piling Changed 02/12/2013

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
1740	803-F009	(S)			Deleted 02/15/2013
1750	803-F011	(S)			Deleted 02/15/2013
1760	803-I001	(S)	20	Each	PDA Test Pile Changed 02/12/2013
1770	805-A001	(S)	2,125,184	Pounds	Reinforcement Changed 02/12/2013
1780	813-A002	(S)	4,811	Linear Feet	Concrete Railing, 32"
1790	813-E001	(S)	1,516	Linear Feet	Concrete Pedestrian Sidewalk Railing
1800	815-D001	(S)	1,315	Cubic Yard	Concrete Slope Paving
1810	907-803-P002	(S)	3,960	Linear Feet	30" Steel Pipe Piling, Wall Thickness 0.500" Changed 02/12/2013
1820	907-804-A001	(S)	9,782	Cubic Yard	Bridge Concrete, Class AA Changed 02/12/2013
1830	907-804-B001	(S)	772	Cubic Yard	Box Bridge Concrete, Class B
1840	907-804-C022	(S)	1,276	Linear Feet	80' Prestressed Concrete Beam, Type BT-72
1850	907-804-C025	(S)	1,436	Linear Feet	90' Prestressed Concrete Beam, Type BT-72
1860	907-804-C150	(S)	3,057	Linear Feet	110' Prestressed Concrete Beam, Type IV
1870	907-804-C174	(S)	1,113	Linear Feet	80' Prestressed Concrete Beam, Type IV
1880	907-804-C193	(S)	1,439	Linear Feet	103' Prestressed Concrete Beam, Type IV
1890	907-804-C206	(S)	1,197	Linear Feet	86' Prestressed Concrete Beam, Type IV
1900	907-804-C217	(S)	2,973	Linear Feet	107' Prestressed Concrete Beam, Type IV
1910	907-804-C231	(S)	837	Linear Feet	60' Prestressed Concrete Beam, Type IV
1920	907-804-C234	(S)	739	Linear Feet	53' Prestressed Concrete Beam, Type IV
1930	907-804-C235	(S)	1,057	Linear Feet	76' Prestressed Concrete Beam, Type IV
1940	907-804-C236	(S)	1,085	Linear Feet	78' Prestressed Concrete Beam, Type IV
1950	907-804-C237	(S)	1,752	Linear Feet	55' Prestressed Concrete Beam, Type BT-72
1960	907-804-C238	(S)	1,052	Linear Feet	66' Prestressed Concrete Beam, Type BT-72
1970	907-804-C239	(S)	4,088	Linear Feet	128' Prestressed Concrete Beam, Type BT-72