

DESOTO (17)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Dement Construction Company, LLC	T. L. Wallace Construction, Inc.
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$61,641,475.03	\$56,823,653.13	\$60,215,717.11	\$60,832,971.09
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS		2,844,950.00	1,300,000.00	2,400,000.00
0020	202-B002	Removal of Asphalt Driveways, All Depths	880.000	SY		6.60	3.75	3.80
0030	202-B005	Removal of Asphalt Pavement, All Depths	84,951.000	SY		2.85	2.20	2.80
0040	202-B008	Removal of Box Culvert	1.000	EA		7,000.00	2,500.00	8,630.00
0050	202-B042	Removal of Flared End Section, All Sizes	6.000	EA		315.00	165.00	167.00
0060	202-B064	Removal of Pipe, 8" And Above	1,285.000	LF		5.00	5.25	5.30
0070	202-B070	Removal of Sign Including Post & Footing	17.000	EA		200.00	250.00	204.00
0080	202-B076	Removal of Traffic Stripe	6,966.000	LF		1.00	1.00	1.00
0090	202-B079	Removal of Headwall	2.000	EA		550.00	200.00	167.00
0100	202-B292	Removal of Septic Tank, All Sizes	2.000	EA		3,000.00	1,000.00	1,010.00
0110	203-A003	Unclassified Excavation, FM, AH	2,482,969.000	CY		2.65	2.40	2.40
0120	203-EX017	Borrow Excavation, AH, FME, Class B9	397,579.000	CY		0.01	0.10	0.10
0130	203-EX035	Borrow Excavation, AH, FME, Class B9-6	154,022.000	CY		0.01	0.10	0.10
0140	203-G003	Excess Excavation, FM, AH	2,208,549.000	CY		1.40	2.50	2.50
0150	206-A001	Structure Excavation	15,582.000	CY		4.95	3.75	5.70
0160	206-B001	Select Material for Undercuts, Contractor Furnished, FM	625.000	CY		16.00	35.00	53.15
0170	209-A004	Geotextile Stabilization, Type V, Non-Woven	1,340.000	SY		1.70	2.15	2.15
0180	211-B001	Topsoil for Slope Treatment, Contractor Furnished	107,500.000	CY		0.01	0.10	0.10
0190	212-B001	Standard Ground Preparation	5,236.000	SY		0.25	0.25	0.80
0200	213-B001	Combination Fertilizer, 13-13-13	1.000	TON		625.00	640.00	816.00
0210	213-C001	Superphosphate	267.000	TON		595.00	650.00	765.00
0220	216-A001	Solid Sodding	5,236.000	SY		2.25	1.85	3.05
0230	217-A001	Ditch Liner	5,565.000	SY		5.00	1.00	0.50
0240	219-A001	Watering	105.000	KGAL		20.00	20.00	20.00
0250	220-A001	Insect Pest Control	267.000	ACRE		30.00	30.00	30.00
0260	221-A001	Portland Cement Concrete Paved Ditch	1,288.000	CY		335.00	325.00	342.00

DESOTO (17)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Dement Construction Company, LLC	T. L. Wallace Construction, Inc.
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$61,641,475.03	\$56,823,653.13	\$60,215,717.11	\$60,832,971.09
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0270	223-A001	Mowing	267.000	ACRE		40.00	40.00	40.00
0280	224-A001	Soil Reinforcing Mat	2,520.000	SY		1.85	1.25	2.65
0290	234-A001	Temporary Silt Fence	96,000.000	LF		2.90	2.15	2.05
0300	235-A001	Temporary Erosion Checks	6,000.000	BALE		7.30	6.50	3.55
0310	236-A004	Silt Basin, Type D	57.000	EA		1,250.00	1,280.00	1,290.00
0320	236-B004	Maintenance and Removal of Existing Silt Basins, Type D	57.000	EA		1,250.00	1,000.00	1,010.00
0330	239-A001	Temporary Slope Drains	1,188.000	LF		5.00	6.10	6.15
0340	406-A001	Cold Milling of Bituminous Pavement, All Depths	2,933.000	SY		6.17	2.82	5.10
0350	423-A001	Rumble Strips, Ground In	5.000	MI		300.00	300.00	306.00
0360	501-E001	Expansion Joints, Without Dowels	410.000	LF		10.00	15.15	10.20
0370	502-A001	Reinforced Cement Concrete Bridge End Pavement	875.000	SY		87.00	103.69	88.75
0380	602-A001	Reinforcing Steel	447,629.000	LBS		0.92	0.85	0.90
0390	603-CA002	18" Reinforced Concrete Pipe, Class III	4,220.000	LF		24.00	31.25	31.55
0400	603-CA003	24" Reinforced Concrete Pipe, Class III	440.000	LF		33.00	38.17	38.55
0410	603-CA004	30" Reinforced Concrete Pipe, Class III	512.000	LF		41.00	45.73	46.20
0420	603-CA005	36" Reinforced Concrete Pipe, Class III	808.000	LF		57.00	55.30	55.85
0430	603-CA006	42" Reinforced Concrete Pipe, Class III	424.000	LF		67.00	64.64	65.30
0440	603-CA007	48" Reinforced Concrete Pipe, Class III	812.000	LF		85.00	80.87	81.70
0450	603-CA008	54" Reinforced Concrete Pipe, Class III	692.000	LF		100.00	105.67	107.00
0460	603-CA009	60" Reinforced Concrete Pipe, Class III	1,144.000	LF		110.00	125.54	127.00
0470	603-CA038	18" Reinforced Concrete Pipe, Class IV, Class B Bedding	612.000	LF		28.00	40.29	40.70
0480	603-CA039	24" Reinforced Concrete Pipe, Class IV, Class B Bedding	520.000	LF		38.00	44.74	45.20
0490	603-CA041	36" Reinforced Concrete Pipe, Class IV, Class B Bedding	492.000	LF		68.00	62.96	63.60
0500	603-CA042	42" Reinforced Concrete Pipe, Class IV, Class B Bedding	452.000	LF		80.00	75.78	76.55
0510	603-CA045	60" Reinforced Concrete Pipe, Class IV, Class B Bedding	252.000	LF		140.00	140.17	142.00
0520	603-CB001	18" Reinforced Concrete End Section	34.000	EA		500.00	570.00	576.00

DESOTO (17)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Dement Construction Company, LLC	T. L. Wallace Construction, Inc.
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$61,641,475.03	\$56,823,653.13	\$60,215,717.11	\$60,832,971.09
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0530	603-CB002	24" Reinforced Concrete End Section	9.000	EA		520.00	610.00	616.00
0540	603-CB003	30" Reinforced Concrete End Section	6.000	EA		600.00	650.00	657.00
0550	603-CB004	36" Reinforced Concrete End Section	10.000	EA		900.00	985.00	995.00
0560	603-CB005	42" Reinforced Concrete End Section	6.000	EA		1,100.00	1,225.00	1,240.00
0570	603-CB006	48" Reinforced Concrete End Section	10.000	EA		1,200.00	1,475.00	1,490.00
0580	603-CB007	54" Reinforced Concrete End Section	6.000	EA		1,450.00	1,775.00	1,790.00
0590	603-CB008	60" Reinforced Concrete End Section	6.000	EA		1,800.00	2,175.00	2,200.00
0600	603-CE004	44" x 27" Concrete Arch Pipe, Class A III	184.000	LF		70.00	68.91	69.60
0610	603-CE006	58" x 36" Concrete Arch Pipe, Class A III	84.000	LF		102.00	100.80	102.00
0620	603-CE009	88" x 54" Concrete Arch Pipe, Class A III	880.000	LF		190.00	165.49	167.00
0630	603-CF004	44" x 27" Concrete Arch Pipe End Section	4.000	EA		950.00	1,295.00	1,310.00
0640	603-CF006	58" x 36" Concrete Arch Pipe End Section	2.000	EA		1,250.00	1,675.00	1,690.00
0650	603-CF009	88" x 54" Concrete Arch Pipe End Section	12.000	EA		2,200.00	2,725.00	2,750.00
0660	603-SB028	30" Branch Connections, Stub into Box Culvert	2.000	EA		650.00	650.00	1,080.00
0670	603-SB043	18" Branch Connections, Stub into 88" x 54" Concrete Pipe	1.000	EA		475.00	450.00	1,300.00
0680	604-B001	Gratings	16,500.000	LBS		2.90	3.00	2.40
0690	605-AA004	Geotextile for Subsurface Drainage, Type V	1,900.000	SY		1.70	2.21	2.25
0700	605-W001	Filter Material for Combination Storm Drain and/or Underdrai	160.000	CY		45.00	49.50	50.00
0710	605-W002	Filter Material for Combination Storm Drain and/or Underdrai	175.000	CY		30.00	49.50	50.00
0720	606-B001	Guard Rail, Class A, Type 1	1,111.000	LF		15.00	15.00	15.30
0730	606-D012	Guard Rail, Bridge End Section, Type I	12.000	EA		1,400.00	1,400.00	1,430.00
0740	606-E002	Guard Rail, Terminal End Section, Flared	8.000	EA		1,700.00	1,700.00	1,740.00
0750	606-E003	Guard Rail, Terminal End Section, Non-Flared	4.000	EA		1,800.00	1,800.00	1,840.00
0760	607-A002	60" Type "A" Woven Wire Fence, w/ Barbed Wire as Shown	22,812.000	LF		3.50	3.50	3.55
0770	607-B005	60" Type I Chain Link Fence, Class II	41,566.000	LF		5.20	5.20	5.30
0780	607-E001	Barbed Wire Fence, Single Strand	4,200.000	LF		0.25	0.25	0.25

DESOTO (17)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Dement Construction Company, LLC	T. L. Wallace Construction, Inc.
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$61,641,475.03	\$56,823,653.13	\$60,215,717.11	\$60,832,971.09
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
0790	607-G119	Gate, 3' x 52" Chain Link	8.000	EA		300.00	300.00	306.00
0800	607-P1007	Line Post, 7' x 1 1/2" Galvanized Steel	2,515.000	EA		33.35	33.35	34.05
0810	607-P1013	Line Post, 7' Tee Post Steel	1,294.000	EA		18.00	18.00	18.35
0820	607-P1014	Line Post, 9' Tee Post Steel	259.000	EA		20.00	20.00	20.40
0830	607-P1015	Line Post, 10' Tee Post Steel	173.000	EA		22.00	22.00	22.45
0840	607-P1025	Line Post, 10' x 1 1/2" Galvanized Steel	335.000	EA		35.00	35.00	35.70
0850	607-P1026	Line Post, 9' x 1 1/2" Galvanized Steel	503.000	EA		32.80	32.80	33.45
0860	607-P2001	Brace Post, 8' x 6" Timber	132.000	EA		107.50	107.50	110.00
0870	607-P2002	Brace Post, 10' x 6" Timber	26.000	EA		109.50	109.50	112.00
0880	607-P2003	Brace Post, 12' x 6" Timber	18.000	EA		112.50	112.50	115.00
0890	607-P2019	Brace Post, 10' x 2" Galvanized Steel	26.000	EA		104.00	104.00	106.00
0900	607-P2022	Brace Post, 12' x 2" Galvanized Steel	18.000	EA		108.00	108.00	110.00
0910	607-P2023	Brace Post, 8' x 2" Galvanized Steel	132.000	EA		100.00	100.00	102.00
0920	607-P3006	Gate Post, 12' x 2 1/2" Galvanized Steel	8.000	EA		119.00	119.00	121.00
0930	607-Z001	Concrete Anchors	176.000	EA		26.25	26.25	26.80
0940	608-A001	Concrete Sidewalk, Without Reinforcement	563.000	SY		35.00	31.35	35.70
0950	609-D002	Combination Concrete Curb and Gutter Type 2	306.000	LF		20.00	18.70	20.40
0960	609-D004	Combination Concrete Curb and Gutter Type 3A Modified	1,401.000	LF		14.75	16.10	15.05
0970	615-A018	Concrete Bridge End Barrier, 33.5"	40.000	LF		42.00	53.31	46.70
0980	615-A019	Concrete Bridge End Barrier, 43.5"	80.000	LF		52.00	88.23	57.10
0990	616-A001	Concrete Median and/or Island Pavement, 4-inch	204.000	SY		32.00	33.00	32.65
1000	616-A003	Concrete Median and/or Island Pavement, 10-inch	60.000	SY		72.00	63.35	73.45
1010	618-A001	Maintenance of Traffic	1.000	LS		135,000.00	4,000.00	35,000.00
1020	619-A1004	Temporary Traffic Stripe, Continuous White, Paint	10.000	MI		700.00	700.00	714.00
1030	619-A2004	Temporary Traffic Stripe, Continuous Yellow, Paint	7.000	MI		700.00	700.00	714.00
1040	619-A4002	Temporary Traffic Stripe, Skip Yellow, Paint	2,806.000	LF		0.30	0.30	0.30

DESOTO (17)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Dement Construction Company, LLC	T. L. Wallace Construction, Inc.
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$61,641,475.03	\$56,823,653.13	\$60,215,717.11	\$60,832,971.09
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
1050	619-A5002	Temporary Traffic Stripe, Detail, Paint	51,880.000	LF		0.20	0.20	0.20
1060	619-A5004	Temporary Traffic Stripe, Detail, Type 1 Tape	17,908.000	LF		1.50	1.50	1.55
1070	619-A6003	Temporary Traffic Stripe, Legend, Paint	442.000	LF		1.00	1.00	1.00
1080	619-A6004	Temporary Traffic Stripe, Legend, Paint	789.000	SF		1.50	1.50	1.55
1090	619-C6001	Red-Clear Reflective High Performance Raised Marker	110.000	EA		5.00	5.00	5.10
1100	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	2,653.000	EA		4.00	4.00	4.10
1110	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	702.000	SF		6.00	7.25	7.40
1120	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	682.000	SF		6.00	7.25	7.40
1130	619-F1001	Concrete Median Barrier, Precast	1,890.000	LF		35.00	30.00	65.65
1140	619-F2001	Remove and Reset Concrete Median Barrier, Precast	550.000	LF		12.00	12.50	22.50
1150	619-G4001	Barricades, Type III, Single Faced	989.000	LF		14.00	14.00	14.30
1160	619-G4004	Barricades, Type III, Single Faced, Permanent, Red/White	396.000	LF		25.00	105.00	107.00
1170	619-G4005	Barricades, Type III, Double Faced	126.000	LF		16.00	15.00	15.30
1180	619-G5001	Free Standing Plastic Drums	399.000	EA		32.00	41.00	41.85
1190	619-G7001	Warning Lights, Type "B"	26.000	EA		175.00	110.00	112.00
1200	620-A001	Mobilization	1.000	LS		4,515,000.00	4,920,000.00	4,700,000.00
1210	621-A001	Field Laboratory	1.000	EA		10,000.00	25,000.00	22,000.00
1220	627-K001	Red-Clear Reflective High Performance Raised Markers	110.000	EA		5.00	5.00	5.10
1230	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	2,170.000	EA		4.00	4.00	4.10
1240	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	20.000	SF		13.00	17.00	16.85
1250	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	297.000	SF		14.00	17.50	17.85
1260	630-C004	Steel U-Section Posts, 3.0 to 3.5 lb/ft	325.000	LF		7.25	6.50	7.65
1270	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	152.000	LBS		2.75	1.00	1.00
1280	630-F001	Delineators, Guard Rail, White	66.000	EA		10.80	14.00	13.25
1290	630-G002	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	12.000	EA		25.00	65.00	56.10
1300	630-K001	Welded & Seamless Steel Pipe Posts, 3"	15.000	LF		25.00	40.00	35.70

DESOTO (17)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Dement Construction Company, LLC	T. L. Wallace Construction, Inc.
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$61,641,475.03	\$56,823,653.13	\$60,215,717.11	\$60,832,971.09
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
1310	630-K003	Welded & Seamless Steel Pipe Posts, 4"	107.000	LF		35.00	50.00	45.90
1320	815-A006	Loose Riprap, Size 100	2,500.000	TON		38.00	35.00	35.35
1330	815-A009	Loose Riprap, Size 300	34,010.000	TON		38.00	35.00	35.35
1340	815-E001	Geotextile under Riprap	32,925.000	SY		1.25	2.17	2.20
1350	815-F002	Sediment Control Stone	2,252.000	TON		26.50	29.00	29.30
1360	907-225-A001	Grassing	570.000	ACRE		695.00	585.00	969.00
1370	907-225-B001	Agricultural Limestone	1,601.000	TON		45.00	42.00	40.80
1380	907-225-C001	Mulch, Vegetative Mulch	1,111.000	TON		155.00	150.00	81.65
1390	907-226-A001	Temporary Grassing	570.000	ACRE		550.00	525.00	536.00
1400	907-234-C002	Super Silt Fence	3,543.000	LF		7.50	8.50	8.15
1410	907-234-D001	Inlet Siltation Guard	45.000	EA		440.00	450.00	561.00
1420	907-234-F001	Turbidity Barrier	1,000.000	LF		15.00	13.00	10.20
1430	907-237-A002	Wattles, 12"	4,000.000	LF		2.85	2.85	2.05
1440	907-237-A003	Wattles, 20"	12,000.000	LF		4.15	3.50	3.00
1450	907-245-A001	Triangular Silt Dike	7,500.000	LF		7.25	7.25	6.10
1460	907-246-A001	Sandbags	3,600.000	LF		4.25	8.00	6.10
1470	907-247-A001	Temporary Stream Diversion	7.000	EA		10,000.00	7,500.00	4,050.00
1480	907-249-A001	Riprap for Erosion Control	500.000	TON		45.00	37.00	37.35
1490	907-249-B001	Remove and Reset Riprap	500.000	CY		20.00	10.00	10.10
1500	907-304-B009	Granular Material, Class 3, Group D	49,957.000	TON		2.00	14.80	14.95
1510	907-304-C008	Granular Material, AEA, Class 9, Group B	52,765.000	CY		2.00	13.30	13.45
1530	907-310-B001	Size III Stabilizer Aggregate, Coarse	100.000	TON		45.00	31.00	31.30
1540	907-407-A001	Asphalt for Tack Coat	25,265.000	GAL		0.01	0.01	0.01
1550	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	352.000	LF		10.50	20.11	15.30
1560	907-601-A001	Class "B" Structural Concrete	1,849.000	CY		400.00	380.00	478.00
1570	907-601-B003	Class "B" Structural Concrete, Minor Structures	68.000	CY		1,200.00	1,500.00	1,320.00

DESOTO (17)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Dement Construction Company, LLC	T. L. Wallace Construction, Inc.
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$61,641,475.03	\$56,823,653.13	\$60,215,717.11	\$60,832,971.09
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
1580	907-603-ALT01	18" Type A Alternate Pipe	908.000	LF		17.00	20.00	20.20
1590	907-603-ALT02	24" Type A Alternate Pipe	920.000	LF		24.00	25.00	25.25
1600	907-605-O001	6" Perforated Sewer Pipe for Underdrains, SDR 23.5	2,500.000	LF		9.00	8.40	8.50
1610	907-605-P001	6" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	100.000	LF		9.00	8.40	8.50
1620	907-617-A001	Right-of-Way Marker	239.000	EA		150.00	150.00	153.00
1630	907-619-E3001	Changeable Message Sign	5.000	EA		10,800.00	12,000.00	17,000.00
1640	907-626-B003	6" Thermoplastic Traffic Stripe, Continuous White	1,856.000	LF		0.50	0.50	0.50
1650	907-626-C008	6" Thermoplastic Edge Stripe, Continuous White	30,569.000	LF		0.50	0.50	0.50
1660	907-626-D004	6" Thermoplastic Traffic Stripe, Skip Yellow	2,806.000	LF		0.25	0.25	0.25
1670	907-626-E003	6" Thermoplastic Traffic Stripe, Continuous Yellow	17,118.000	LF		0.50	0.50	0.50
1680	907-626-G004	Thermoplastic Detail Stripe, White	3,479.000	LF		1.25	1.25	1.30
1690	907-626-G005	Thermoplastic Detail Stripe, Yellow	44,986.000	LF		1.00	1.00	1.00
1700	907-626-H004	Thermoplastic Legend, White	442.000	LF		2.00	2.00	2.05
1710	907-626-H005	Thermoplastic Legend, White	702.000	SF		6.00	6.00	6.10
1720	907-630-O002	Remove and Reset Sign Assembly	1.000	EA		275.00	500.00	281.00
1730	907-699-A002	Roadway Construction Stakes	1.000	LS		427,500.00	317,900.00	545,000.00
1740	907-804-B001	Box Bridge Concrete, Class B	566.000	CY		390.00	380.00	495.00
1750	907-906001	Trainees	2,080.000	HRS		5.00	5.00	5.00
1760	907-308-A001	Portland Cement	713.000	TON		130.00	119.00	121.00
1770	907-308-B002	Soil-Cement-Water Mixing, Optional Mixers, Design Soil	61,265.000	SY		1.15	1.20	1.20
1780	907-308-S001	Bituminous Curing Seal	15,316.000	GAL		3.05	2.95	3.00
1790	907-311-A003	Processing Lime and Fly Ash Treated Course, 6" Thick	61,265.000	SY				
1800	907-311-B001	Lime	472.000	TON				
1810	907-311-C002	Fly Ash, Class C or F	1,885.000	TON				
1820	907-311-S001	Bituminous Curing Seal	15,316.000	GAL				
1830	907-403-A006	Hot Mix Asphalt, MT, 12.5-mm mixture	5,034.000	TON		86.74	86.74	88.50

DESOTO (17)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Dement Construction Company, LLC	T. L. Wallace Construction, Inc.
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$61,641,475.03	\$56,823,653.13	\$60,215,717.11	\$60,832,971.09
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
1840	907-403-M002	Warm Mix Asphalt, MT, 12.5-mm mixture	5,034.000	TON				
1850	907-403-A007	Hot Mix Asphalt, MT, 19-mm mixture	5,564.000	TON		76.89	76.89	78.45
1860	907-403-M007	Warm Mix Asphalt, MT, 19-mm mixture	5,564.000	TON				
1870	907-403-A010	Hot Mix Asphalt, MT, 9.5-mm mixture	4,221.000	TON		88.62	88.62	90.45
1880	907-403-M006	Warm Mix Asphalt, MT, 9.5-mm mixture	4,221.000	TON				
1890	907-403-A011	Hot Mix Asphalt, ST, 12.5-mm mixture	12,356.000	TON		87.74	87.74	89.55
1900	907-403-M003	Warm Mix Asphalt, ST, 12.5-mm mixture	12,356.000	TON				
1910	907-403-A012	Hot Mix Asphalt, ST, 19-mm mixture	10,483.000	TON		76.89	76.89	78.45
1920	907-403-M004	Warm Mix Asphalt, ST, 19-mm mixture	10,483.000	TON				
1930	907-403-A015	Hot Mix Asphalt, ST, 9.5-mm mixture	9,267.000	TON		89.00	89.00	90.80
1940	907-403-M001	Warm Mix Asphalt, ST, 9.5-mm mixture	9,267.000	TON				
1950	907-626-J003	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous	2,540.000	LF				
1960	907-626-L001	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous	877.000	LF				
1970	907-626-M002	Inverted Profile Thermoplastic Detail Traffic Stripe, Yellow	4,922.000	LF				
1980	628-J002	6" High Performance Cold Plastic Traffic Stripe, Continuous	2,540.000	LF		5.00	5.00	5.10
1990	628-M002	6" High Performance Cold Plastic Traffic Stripe, Continuous	877.000	LF		5.00	5.00	5.10
2000	628-O002	High Performance Cold Plastic Detail Stripe, Yellow	4,922.000	LF		5.25	5.25	5.35
2001	907-304-F002	Size 610 Crushed Stone Base	605.000	TON		38.00		29.30
2002	907-304-F004	Size 825B Crushed Stone Base	605.000	TON				
2003	907-304-F003	3/4" and Down Crushed Stone Base	605.000	TON			30.00	
2010	501-K001	Transverse Grooving	33,370.000	SY		1.32	1.25	1.30
2020	801-A001	Foundation Excavation for Bridges	3,384.000	CY		10.00	10.00	13.60
2030	803-B002	Conventional Static Pile Load Test	11.000	EA		5,000.00	5,000.00	5,000.00
2040	803-C002	14" x 14" Prestressed Concrete Piling	5,780.000	LF		36.00	27.00	40.40
2050	803-C004	18" x 18" Prestressed Concrete Piling	12,980.000	LF		45.00	37.00	50.70
2060	803-D007	HP 14 x 89 Steel Piling	46,965.000	LF		46.00	48.00	53.20

DESOTO (17)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Dement Construction Company, LLC	T. L. Wallace Construction, Inc.
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$61,641,475.03	\$56,823,653.13	\$60,215,717.11	\$60,832,971.09
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
2070	803-F009	20" Pre-Formed Pile Hole	700.000	LF		10.00	25.00	24.45
2080	803-I001	PDA Test Pile	36.000	EA		5,000.00	7,000.00	6,520.00
2090	803-J001	Pile Restrike	11.000	EA		1,000.00	500.00	1,610.00
2100	805-A001	Reinforcement	3,865,211.000	LBS		0.92	0.68	0.76
2110	810-A003	Structural Steel, A 709, Grade 50	2,608,132.000	LBS		1.43	1.60	1.44
2120	813-A002	Concrete Railing, 32"	11,301.000	LF		42.00	50.00	46.70
2130	813-A003	Concrete Railing, 42"	1,549.000	LF		52.00	55.00	57.15
2140	813-E001	Concrete Pedestrian Sidewalk Railing	744.000	LF		42.00	60.00	47.20
2150	815-A009	Loose Riprap, Size 300	26,907.000	TON		38.00	35.00	35.35
2160	815-D001	Concrete Slope Paving	727.000	CY		300.00	500.00	408.00
2170	815-E001	Geotextile under Riprap	38,465.000	SY		1.25	1.50	2.20
2180	907-803-K003	Drilled Shaft, 54" Diameter	660.000	LF		510.00	650.00	317.00
2190	907-803-K005	Drilled Shaft, 66" Diameter	660.000	LF		660.00	725.00	451.00
2200	907-803-K010	Drilled Shaft, 72" Diameter	2,316.000	LF		895.00	1,200.00	503.00
2210	907-803-L001	Test Shaft, 66" Diameter	1.000	EA		164,000.00	165,000.00	150,000.00
2220	907-803-L006	Test Shaft, 72" Diameter	1.000	EA		185,000.00	200,000.00	155,000.00
2230	907-803-M004	Trial Shaft, 66" Diameter	73.000	LF		830.00	1,000.00	807.00
2240	907-803-M008	Trial Shaft, 72" Diameter	78.000	LF		1,045.00	1,500.00	851.00
2250	907-804-A001	Bridge Concrete, Class AA	17,985.000	CY		410.00	439.00	482.00
2260	907-804-C011	130' Prestressed Concrete Beam, Type BT-72	2,076.000	LF		135.00	130.00	141.00
2270	907-804-C016	40' Prestressed Concrete Beam, Type I+2	9,374.000	LF		60.00	80.00	65.75
2280	907-804-C019	60' Prestressed Concrete Beam, Type II+2	3,322.000	LF		70.00	90.00	85.15
2290	907-804-C021	70' Prestressed Concrete Beam, Type III	972.000	LF		70.00	100.00	97.70
2300	907-804-C030	80' Prestressed Concrete Beam, Type III	2,538.000	LF		80.00	100.00	89.70
2310	907-804-C145	50' Prestressed Concrete Beam, Type II + 2	1,385.000	LF		80.00	90.00	83.70
2320	907-804-C146	88' Prestressed Concrete Beam, Type IV	612.000	LF		90.00	115.00	119.00

DESOTO (17)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Tanner Construction Company, Inc.	Dement Construction Company, LLC	T. L. Wallace Construction, Inc.
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$61,641,475.03	\$56,823,653.13	\$60,215,717.11	\$60,832,971.09
Ref#	SM Item	Item Description	Item Qty	Units		1	2	3
2330	907-804-C148	75' Prestressed Concrete Beam, Type IV	1,042.000	LF		90.00	115.00	104.00
2340	907-804-C150	110' Prestressed Concrete Beam, Type IV	3,503.000	LF		90.00	115.00	122.00
2350	907-804-C171	100' Prestressed Concrete Beam, Type IV	3,192.000	LF		100.00	115.00	112.00
2360	907-804-C178	73' Prestressed Concrete Beam, Type IV	579.000	LF		100.00	115.00	110.00
2370	907-804-C206	86' Prestressed Concrete Beam, Type IV	598.000	LF		100.00	115.00	120.00
2380	907-804-C217	107' Prestressed Concrete Beam, Type IV	4,671.000	LF		100.00	115.00	124.00
2390	907-804-C239	128' Prestressed Concrete Beam, Type BT-72	2,035.000	LF		100.00	130.00	143.00
2400	907-804-C242	81' Prestressed Concrete Beam, Type IV	1,126.000	LF		100.00	115.00	103.00
2410	907-804-C248	64' Prestressed Concrete Beam, Type BT-72	1,015.000	LF		110.00	130.00	134.00
2420	907-804-C249	68' Prestressed Concrete Beam, Type BT-72	1,079.000	LF		110.00	130.00	135.00
2430	907-804-C250	87' Prestressed Concrete Beam, Type IV	691.000	LF		110.00	115.00	117.00
2440	907-804-C251	111' Prestressed Concrete Beam, Type IV	1,542.000	LF		110.00	115.00	127.00
2450	907-811-D001	Disc Bearing Device	40.000	EA		4,500.00	7,000.00	4,200.00

DESOTO (17)					Eutaw Construction Company, Inc.	James Construction Group, LLC	N. L. Carson Construction Company, Inc.	
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$62,375,386.01	\$65,156,542.64	\$66,543,672.56	
Ref#	SM Item	Item Description	Item Qty	Units	4	5	6	
0010	201-A001	Clearing and Grubbing	1.000	LS	2,211,000.00	1,238,400.00	2,657,206.98	
0020	202-B002	Removal of Asphalt Driveways, All Depths	880.000	SY	4.87	3.75	3.75	
0030	202-B005	Removal of Asphalt Pavement, All Depths	84,951.000	SY	2.30	3.00	2.45	
0040	202-B008	Removal of Box Culvert	1.000	EA	3,150.00	8,000.00	10,000.00	
0050	202-B042	Removal of Flared End Section, All Sizes	6.000	EA	133.00	165.00	165.00	
0060	202-B064	Removal of Pipe, 8" And Above	1,285.000	LF	7.00	5.24	5.24	
0070	202-B070	Removal of Sign Including Post & Footing	17.000	EA	193.00	200.00	200.00	
0080	202-B076	Removal of Traffic Stripe	6,966.000	LF	0.97	0.97	1.00	
0090	202-B079	Removal of Headwall	2.000	EA	287.00	165.00	165.00	
0100	202-B292	Removal of Septic Tank, All Sizes	2.000	EA	1,500.00	1,000.00	1,000.00	
0110	203-A003	Unclassified Excavation, FM, AH	2,482,969.000	CY	3.30	2.29	2.29	
0120	203-EX017	Borrow Excavation, AH, FME, Class B9	397,579.000	CY	0.01	0.10	0.10	
0130	203-EX035	Borrow Excavation, AH, FME, Class B9-6	154,022.000	CY	4.40	0.10	0.10	
0140	203-G003	Excess Excavation, FM, AH	2,208,549.000	CY	2.00	2.40	2.40	
0150	206-A001	Structure Excavation	15,582.000	CY	6.00	3.75	3.75	
0160	206-B001	Select Material for Undercuts, Contractor Furnished, FM	625.000	CY	50.00	35.00	35.00	
0170	209-A004	Geotextile Stabilization, Type V, Non-Woven	1,340.000	SY	2.00	2.15	2.15	
0180	211-B001	Topsoil for Slope Treatment, Contractor Furnished	107,500.000	CY	2.40	0.10	0.10	
0190	212-B001	Standard Ground Preparation	5,236.000	SY	0.80	0.24	0.25	
0200	213-B001	Combination Fertilizer, 13-13-13	1.000	TON	800.00	603.00	625.00	
0210	213-C001	Superphosphate	267.000	TON	750.00	575.00	595.00	
0220	216-A001	Solid Sodding	5,236.000	SY	3.00	2.20	2.25	
0230	217-A001	Ditch Liner	5,565.000	SY	0.50	1.00	1.00	
0240	219-A001	Watering	105.000	KGAL	20.00	20.00	20.00	
0250	220-A001	Insect Pest Control	267.000	ACRE	30.00	30.00	30.00	
0260	221-A001	Portland Cement Concrete Paved Ditch	1,288.000	CY	300.00	325.00	359.00	

DESOTO (17)					Eutaw Construction Company, Inc.	James Construction Group, LLC	N. L. Carson Construction Company, Inc.	
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$62,375,386.01	\$65,156,542.64	\$66,543,672.56	
Ref#	SM Item	Item Description	Item Qty	Units	4	5	6	
0270	223-A001	Mowing	267.000	ACRE	40.00	40.00	40.00	
0280	224-A001	Soil Reinforcing Mat	2,520.000	SY	2.60	1.80	1.85	
0290	234-A001	Temporary Silt Fence	96,000.000	LF	2.75	3.50	2.90	
0300	235-A001	Temporary Erosion Checks	6,000.000	BALE	3.50	10.00	7.30	
0310	236-A004	Silt Basin, Type D	57.000	EA	1,115.00	1,280.00	1,280.00	
0320	236-B004	Maintenance and Removal of Existing Silt Basins, Type D	57.000	EA	1,553.00	1,000.00	1,000.00	
0330	239-A001	Temporary Slope Drains	1,188.000	LF	4.65	6.10	6.10	
0340	406-A001	Cold Milling of Bituminous Pavement, All Depths	2,933.000	SY	4.50	3.00	3.32	
0350	423-A001	Rumble Strips, Ground In	5.000	MI	289.50	300.00	350.00	
0360	501-E001	Expansion Joints, Without Dowels	410.000	LF	11.00	16.00	11.00	
0370	502-A001	Reinforced Cement Concrete Bridge End Pavement	875.000	SY	115.00	90.00	110.00	
0380	602-A001	Reinforcing Steel	447,629.000	LBS	0.71	0.70	0.87	
0390	603-CA002	18" Reinforced Concrete Pipe, Class III	4,220.000	LF	30.30	31.25	31.25	
0400	603-CA003	24" Reinforced Concrete Pipe, Class III	440.000	LF	38.00	38.17	38.17	
0410	603-CA004	30" Reinforced Concrete Pipe, Class III	512.000	LF	46.39	45.73	45.73	
0420	603-CA005	36" Reinforced Concrete Pipe, Class III	808.000	LF	56.87	55.30	55.30	
0430	603-CA006	42" Reinforced Concrete Pipe, Class III	424.000	LF	65.06	64.64	64.64	
0440	603-CA007	48" Reinforced Concrete Pipe, Class III	812.000	LF	78.49	80.87	80.87	
0450	603-CA008	54" Reinforced Concrete Pipe, Class III	692.000	LF	99.05	105.67	105.67	
0460	603-CA009	60" Reinforced Concrete Pipe, Class III	1,144.000	LF	114.61	125.54	125.54	
0470	603-CA038	18" Reinforced Concrete Pipe, Class IV, Class B Bedding	612.000	LF	41.41	40.29	40.29	
0480	603-CA039	24" Reinforced Concrete Pipe, Class IV, Class B Bedding	520.000	LF	51.80	44.74	44.74	
0490	603-CA041	36" Reinforced Concrete Pipe, Class IV, Class B Bedding	492.000	LF	77.36	62.96	62.96	
0500	603-CA042	42" Reinforced Concrete Pipe, Class IV, Class B Bedding	452.000	LF	81.16	75.78	75.78	
0510	603-CA045	60" Reinforced Concrete Pipe, Class IV, Class B Bedding	252.000	LF	160.54	140.17	140.17	
0520	603-CB001	18" Reinforced Concrete End Section	34.000	EA	647.94	570.00	570.00	

DESOTO (17)					Eutaw Construction Company, Inc.	James Construction Group, LLC	N. L. Carson Construction Company, Inc.	
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$62,375,386.01	\$65,156,542.64	\$66,543,672.56	
Ref#	SM Item	Item Description	Item Qty	Units	4	5	6	
0530	603-CB002	24" Reinforced Concrete End Section	9.000	EA	687.25	610.00	610.00	
0540	603-CB003	30" Reinforced Concrete End Section	6.000	EA	733.12	650.00	650.00	
0550	603-CB004	36" Reinforced Concrete End Section	10.000	EA	1,027.98	985.00	985.00	
0560	603-CB005	42" Reinforced Concrete End Section	6.000	EA	1,191.79	1,225.00	1,225.00	
0570	603-CB006	48" Reinforced Concrete End Section	10.000	EA	1,286.80	1,475.00	1,475.00	
0580	603-CB007	54" Reinforced Concrete End Section	6.000	EA	1,590.30	1,775.00	1,775.00	
0590	603-CB008	60" Reinforced Concrete End Section	6.000	EA	1,773.76	2,175.00	2,175.00	
0600	603-CE004	44" x 27" Concrete Arch Pipe, Class A III	184.000	LF	71.55	69.00	68.91	
0610	603-CE006	58" x 36" Concrete Arch Pipe, Class A III	84.000	LF	103.49	100.80	100.80	
0620	603-CE009	88" x 54" Concrete Arch Pipe, Class A III	880.000	LF	220.90	165.50	165.49	
0630	603-CF004	44" x 27" Concrete Arch Pipe End Section	4.000	EA	1,054.20	1,200.00	1,295.00	
0640	603-CF006	58" x 36" Concrete Arch Pipe End Section	2.000	EA	1,350.86	1,675.00	1,675.00	
0650	603-CF009	88" x 54" Concrete Arch Pipe End Section	12.000	EA	2,412.62	2,725.00	2,725.00	
0660	603-SB028	30" Branch Connections, Stub into Box Culvert	2.000	EA	723.75	857.13	450.00	
0670	603-SB043	18" Branch Connections, Stub into 88" x 54" Concrete Pipe	1.000	EA	723.75	1,000.00	350.00	
0680	604-B001	Gratings	16,500.000	LBS	3.38	4.19	2.48	
0690	605-AA004	Geotextile for Subsurface Drainage, Type V	1,900.000	SY	1.18	2.21	2.21	
0700	605-W001	Filter Material for Combination Storm Drain and/or Underdrai	160.000	CY	56.00	49.50	49.50	
0710	605-W002	Filter Material for Combination Storm Drain and/or Underdrai	175.000	CY	25.32	49.50	49.50	
0720	606-B001	Guard Rail, Class A, Type 1	1,111.000	LF	14.48	15.00	15.00	
0730	606-D012	Guard Rail, Bridge End Section, Type I	12.000	EA	1,351.00	1,400.00	1,400.00	
0740	606-E002	Guard Rail, Terminal End Section, Flared	8.000	EA	1,640.50	1,700.00	1,700.00	
0750	606-E003	Guard Rail, Terminal End Section, Non-Flared	4.000	EA	1,737.00	1,800.00	1,800.00	
0760	607-A002	60" Type "A" Woven Wire Fence, w/ Barbed Wire as Shown	22,812.000	LF	2.27	3.50	3.50	
0770	607-B005	60" Type I Chain Link Fence, Class II	41,566.000	LF	3.79	5.20	5.20	
0780	607-E001	Barbed Wire Fence, Single Strand	4,200.000	LF	0.51	0.25	0.25	

DESOTO (17)					Eutaw Construction Company, Inc.	James Construction Group, LLC	N. L. Carson Construction Company, Inc.	
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$62,375,386.01	\$65,156,542.64	\$66,543,672.56	
Ref#	SM Item	Item Description	Item Qty	Units	4	5	6	
0790	607-G119	Gate, 3' x 52" Chain Link	8.000	EA	151.50	300.00	300.00	
0800	607-P1007	Line Post, 7' x 1 1/2" Galvanized Steel	2,515.000	EA	31.31	36.04	33.35	
0810	607-P1013	Line Post, 7' Tee Post Steel	1,294.000	EA	12.12	18.00	18.00	
0820	607-P1014	Line Post, 9' Tee Post Steel	259.000	EA	17.17	20.00	20.00	
0830	607-P1015	Line Post, 10' Tee Post Steel	173.000	EA	17.17	20.17	22.00	
0840	607-P1025	Line Post, 10' x 1 1/2" Galvanized Steel	335.000	EA	42.42	35.00	35.00	
0850	607-P1026	Line Post, 9' x 1 1/2" Galvanized Steel	503.000	EA	37.37	32.80	32.80	
0860	607-P2001	Brace Post, 8' x 6" Timber	132.000	EA	128.27	107.50	107.50	
0870	607-P2002	Brace Post, 10' x 6" Timber	26.000	EA	156.55	109.50	109.50	
0880	607-P2003	Brace Post, 12' x 6" Timber	18.000	EA	160.59	112.50	112.50	
0890	607-P2019	Brace Post, 10' x 2" Galvanized Steel	26.000	EA	114.13	104.00	104.00	
0900	607-P2022	Brace Post, 12' x 2" Galvanized Steel	18.000	EA	141.40	108.00	108.00	
0910	607-P2023	Brace Post, 8' x 2" Galvanized Steel	132.000	EA	93.93	100.00	100.00	
0920	607-P3006	Gate Post, 12' x 2 1/2" Galvanized Steel	8.000	EA	126.25	119.00	119.00	
0930	607-Z001	Concrete Anchors	176.000	EA	25.25	26.25	26.25	
0940	608-A001	Concrete Sidewalk, Without Reinforcement	563.000	SY	33.78	33.80	36.00	
0950	609-D002	Combination Concrete Curb and Gutter Type 2	306.000	LF	19.30	19.00	18.00	
0960	609-D004	Combination Concrete Curb and Gutter Type 3A Modified	1,401.000	LF	14.23	14.25	20.00	
0970	615-A018	Concrete Bridge End Barrier, 33.5"	40.000	LF	40.53	43.00	46.90	
0980	615-A019	Concrete Bridge End Barrier, 43.5"	80.000	LF	50.18	54.50	61.90	
0990	616-A001	Concrete Median and/or Island Pavement, 4-inch	204.000	SY	30.88	30.90	38.00	
1000	616-A003	Concrete Median and/or Island Pavement, 10-inch	60.000	SY	69.48	69.50	75.00	
1010	618-A001	Maintenance of Traffic	1.000	LS	120,000.00	10,000.00	90,500.00	
1020	619-A1004	Temporary Traffic Stripe, Continuous White, Paint	10.000	MI	675.50	675.50	700.00	
1030	619-A2004	Temporary Traffic Stripe, Continuous Yellow, Paint	7.000	MI	675.50	675.50	700.00	
1040	619-A4002	Temporary Traffic Stripe, Skip Yellow, Paint	2,806.000	LF	0.29	0.30	0.30	

DESOTO (17)					Eutaw Construction Company, Inc.	James Construction Group, LLC	N. L. Carson Construction Company, Inc.	
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$62,375,386.01	\$65,156,542.64	\$66,543,672.56	
Ref#	SM Item	Item Description	Item Qty	Units	4	5	6	
1050	619-A5002	Temporary Traffic Stripe, Detail, Paint	51,880.000	LF	0.19	0.20	0.20	
1060	619-A5004	Temporary Traffic Stripe, Detail, Type 1 Tape	17,908.000	LF	1.45	1.45	1.50	
1070	619-A6003	Temporary Traffic Stripe, Legend, Paint	442.000	LF	0.97	1.00	1.00	
1080	619-A6004	Temporary Traffic Stripe, Legend, Paint	789.000	SF	1.45	1.45	1.50	
1090	619-C6001	Red-Clear Reflective High Performance Raised Marker	110.000	EA	4.83	5.00	5.00	
1100	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	2,653.000	EA	3.86	4.00	4.00	
1110	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	702.000	SF	5.79	6.00	6.00	
1120	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	682.000	SF	5.79	6.00	6.00	
1130	619-F1001	Concrete Median Barrier, Precast	1,890.000	LF	32.50	60.00	43.50	
1140	619-F2001	Remove and Reset Concrete Median Barrier, Precast	550.000	LF	7.71	2.70	15.00	
1150	619-G4001	Barricades, Type III, Single Faced	989.000	LF	13.51	14.00	14.00	
1160	619-G4004	Barricades, Type III, Single Faced, Permanent, Red/White	396.000	LF	24.13	25.00	25.00	
1170	619-G4005	Barricades, Type III, Double Faced	126.000	LF	15.44	16.00	16.00	
1180	619-G5001	Free Standing Plastic Drums	399.000	EA	30.88	32.00	32.00	
1190	619-G7001	Warning Lights, Type "B"	26.000	EA	168.88	175.00	175.00	
1200	620-A001	Mobilization	1.000	LS	5,200,000.00	5,575,000.00	6,493,745.00	
1210	621-A001	Field Laboratory	1.000	EA	20,000.00	50,000.00	25,000.00	
1220	627-K001	Red-Clear Reflective High Performance Raised Markers	110.000	EA	4.83	5.00	5.00	
1230	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	2,170.000	EA	3.86	4.00	4.00	
1240	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	20.000	SF	15.92	16.50	16.50	
1250	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	297.000	SF	16.89	17.50	17.50	
1260	630-C004	Steel U-Section Posts, 3.0 to 3.5 lb/ft	325.000	LF	7.24	7.50	7.50	
1270	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	152.000	LBS	0.97	1.00	1.00	
1280	630-F001	Delineators, Guard Rail, White	66.000	EA	12.55	13.00	13.00	
1290	630-G002	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	12.000	EA	53.08	55.00	55.00	
1300	630-K001	Welded & Seamless Steel Pipe Posts, 3"	15.000	LF	33.78	35.00	35.00	

DESOTO (17)					Eutaw Construction Company, Inc.	James Construction Group, LLC	N. L. Carson Construction Company, Inc.	
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$62,375,386.01	\$65,156,542.64	\$66,543,672.56	
Ref#	SM Item	Item Description	Item Qty	Units	4	5	6	
1310	630-K003	Welded & Seamless Steel Pipe Posts, 4"	107.000	LF	43.43	45.00	45.00	
1320	815-A006	Loose Riprap, Size 100	2,500.000	TON	43.00	40.00	39.00	
1330	815-A009	Loose Riprap, Size 300	34,010.000	TON	40.00	40.00	39.00	
1340	815-E001	Geotextile under Riprap	32,925.000	SY	2.80	1.40	2.17	
1350	815-F002	Sediment Control Stone	2,252.000	TON	29.54	33.60	29.00	
1360	907-225-A001	Grassing	570.000	ACRE	950.00	675.00	695.00	
1370	907-225-B001	Agricultural Limestone	1,601.000	TON	40.00	44.00	45.00	
1380	907-225-C001	Mulch, Vegetative Mulch	1,111.000	TON	80.00	150.00	155.00	
1390	907-226-A001	Temporary Grassing	570.000	ACRE	525.00	531.00	550.00	
1400	907-234-C002	Super Silt Fence	3,543.000	LF	8.00	7.25	7.50	
1410	907-234-D001	Inlet Siltation Guard	45.000	EA	550.00	425.00	440.00	
1420	907-234-F001	Turbidity Barrier	1,000.000	LF	10.00	22.00	15.00	
1430	907-237-A002	Wattles, 12"	4,000.000	LF	2.00	2.75	2.85	
1440	907-237-A003	Wattles, 20"	12,000.000	LF	2.95	4.00	4.15	
1450	907-245-A001	Triangular Silt Dike	7,500.000	LF	6.00	7.00	7.25	
1460	907-246-A001	Sandbags	3,600.000	LF	6.00	4.10	4.25	
1470	907-247-A001	Temporary Stream Diversion	7.000	EA	15,000.00	4,500.00	7,000.00	
1480	907-249-A001	Riprap for Erosion Control	500.000	TON	50.00	37.00	37.00	
1490	907-249-B001	Remove and Reset Riprap	500.000	CY	20.00	10.00	10.00	
1500	907-304-B009	Granular Material, Class 3, Group D	49,957.000	TON	8.00	14.57	14.80	
1510	907-304-C008	Granular Material, AEA, Class 9, Group B	52,765.000	CY	4.00	13.30	13.30	
1530	907-310-B001	Size III Stabilizer Aggregate, Coarse	100.000	TON	100.00	127.83	31.00	
1540	907-407-A001	Asphalt for Tack Coat	25,265.000	GAL	0.01	0.01	0.01	
1550	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	352.000	LF	15.07	15.00	15.00	
1560	907-601-A001	Class "B" Structural Concrete	1,849.000	CY	420.00	1,000.00	375.00	
1570	907-601-B003	Class "B" Structural Concrete, Minor Structures	68.000	CY	1,725.00	400.00	1,500.00	

DESOTO (17)					Eutaw Construction Company, Inc.	James Construction Group, LLC	N. L. Carson Construction Company, Inc.	
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$62,375,386.01	\$65,156,542.64	\$66,543,672.56	
Ref#	SM Item	Item Description	Item Qty	Units	4	5	6	
1580	907-603-ALT01	18" Type A Alternate Pipe	908.000	LF	19.43	20.00	20.00	
1590	907-603-ALT02	24" Type A Alternate Pipe	920.000	LF	26.67	25.00	25.00	
1600	907-605-O001	6" Perforated Sewer Pipe for Underdrains, SDR 23.5	2,500.000	LF	8.66	8.40	8.40	
1610	907-605-P001	6" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	100.000	LF	8.66	8.40	8.40	
1620	907-617-A001	Right-of-Way Marker	239.000	EA	130.00	154.00	200.00	
1630	907-619-E3001	Changeable Message Sign	5.000	EA	10,500.00	11,000.00	10,800.00	
1640	907-626-B003	6" Thermoplastic Traffic Stripe, Continuous White	1,856.000	LF	0.48	0.50	0.50	
1650	907-626-C008	6" Thermoplastic Edge Stripe, Continuous White	30,569.000	LF	0.48	0.50	0.50	
1660	907-626-D004	6" Thermoplastic Traffic Stripe, Skip Yellow	2,806.000	LF	0.24	0.25	0.25	
1670	907-626-E003	6" Thermoplastic Traffic Stripe, Continuous Yellow	17,118.000	LF	0.48	0.50	0.50	
1680	907-626-G004	Thermoplastic Detail Stripe, White	3,479.000	LF	1.21	1.25	1.25	
1690	907-626-G005	Thermoplastic Detail Stripe, Yellow	44,986.000	LF	0.97	1.00	1.00	
1700	907-626-H004	Thermoplastic Legend, White	442.000	LF	1.93	1.95	2.00	
1710	907-626-H005	Thermoplastic Legend, White	702.000	SF	5.79	5.80	6.00	
1720	907-630-O002	Remove and Reset Sign Assembly	1.000	EA	265.38	275.00	275.00	
1730	907-699-A002	Roadway Construction Stakes	1.000	LS	300,000.00	596,000.00	549,930.00	
1740	907-804-B001	Box Bridge Concrete, Class B	566.000	CY	372.00	700.00	434.00	
1750	907-906001	Trainees	2,080.000	HRS	5.00	5.00	5.00	
1760	907-308-A001	Portland Cement	713.000	TON	121.00	118.00	125.00	
1770	907-308-B002	Soil-Cement-Water Mixing, Optional Mixers, Design Soil	61,265.000	SY	1.10	1.20	1.10	
1780	907-308-S001	Bituminous Curing Seal	15,316.000	GAL	3.26	3.00	3.38	
1790	907-311-A003	Processing Lime and Fly Ash Treated Course, 6" Thick	61,265.000	SY				
1800	907-311-B001	Lime	472.000	TON				
1810	907-311-C002	Fly Ash, Class C or F	1,885.000	TON				
1820	907-311-S001	Bituminous Curing Seal	15,316.000	GAL				
1830	907-403-A006	Hot Mix Asphalt, MT, 12.5-mm mixture	5,034.000	TON	84.00	84.00	86.74	

DESOTO (17)					Eutaw Construction Company, Inc.	James Construction Group, LLC	N. L. Carson Construction Company, Inc.	
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$62,375,386.01	\$65,156,542.64	\$66,543,672.56	
Ref#	SM Item	Item Description	Item Qty	Units	4	5	6	
1840	907-403-M002	Warm Mix Asphalt, MT, 12.5-mm mixture	5,034.000	TON				
1850	907-403-A007	Hot Mix Asphalt, MT, 19-mm mixture	5,564.000	TON	74.50	75.00	76.89	
1860	907-403-M007	Warm Mix Asphalt, MT, 19-mm mixture	5,564.000	TON				
1870	907-403-A010	Hot Mix Asphalt, MT, 9.5-mm mixture	4,221.000	TON	85.50	86.00	88.62	
1880	907-403-M006	Warm Mix Asphalt, MT, 9.5-mm mixture	4,221.000	TON				
1890	907-403-A011	Hot Mix Asphalt, ST, 12.5-mm mixture	12,356.000	TON	84.75	85.00	87.74	
1900	907-403-M003	Warm Mix Asphalt, ST, 12.5-mm mixture	12,356.000	TON				
1910	907-403-A012	Hot Mix Asphalt, ST, 19-mm mixture	10,483.000	TON	74.25	74.50	76.89	
1920	907-403-M004	Warm Mix Asphalt, ST, 19-mm mixture	10,483.000	TON				
1930	907-403-A015	Hot Mix Asphalt, ST, 9.5-mm mixture	9,267.000	TON	85.90	86.00	89.00	
1940	907-403-M001	Warm Mix Asphalt, ST, 9.5-mm mixture	9,267.000	TON				
1950	907-626-J003	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous	2,540.000	LF				
1960	907-626-L001	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous	877.000	LF				
1970	907-626-M002	Inverted Profile Thermoplastic Detail Traffic Stripe, Yellow	4,922.000	LF				
1980	628-J002	6" High Performance Cold Plastic Traffic Stripe, Continuous	2,540.000	LF	4.83	5.00	5.00	
1990	628-M002	6" High Performance Cold Plastic Traffic Stripe, Continuous	877.000	LF	4.83	5.00	5.00	
2000	628-O002	High Performance Cold Plastic Detail Stripe, Yellow	4,922.000	LF	5.04	5.00	5.25	
2001	907-304-F002	Size 610 Crushed Stone Base	605.000	TON	35.00	30.00	31.00	
2002	907-304-F004	Size 825B Crushed Stone Base	605.000	TON				
2003	907-304-F003	3/4" and Down Crushed Stone Base	605.000	TON				
2010	501-K001	Transverse Grooving	33,370.000	SY	1.26	1.50	1.25	
2020	801-A001	Foundation Excavation for Bridges	3,384.000	CY	11.00	3.50	15.00	
2030	803-B002	Conventional Static Pile Load Test	11.000	EA	5,000.00	5,000.00	5,000.00	
2040	803-C002	14" x 14" Prestressed Concrete Piling	5,780.000	LF	35.00	58.00	36.00	
2050	803-C004	18" x 18" Prestressed Concrete Piling	12,980.000	LF	55.00	70.00	47.00	
2060	803-D007	HP 14 x 89 Steel Piling	46,965.000	LF	55.00	50.00	54.10	

DESOTO (17)					Eutaw Construction Company, Inc.	James Construction Group, LLC	N. L. Carson Construction Company, Inc.	
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$62,375,386.01	\$65,156,542.64	\$66,543,672.56	
Ref#	SM Item	Item Description	Item Qty	Units	4	5	6	
2070	803-F009	20" Pre-Formed Pile Hole	700.000	LF	10.00	20.00	25.00	
2080	803-I001	PDA Test Pile	36.000	EA	6,500.00	475.00	7,700.00	
2090	803-J001	Pile Restrike	11.000	EA	400.00	1,500.00	750.00	
2100	805-A001	Reinforcement	3,865,211.000	LBS	0.90	0.80	0.85	
2110	810-A003	Structural Steel, A 709, Grade 50	2,608,132.000	LBS	1.75	1.75	1.50	
2120	813-A002	Concrete Railing, 32"	11,301.000	LF	44.50	44.00	46.90	
2130	813-A003	Concrete Railing, 42"	1,549.000	LF	54.50	55.00	61.90	
2140	813-E001	Concrete Pedestrian Sidewalk Railing	744.000	LF	44.50	45.00	46.90	
2150	815-A009	Loose Riprap, Size 300	26,907.000	TON	40.00	40.00	39.00	
2160	815-D001	Concrete Slope Paving	727.000	CY	400.00	375.00	375.00	
2170	815-E001	Geotextile under Riprap	38,465.000	SY	2.50	1.40	2.17	
2180	907-803-K003	Drilled Shaft, 54" Diameter	660.000	LF	300.00	315.00	515.00	
2190	907-803-K005	Drilled Shaft, 66" Diameter	660.000	LF	330.00	400.00	690.00	
2200	907-803-K010	Drilled Shaft, 72" Diameter	2,316.000	LF	500.00	450.00	795.00	
2210	907-803-L001	Test Shaft, 66" Diameter	1.000	EA	145,000.00	143,000.00	170,500.00	
2220	907-803-L006	Test Shaft, 72" Diameter	1.000	EA	155,000.00	150,000.00	183,500.00	
2230	907-803-M004	Trial Shaft, 66" Diameter	73.000	LF	715.00	700.00	850.00	
2240	907-803-M008	Trial Shaft, 72" Diameter	78.000	LF	850.00	725.00	940.00	
2250	907-804-A001	Bridge Concrete, Class AA	17,985.000	CY	450.00	622.00	525.00	
2260	907-804-C011	130' Prestressed Concrete Beam, Type BT-72	2,076.000	LF	120.00	155.00	170.00	
2270	907-804-C016	40' Prestressed Concrete Beam, Type I+2	9,374.000	LF	65.00	75.00	130.00	
2280	907-804-C019	60' Prestressed Concrete Beam, Type II+2	3,322.000	LF	80.00	100.00	140.00	
2290	907-804-C021	70' Prestressed Concrete Beam, Type III	972.000	LF	90.00	110.00	150.00	
2300	907-804-C030	80' Prestressed Concrete Beam, Type III	2,538.000	LF	90.00	115.00	150.00	
2310	907-804-C145	50' Prestressed Concrete Beam, Type II + 2	1,385.000	LF	75.00	105.00	140.00	
2320	907-804-C146	88' Prestressed Concrete Beam, Type IV	612.000	LF	113.00	150.00	160.00	

DESOTO (17)					Eutaw Construction Company, Inc.	James Construction Group, LLC	N. L. Carson Construction Company, Inc.	
SR 304 Relocation/I-269 from STA. 240+00 (east of Malone Road) to Station 525+00 (east of SR 305), known as Federal Aid Project No. STP-0029-02(015) / 102556311 in Desoto County.					\$62,375,386.01	\$65,156,542.64	\$66,543,672.56	
Ref#	SM Item	Item Description	Item Qty	Units	4	5	6	
2330	907-804-C148	75' Prestressed Concrete Beam, Type IV	1,042.000	LF	113.00	150.00	160.00	
2340	907-804-C150	110' Prestressed Concrete Beam, Type IV	3,503.000	LF	113.00	150.00	160.00	
2350	907-804-C171	100' Prestressed Concrete Beam, Type IV	3,192.000	LF	113.00	145.00	160.00	
2360	907-804-C178	73' Prestressed Concrete Beam, Type IV	579.000	LF	113.00	145.00	160.00	
2370	907-804-C206	86' Prestressed Concrete Beam, Type IV	598.000	LF	113.00	150.00	160.00	
2380	907-804-C217	107' Prestressed Concrete Beam, Type IV	4,671.000	LF	110.00	150.00	160.00	
2390	907-804-C239	128' Prestressed Concrete Beam, Type BT-72	2,035.000	LF	118.00	175.00	170.00	
2400	907-804-C242	81' Prestressed Concrete Beam, Type IV	1,126.000	LF	113.00	150.00	160.00	
2410	907-804-C248	64' Prestressed Concrete Beam, Type BT-72	1,015.000	LF	118.00	175.00	170.00	
2420	907-804-C249	68' Prestressed Concrete Beam, Type BT-72	1,079.000	LF	118.00	175.00	170.00	
2430	907-804-C250	87' Prestressed Concrete Beam, Type IV	691.000	LF	111.00	150.00	160.00	
2440	907-804-C251	111' Prestressed Concrete Beam, Type IV	1,542.000	LF	111.00	150.00	160.00	
2450	907-811-D001	Disc Bearing Device	40.000	EA	6,000.00	5,000.00	4,800.00	