

Call 04 Chip Seal approximately 75 miles of Highway on various routes, known as State Project No. MP-3000-00(095) / 304787301 in District 3.

Q1. In reference to Line Items 0240 and 0250, are these items alternates? I presume so since they are identified as alternate items in the proposal though not in the specs. The three previous items are specifically identified as alternates in the specifications as well as in the proposal.

A1. Yes, they are alternate items.

Q2. On SR 16 in Issaquena County you have the GPS location of N 32.97474 W 90.94328 listed twice, is this a duplicate? If so, will these tons be placed, and where?

A2. Yes, the Department anticipates placing the tonnage estimated in the Contract.

Q3. 1. Paragraph 5 of the Scope of Work states that temporary stripe shall be placed daily. Is this referring to the Chip Seal Markers for which there is a pay item? 2. Is 4 inch width for the Cold Plastic correct? 3. What is the width of the High Build Traffic Stripe?

A3. 1. Yes 2. Yes 3. 4" (four-inch)

Q4. Are the GPS locations at the BOP/EOP or middle of the locations? If BOP or EOP in which directions will the work take place (north/south)?

A4. They are referenced from the approximate BOP.