

Call 04 Level and Seal approximately 8 miles of SR 4 from East of MLK Dr. to SR 371, known as State Project No. MP-1004-59(009) / 304803301 in Prentiss County.

- Q1. On sheet 3 note E of the plans it states that all stripe to be removed prior to seal. Will this removal have to be done or is the stripe already worn down enough for the seal to bond? Usually this removal does not have to be done in the past jobs we have bid.
- A1. Yes, existing striping must be removed prior to placement of the scrub seal. Payment for Removal of Stripe will be absorbed in other items bid.