

Call 13 Scrub Seal & Overlay approximately 9 miles of SR 21 from Newton County Line to south of Dixon and from Scott County Line to Neshoba County Line, known as State Project Nos. MP-5021-50(018) / 304808301 & MP-5021-51(001) / 304808302 in Neshoba & Newton Counties

Q1. Scope of work does not address any removal of asphalt for failed areas in the roadway. Is this item for the removal of asphalt pavement under guardrail?

A1. Yes

Q2. There is an item 808-A001 Joint Preparation. Is this on a bridge? If so would there also be repair of joint and sealing of joint?

A2. Yes, this is on a bridge. A pay item is provided (907-823-A002, Preformed Joint Seal, Type II).

Q3. The Scope of Work states that all thermoplastic pavement markings are to be removed prior to the scrub seal, and the methods of removal must be approved by the Engineer. Can stripe be removed with a motor grader?

A3. Yes, except on bridges and bridge approaches.