

Call 07 Overlay approximately 9 miles of SR 43 from Rankin County Line to Dinkins Street, known as State Project No. MP-5043-45(009) / 304807301 in Madison County.

- Q1. 1. Sheet 44 of the Scope of Work shows widening the left side 4' and installing 4" of Hot Mix Asphalt; will the excavation for the widening be paid under the excess pay item? 2. Is there room between the existing pavement and the Rip Rap to allow for the 4' of widening?
- A1. 1. Yes. 2. Yes
- Q2. On page 45 of the Scope of Work under Section: Guardrail Replacement it states that 12.5mm MT asphalt mix will be used for the trench widening, is this correct?
- A2. No, trench widening will be done with 19mm MT asphalt.
- Q3. Why do you have so much linear footage setup for sawing 3" and 4" on the bridge sealing?
- A3. The Saw Cut, 4-inch **will not** be used on the project, See Fax Letter dated 7-22-13.