

Call 12 Bridge Replacement on SR 309 between US 78 and Barton, known as Federal Aid Project No. BR-0914-00(007) / 100299301 in Marshall County.

- Q1. Reference Bid Item 830 803-I001 PDA TEST PILE: Proposal quantity = 10 ea Sheet 8002 Summary of Quantities = 10 ea Sheet 8003 Estimated Bridge Quantities = 10 ea Sheet 8004 PDA Test Pile Schedule count = 9 ea Sheet 8004 Estimated Bridge Quantities = 9 ea EBS file = 10 ea Please clarify.
- A1. See the addendum for this project.
- Q2. Note 16 states all clearing “underneath” the bridge must be done with saws. Note 17 states a haul road can be constructed within the 75’ working area allowed for bridge construction in the wetland area. Note 17 further states any clearing outside of this 75’ working area will have to be done with saws “only”. The haul road will have to be constructed and removed using mechanized equipment. Can a contractor clear (w/o grubbing) within the 75’ bridge working area with mechanized equipment and clear anything outside of this area with saws only?
- A2. Clearing in areas where a haul road is to be placed in wetland areas may be done with mechanized equipment. All other clearing in wetland areas is to be done with saws only. Clearing must be addressed in the Contractor’s Erosion Control Plan.
- Q3. Is it acceptable to submit (1) one signed copy of Form OCR-485 as a cover sheet to represent software generated attachments that have the information required by form OCR-485 on them?
- A3. Reference NTB 4103 Supplement: “OCR-485: Bidder must submit **signed form with bid proposal** of all firms that submitted quotes for material supplies or items to be subcontracted. Please make and add copies of this form when needed or attach additional sheets containing the information required by the form and add these sheets to the bid proposal. If at least one copy of this form is not signed and included as part of bid proposal, your bid will be deemed irregular.” Also repeated in NTB 4488.” Bidders are also advised that Form OCR-485 will be completed by **ALL BIDDERS** submitting a bid proposal and **must be signed and included in the bid proposal package**. If at least one copy of this form is not signed and included as part of bid proposal, your bid will be deemed irregular.”
- Q4. Pay Item 815-A004 Loose RipRap, size 300 Proposal & EBS file shows unit of measure as “SY.” All of the tables in the plans show “TON” Please clarify.
- A4. Reference the fax letter for this project dated 1-24-14.