

Call 16 Overlay approximately 6 miles of SR 27 from I-55 to Hinds County Line, known as State Project No. MP-3027-15(007) / 305096301 in Copiah County.

Q1. Will the contractor be required to pave behind guardrail on this project?

A1. No

Q2. Per current MDOT ride specifications how is the contractor to account for existing rumble strip at the centerline of roadway?

A2. Smoothness testing will be conducted in the wheel paths.

Q3. **1)** Will any work be required on the centerline rumble strip prior to overlaying the roadway? **2)** The proposal states that side roads and driveway pads will be paid for as leveling. Will any other leveling be performed on the project? If so where? **3)** Will asphalt be placed underneath the guardrails on the project?

A3. **1)** No **2)** Required leveling as of today, outside of the side roads and driveway pads are STA 148+50 to STA 163+00, STA 175+00 to STA 180+00, and STA 215+00 to STA 228+50 , additional areas may be added if conditions dictate. **3)** No