

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) further propose to execute the attached contract agreement (Section 902) as soon as the work is awarded to me (us), and to begin and complete the work within the time limit(s) provided for in the Specifications and Advertisement. I (We) also propose to execute the attached contract bond (Section 903) in an amount not less than one hundred (100) percent of the total of my (our) part, but also to guarantee the excellence of both workmanship and materials until the work is finally accepted.

I (We) enclose a certified check, cashier's check or bid bond for **five percent (5%) of total bid** and hereby agree that in case of my (our) failure to execute the contract and furnish bond within Ten (10) days after notice of award, the amount of this check (bid bond) will be forfeited to the State of Mississippi as liquidated damages arising out of my (our) failure to execute the contract as proposed. It is understood that in case I am (we are) not awarded the work, the check will be returned as provided in the Specifications.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. 1 DATED 2/18/2014 ADDENDUM NO. DATED
ADDENDUM NO. DATED ADDENDUM NO. DATED

Number	Description
1	Revise Bid Items, replace same; Amendment EBS Download Required.

TOTAL ADDENDA: 1
(Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

Contractor

BY _____
Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

_____ President	_____ Address
_____ Secretary	_____ Address
_____ Treasurer	_____ Address

The following is my (our) itemized proposal.

IM-0059-02(104) / 106408302 Jasper County(ies)

Revised 09/21/2005

Mill & Overlay approximately 13 miles of I-59 from Jones County Line to Vossburg, known as Federal Aid Project No. IM-0059-02(104) / 106408302 in Jasper County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
Roadway Items					
0010	202-B005		478	Square Yard	Removal of Asphalt Pavement, All Depths
0020	202-B013		259	Square Yard	Removal of Cement Treated Base, All Depths
0030	202-B025		86	Square Yard	Removal of Concrete Paved Ditch
0040	202-B042		10	Each	Removal of Flared End Section, All Sizes
0050	202-B064		24	Linear Feet	Removal of Pipe, 8" And Above
0060	202-B076		9,180	Linear Feet	Removal of Traffic Stripe
0070	202-B081		259	Square Yard	Removal of Continuously Reinforced Concrete Pavement, 8-inch Depth
0080	202-B102		7,038	Linear Feet	Removal of Guard Rail
0090	202-B262		181	Square Yard	Removal of Reinforced Concrete Pavement, 8" Depth
0100	202-B298		202	Linear Feet	Removal of Existing Joint Material
0110	203-EX014	(E)	100	Cubic Yard	Borrow Excavation, AH, LVM, Class B7
0120	206-A001	(S)	8	Cubic Yard	Structure Excavation
0130	221-A001	(S)	135	Cubic Yard	Portland Cement Concrete Paved Ditch
0140	406-A001		20,157	Square Yard	Cold Milling of Bituminous Pavement, All Depths
0150	406-B001		560	Square Yard	Cold Milling of Concrete Pavement, All Depths
0160	413-B001		1,974	Linear Feet	Cleaning and Sealing Joints
0170	413-D001		288	Linear Feet	Cleaning and Filling Joints
0180	423-A001		51	Mile	Rumble Strips, Ground In
0190	501-D001		108	Linear Feet	Expansion Joints, With Dowels
0200	501-G001		66	Each	Dowels, Drilled and Installed
0210	501-I001		108	Linear Feet	Joint Filler, Wooden Board
0220	503-B001		230	Linear Feet	Saw Cut, Longitudinal Joints
0230	503-C002		1,858	Linear Feet	Saw Cut, 3-inch
0240	503-C005		1,228	Linear Feet	Saw Cut, 8-inch
0250	503-D001		46	Cubic Yard	Concrete for Base Repair
0260	503-E002		131	Each	Tie Bars, No. 5 Deformed Drilled and Epoxied or Grouted
0270	603-CA088	(S)	24	Linear Feet	18" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets
0280	603-CB001	(S)	4	Each	18" Reinforced Concrete End Section
0290	603-CB002	(S)	5	Each	24" Reinforced Concrete End Section
0300	603-CB003	(S)	1	Each	30" Reinforced Concrete End Section
0310	603-RA003	(S)	16	Linear Feet	24" Pipe Removed and Relaid
0320	603-RB003	(S)	2	Each	24" End Section Removed and Relaid

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0330	606-B005		5,711	Linear Feet	Guard Rail, Class A, Type 1, 'W' Beam
0340	606-C002		16	Each	Guard Rail, Cable Anchor Type 1, Metal Post
0350	606-D001		4	Each	Guard Rail, Bridge End Section, Type A
0360	606-E002		48	Each	Guard Rail, Terminal End Section, Flared
0370	615-A012	(S)	202	Linear Feet	Concrete Type IV Modified, 42" Height, Cast-in-Place Median Barrier
0380	618-A001		1	Lump Sum	Maintenance of Traffic
0390	619-A1002		52	Mile	Temporary Traffic Stripe, Continuous White
0400	619-A2002		52	Mile	Temporary Traffic Stripe, Continuous Yellow
0410	619-A3006		52	Mile	Temporary Traffic Stripe, Skip White
0420	619-A5001		1,408	Linear Feet	Temporary Traffic Stripe, Detail
0430	619-D1001		104	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet
0440	619-D2001		304	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More
0450	619-G4001		48	Linear Feet	Barricades, Type III, Single Faced
0460	620-A001		1	Lump Sum	Mobilization
0470	627-K001		2,197	Each	Red-Clear Reflective High Performance Raised Markers
0480	627-L001		105	Each	Two-Way Yellow Reflective High Performance Raised Markers
0490	630-F001		186	Each	Delineators, Guard Rail, White
0500	630-F002		52	Each	Delineators, Guard Rail, Yellow
0510	630-G002		24	Each	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted
0520	808-A001	(S)	630	Linear Feet	Joint Preparation
0530	907-216-A001		350	Square Yard	Solid Sodding
0540	907-237-A003		1,000	Linear Feet	Wattles, 20"
0550	907-402-A004	(BA1)	19,962	Ton	Open Graded Friction Course, 9.5-mm Mixture
0560	907-402-B001	(A3)	31,686	Gallon	Bituminous Tack Coat
0570	907-403-AA001	(BA1)	33,208	Ton	Stone Matrix Asphalt, 9.5 mm Mixture
0580	907-403-AA002	(BA1)	44,277	Ton	Stone Matrix Asphalt, 12.5 mm Mixture
0590	907-403-S004		51	Mile	Joint Sealant
0600	907-407-A001	(A2)	58,205	Gallon	Asphalt for Tack Coat
0610	907-413-E001		288	Linear Feet	Sawing and Sealing Transverse Joints in Asphalt Pavement
0620	907-503-A002	(C)	259	Square Yard	8" and Variable Continuously Reinforced Concrete Pavement, Broom Finish
0630	907-503-A003	(C)	149	Square Yard	8" and Variable Jointed Concrete Pavement
0640	907-601-B003	(S)	4	Cubic Yard	Class "B" Structural Concrete, Minor Structures
0650	907-626-A003		26	Mile	6" Thermoplastic Traffic Stripe, Skip White
0660	907-626-C003		26	Mile	6" Thermoplastic Double Drop Edge Stripe, Continuous White
0670	907-626-E003		7,283	Linear Feet	6" Thermoplastic Traffic Stripe, Continuous Yellow

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0680	907-626-F003		26	Mile	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow
0690	907-626-G004		596	Linear Feet	Thermoplastic Detail Stripe, White
0700	907-626-G005		812	Linear Feet	Thermoplastic Detail Stripe, Yellow
0710	907-626-H004		815	Linear Feet	Thermoplastic Legend, White
0720	907-823-A001		378	Linear Feet	Preformed Joint Seal, Type I
0730	907-906001		1,040	Hours	Trainees [\$5.00]
Changed 02/18/2014					
ALTERNATE GROUP AA NUMBER 1					
0740	907-304-F002	(GT)	19,220	Ton	Size 610 Crushed Stone Base
ALTERNATE GROUP AA NUMBER 2					
0750	907-304-F003	(GT)	19,220	Ton	3/4" and Down Crushed Stone Base
ALTERNATE GROUP AA NUMBER 3					
0760	907-304-F004	(GT)	19,220	Ton	Size 825B Crushed Stone Base
ALTERNATE GROUP BB NUMBER 1					
0770	907-403-A015	(BA1)	31,164	Ton	Hot Mix Asphalt, ST, 9.5-mm mixture
ALTERNATE GROUP BB NUMBER 2					
0780	907-403-M001	(BA1)	31,164	Ton	Warm Mix Asphalt, ST, 9.5-mm mixture
ALTERNATE GROUP CC NUMBER 1					
0790	907-403-A001	(BA1)	1,973	Ton	Hot Mix Asphalt, HT, 12.5-mm mixture
ALTERNATE GROUP CC NUMBER 2					
0800	907-403-M010	(BA1)	1,973	Ton	Warm Mix Asphalt, HT, 12.5-mm mixture