

JASPER (31)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Dunn Roadbuilders, LLC		
Mill & Overlay approximately 13 miles of I-59 from Jones County Line to Vossburg, known as Federal Aid Project No. IM-0059-02(104) / 106408302 in Jasper County.					\$15,155,630.80	\$16,595,716.50		
Ref#	SM Item	Item Description	Item Qty	Units		1		
0010	202-B005	Removal of Asphalt Pavement, All Depths	478.000	SY		35.00		
0020	202-B013	Removal of Cement Treated Base, All Depths	259.000	SY		8.00		
0030	202-B025	Removal of Concrete Paved Ditch	86.000	SY		6.50		
0040	202-B042	Removal of Flared End Section, All Sizes	10.000	EA		161.00		
0050	202-B064	Removal of Pipe, 8" And Above	24.000	LF		16.00		
0060	202-B076	Removal of Traffic Stripe	9,180.000	LF		1.10		
0070	202-B081	Removal of Continuously Reinforced Concrete Pavement, 8-inch	259.000	SY		130.00		
0080	202-B102	Removal of Guard Rail	7,038.000	LF		4.00		
0090	202-B262	Removal of Reinforced Concrete Pavement, 8" Depth	181.000	SY		69.00		
0100	202-B298	Removal of Existing Joint Material	202.000	LF		54.00		
0110	203-EX014	Borrow Excavation, AH, LVM, Class B7	100.000	CY		45.00		
0120	206-A001	Structure Excavation	8.000	CY		22.00		
0130	221-A001	Portland Cement Concrete Paved Ditch	135.000	CY		401.00		
0140	406-A001	Cold Milling of Bituminous Pavement, All Depths	20,157.000	SY		6.50		
0150	406-B001	Cold Milling of Concrete Pavement, All Depths	560.000	SY		35.00		
0160	413-B001	Cleaning and Sealing Joints	1,974.000	LF		6.00		
0170	413-D001	Cleaning and Filling Joints	288.000	LF		11.00		
0180	423-A001	Rumble Strips, Ground In	51.000	MI		268.00		
0190	501-D001	Expansion Joints, With Dowels	108.000	LF		26.00		
0200	501-G001	Dowels, Drilled and Installed	66.000	EA		18.00		
0210	501-I001	Joint Filler, Wooden Board	108.000	LF		24.00		
0220	503-B001	Saw Cut, Longitudinal Joints	230.000	LF		11.00		
0230	503-C002	Saw Cut, 3-inch	1,858.000	LF		6.00		
0240	503-C005	Saw Cut, 8-inch	1,228.000	LF		11.00		
0250	503-D001	Concrete for Base Repair	46.000	CY		236.00		
0260	503-E002	Tie Bars, No. 5 Deformed Drilled and Epoxied or Grouted	131.000	EA		11.00		

JASPER (31)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Dunn Roadbuilders, LLC		
Mill & Overlay approximately 13 miles of I-59 from Jones County Line to Vossburg, known as Federal Aid Project No. IM-0059-02(104) / 106408302 in Jasper County.					\$15,155,630.80	\$16,595,716.50		
Ref#	SM Item	Item Description	Item Qty	Units		1		
0270	603-CA088	18" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	24.000	LF		49.00		
0280	603-CB001	18" Reinforced Concrete End Section	4.000	EA		749.00		
0290	603-CB002	24" Reinforced Concrete End Section	5.000	EA		776.00		
0300	603-CB003	30" Reinforced Concrete End Section	1.000	EA		803.00		
0310	603-RA003	24" Pipe Removed and Relaid	16.000	LF		38.00		
0320	603-RB003	24" End Section Removed and Relaid	2.000	EA		428.00		
0330	606-B005	Guard Rail, Class A, Type 1, 'W' Beam	5,711.000	LF		20.00		
0340	606-C002	Guard Rail, Cable Anchor Type 1, Metal Post	16.000	EA		910.00		
0350	606-D001	Guard Rail, Bridge End Section, Type A	4.000	EA		1,659.00		
0360	606-E002	Guard Rail, Terminal End Section, Flared	48.000	EA		2,140.00		
0370	615-A012	Concrete Type IV Modified, 42" Height, Cast-in-Place Median	202.000	LF		241.00		
0380	618-A001	Maintenance of Traffic	1.000	LS		140,000.00		
0390	619-A1002	Temporary Traffic Stripe, Continuous White	52.000	MI		321.00		
0400	619-A2002	Temporary Traffic Stripe, Continuous Yellow	52.000	MI		321.00		
0410	619-A3006	Temporary Traffic Stripe, Skip White	52.000	MI		321.00		
0420	619-A5001	Temporary Traffic Stripe, Detail	1,408.000	LF		1.00		
0430	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Fe	104.000	SF		18.00		
0440	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	304.000	SF		18.00		
0450	619-G4001	Barricades, Type III, Single Faced	48.000	LF		19.00		
0460	620-A001	Mobilization	1.000	LS		440,000.00		
0470	627-K001	Red-Clear Reflective High Performance Raised Markers	2,197.000	EA		5.00		
0480	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	105.000	EA		5.00		
0490	630-F001	Delineators, Guard Rail, White	186.000	EA		20.00		
0500	630-F002	Delineators, Guard Rail, Yellow	52.000	EA		20.00		
0510	630-G002	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	24.000	EA		81.00		
0520	808-A001	Joint Preparation	630.000	LF		32.00		

JASPER (31)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Dunn Roadbuilders, LLC		
Mill & Overlay approximately 13 miles of I-59 from Jones County Line to Vossburg, known as Federal Aid Project No. IM-0059-02(104) / 106408302 in Jasper County.					\$15,155,630.80	\$16,595,716.50		
Ref#	SM Item	Item Description	Item Qty	Units		1		
0530	907-216-A001	Solid Sodding	350.000	SY		11.00		
0540	907-237-A003	Wattles, 20"	1,000.000	LF		3.20		
0550	907-402-A004	Open Graded Friction Course, 9.5-mm Mixture	19,962.000	TON		114.50		
0560	907-402-B001	Bituminous Tack Coat	31,686.000	GAL		8.50		
0570	907-403-AA001	Stone Matrix Asphalt, 9.5 mm Mixture	33,208.000	TON		109.50		
0580	907-403-AA002	Stone Matrix Asphalt, 12.5 mm Mixture	44,277.000	TON		107.00		
0590	907-403-S004	Joint Sealant	51.000	MI		1,391.00		
0600	907-407-A001	Asphalt for Tack Coat	58,205.000	GAL		5.00		
0610	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	288.000	LF		6.00		
0620	907-503-A002	8" and Variable Continuously Reinforced Concrete Pavement,	259.000	SY		160.00		
0630	907-503-A003	8" and Variable Jointed Concrete Pavement	149.000	SY		160.00		
0640	907-601-B003	Class "B" Structural Concrete, Minor Structures	4.000	CY		2,247.00		
0650	907-626-A003	6" Thermoplastic Traffic Stripe, Skip White	26.000	MI		1,070.00		
0660	907-626-C003	6" Thermoplastic Double Drop Edge Stripe, Continuous White	26.000	MI		2,033.00		
0670	907-626-E003	6" Thermoplastic Traffic Stripe, Continuous Yellow	7,283.000	LF		1.00		
0680	907-626-F003	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	26.000	MI		2,033.00		
0690	907-626-G004	Thermoplastic Detail Stripe, White	596.000	LF		1.00		
0700	907-626-G005	Thermoplastic Detail Stripe, Yellow	812.000	LF		1.00		
0710	907-626-H004	Thermoplastic Legend, White	815.000	LF		1.00		
0720	907-823-A001	Preformed Joint Seal, Type I	378.000	LF		43.00		
0730	907-906001	Trainees	1,040.000	HRS		5.00		
0740	907-304-F002	Size 610 Crushed Stone Base	19,220.000	TON				
0750	907-304-F003	3/4" and Down Crushed Stone Base	19,220.000	TON				
0760	907-304-F004	Size 825B Crushed Stone Base	19,220.000	TON		41.00		
0770	907-403-A015	Hot Mix Asphalt, ST, 9.5-mm mixture	31,164.000	TON				
0780	907-403-M001	Warm Mix Asphalt, ST, 9.5-mm mixture	31,164.000	TON		86.00		

JASPER (31)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	Dunn Roadbuilders, LLC		
Mill & Overlay approximately 13 miles of I-59 from Jones County Line to Vossburg, known as Federal Aid Project No. IM-0059-02(104) / 106408302 in Jasper County.					\$15,155,630.80	\$16,595,716.50		
Ref#	SM Item	Item Description	Item Qty	Units		1		
0790	907-403-A001	Hot Mix Asphalt, HT, 12.5-mm mixture	1,973.000	TON				
0800	907-403-M010	Warm Mix Asphalt, HT, 12.5-mm mixture	1,973.000	TON		108.00		