

Call 18 Lot Improvement at District 1 Headquarters in Tupelo, known as State Project No. LWO-1033-41(005) / 501637302 in Lee County

Q1. When do you expect to have asphalt and stone base quantities revised?

A1. An addendum will be posted with the revised quantities.

Q2. (1) On sheet 1002 in reference notes section, symbol 32-01 references hid card reader, with no reference to controller only that the reader needs to be within 500', is there existing automation? (2) How many cards are needed? (3) Do they want tracking capabilities on the cards?

A2. (1) The Controller is in the Commissioner's Office. The Contractor will be required to pull the wire for the reader and MDOT will make the final tie in. (2) The Contractor will not have to supply the cards. (3) The Contractor will not have to supply the cards

Q3. Do you want to use dry pack or wet pour for all the precast concrete on working number HS-4?

A3. We want to use the dry pack precast application, to match the existing stone veneer on the building.