

**SECTION 905 -- PROPOSAL (CONTINUED)**

I (We) further propose to execute the attached contract agreement (Section 902) as soon as the work is awarded to me (us), and to begin and complete the work within the time limit(s) provided for in the Specifications and Advertisement. I (We) also propose to execute the attached contract bond (Section 903) in an amount not less than one hundred (100) percent of the total of my (our) part, but also to guarantee the excellence of both workmanship and materials until the work is finally accepted.

I (We) enclose a certified check, cashier's check or bid bond for **five percent (5%) of total bid** and hereby agree that in case of my (our) failure to execute the contract and furnish bond within Ten (10) days after notice of award, the amount of this check (bid bond) will be forfeited to the State of Mississippi as liquidated damages arising out of my (our) failure to execute the contract as proposed. It is understood that in case I am (we are) not awarded the work, the check will be returned as provided in the Specifications.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO.   1   DATED   4/2/2014   ADDENDUM NO.        DATED         
ADDENDUM NO.        DATED        ADDENDUM NO.        DATED       

Number	Description
1	Revise Bid Items; Amendment EBS Download Required.

TOTAL ADDENDA:   1    
(Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE \_\_\_\_\_

\_\_\_\_\_  
Contractor

BY \_\_\_\_\_  
Signature

TITLE \_\_\_\_\_

ADDRESS \_\_\_\_\_

CITY, STATE, ZIP \_\_\_\_\_

PHONE \_\_\_\_\_

FAX \_\_\_\_\_

E-MAIL \_\_\_\_\_

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of \_\_\_\_\_ and the names, titles and business addresses of the executives are as follows:

_____ President	_____ Address
_____ Secretary	_____ Address
_____ Treasurer	_____ Address

The following is my (our) itemized proposal.

IM-0020-01(212) / 106651301 & 302      Hinds County(ies)

Revised 09/21/2005

Mill & Overlay, Bridge Repair, & Landscaping approximately 7 miles of I-20 from Natchez Trace to SR 18, known as Federal Aid Project No. IM-0020-01(212) / 106651301 & 302 in Hinds County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
					<b>Roadway Items</b>
0010	201-D001		408	Station	Random Clearing
0020	202-B005		7,769	Square Yard	Removal of Asphalt Pavement, All Depths
0030	202-B021		6	Each	Removal of Concrete Lug Anchor
0040	202-B022		3,758	Linear Feet	Removal of Concrete Median Barrier
0050	202-B025		26	Square Yard	Removal of Concrete Paved Ditch
0060	202-B030		11,350	Square Yard	Removal of Concrete Pavement, All Depths
0070	202-B041		622	Linear Feet	Removal of Fence, All Types
0080	202-B064		1,000	Linear Feet	Removal of Pipe, 8" And Above
0090	202-B069		4	Each	Removal of Sign
0100	202-B076		4,920	Linear Feet	Removal of Traffic Stripe
0110	202-B087		3,038	Linear Feet	Removal of Guard Rail, Including Rails, Posts and Terminal Ends
0120	202-B114		14	Each	Removal of Tree Less Than 10"
0130	203-EX040	(E)	5,925	Cubic Yard	Borrow Excavation, AH, LVM, Class B9-6
0140	203-G003	(E)	24,039	Cubic Yard	Excess Excavation, FM, AH
0150	204-A003		16,000	Square Yard	Geogrid, Type II, Biaxial
0160	209-A004		3,091	Square Yard	Geotextile Stabilization, Type V, Non-Woven
0170	209-A007		22,245	Square Yard	Geotextile Stabilization, Type VII, Non-Woven
0180	211-C001	(E)	263	Cubic Yard	Topsoil for Plant Holes, Contractor Furnished
0190	213-B001		1	Ton	Combination Fertilizer, 13-13-13
0200	213-B002		1	Ton	Combination Fertilizer, 8-8-8
0210	213-C001		2	Ton	Superphosphate
0220	220-A001		2	Acre	Insect Pest Control [\$30.00]
0230	221-A001	(S)	8	Cubic Yard	Portland Cement Concrete Paved Ditch
0240	223-A001		4	Acre	Mowing [\$50.00]
0250	232-A002		2	Thousand	Fertilizer for Woody Plant Material, Tablet, 21 gram
0260	232-A003		8	Thousand	Fertilizer for Woody Plant Material, Tablet, 10 gram
0270	234-A001		3,037	Linear Feet	Temporary Silt Fence
0280	406-A001		3,637	Square Yard	Cold Milling of Bituminous Pavement, All Depths
0290	406-A003		29,890	Ton	Cold Milling of Bituminous Pavement, All Depths
0300	423-A001		25	Mile	Rumble Strips, Ground In
0310	501-E001		111	Linear Feet	Expansion Joints, Without Dowels
0320	501-F001		80	Linear Feet	Concrete Lug Anchors

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0330	501-K001		216	Square Yard	Transverse Grooving
0340	503-B001		604	Linear Feet	Saw Cut, Longitudinal Joints
0350	503-C002		474	Linear Feet	Saw Cut, 3-inch
0360	503-C007		630	Linear Feet	Saw Cut, Full Depth
0370	503-D001		39	Cubic Yard	Concrete for Base Repair
0380	503-E002		151	Each	Tie Bars, No. 5 Deformed Drilled and Epoxied or Grouted
0390	512-A001		966	Each	Holes
0400	603-A006	(S)	605	Linear Feet	6" Steel Pipe, Jacked or Bored, Wall Thickness 0.250"
0410	603-CE003	(S)	240	Linear Feet	36" x 23" Concrete Arch Pipe, Class A III
0420	603-CF003	(S)	1	Each	36" x 23" Concrete Arch Pipe End Section
0430	606-B001		3,438	Linear Feet	Guard Rail, Class A, Type 1
0440	606-C003		8	Each	Guard Rail, Cable Anchor, Type 1
0450	606-D003		6	Each	Guard Rail, Bridge End Section, Type D Modified
0460	606-D004		4	Each	Guard Rail, Bridge End Section, Type E
0470	606-D012		1	Each	Guard Rail, Bridge End Section, Type I
0480	606-E001		18	Each	Guard Rail, Terminal End Section
0490	607-B002		622	Linear Feet	60" Type II Chain Link Fence, Class I
0500	607-G132		1	Each	Gate, 3' x 60" Chain Link
0510	607-P1007		63	Each	Line Post, 7' x 1 1/2" Galvanized Steel
0520	607-P2008		9	Each	Brace Post, 7 1/2' x 2" Galvanized Steel
0530	607-P2017		1	Each	Brace Post, 5' x 2 1/2" Galvanized Steel
0540	607-P3003		2	Each	Gate Post, 8' x 2 1/2" Galvanized Steel
0550	618-A001		1	Lump Sum	Maintenance of Traffic
0560	619-A1002		45	Mile	Temporary Traffic Stripe, Continuous White
0570	619-A2002		46	Mile	Temporary Traffic Stripe, Continuous Yellow
0580	619-A3006		17	Mile	Temporary Traffic Stripe, Skip White
0590	619-A5002		3,845	Linear Feet	Temporary Traffic Stripe, Detail, Paint
0600	619-A6003		1,348	Linear Feet	Temporary Traffic Stripe, Legend, Paint
0610	619-C6001		2,254	Each	Red-Clear Reflective High Performance Raised Marker
0620	619-C7001		118	Each	Two-Way Yellow Reflective High Performance Raised Marker
0630	619-D1001		230	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet
0640	619-D2001		719	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More
0650	619-F1001		9,700	Linear Feet	Concrete Median Barrier, Precast
0660	619-F2001		12,100	Linear Feet	Remove and Reset Concrete Median Barrier, Precast
0670	619-G4001		66	Linear Feet	Barricades, Type III, Single Faced

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0680	619-G4005		72	Linear Feet	Barricades, Type III, Double Faced
0690	619-G5001		138	Each	Free Standing Plastic Drums
0700	619-G7001		10	Each	Warning Lights, Type "B"
0710	619-J1003		3	Unit	Impact Attenuator, 60 MPH
0720	619-J2002		1	Unit	Impact Attenuator, 60 MPH, Replacement Package
0730	620-A001		1	Lump Sum	Mobilization
0740	627-K001		2,884	Each	Red-Clear Reflective High Performance Raised Markers
0750	627-L001		206	Each	Two-Way Yellow Reflective High Performance Raised Markers
0760	630-F001		79	Each	Delineators, Guard Rail, White
0770	630-F002		82	Each	Delineators, Guard Rail, Yellow
0780	635-A001		786	Linear Feet	Vehicle Loop Assemblies
0790	815-A007	(S )	46	Ton	Loose Riprap, Size 150
0800	815-A009	(S )	141	Ton	Loose Riprap, Size 300
0810	907-216-B004		1,000	Square Yard	Solid Sodding, Bermuda
0820	907-225-A001		4	Acre	Grassing
0830	907-225-B001		12	Ton	Agricultural Limestone
0840	907-225-C001		8	Ton	Mulch, Vegetative Mulch
0850	907-226-A001		4	Acre	Temporary Grassing
0860	907-230-A135		620	Each	Shrub Planting, Elaeagnus
0870	907-230-A136		1,380	Each	Shrub Planting, Pfitzer Juniper
0880	907-230-B026		40	Each	Tree Planting, Nutall Oak
0890	907-230-B044		350	Each	Tree Planting, Crape Myrtle 'Natchez'
0900	907-230-B050		150	Each	Tree Planting, Bracken's Southern Magnolia
0910	907-230-B102		180	Each	Tree Planting, Columnar Tulip Poplar
0920	907-230-B103		52	Each	Tree Planting, Green Giant Western Cedar
0930	907-233-A001		164	Cubic Yard	Tree Bark Mulch, Type III
0940	907-233-A002		1,619	Cubic Yard	Tree Bark Mulch, Type V
0950	907-237-A003		4,000	Linear Feet	Wattles, 20"
0960	907-245-A001		945	Linear Feet	Triangular Silt Dike
0970	907-246-A001		945	Linear Feet	Sandbags
0980	907-249-A001		189	Ton	Riprap for Erosion Control
0990	907-282-A004		14	Each	Sprinkler Head, 1812-PRS-15EST
1000	907-282-A006		343	Each	Sprinkler Head, 1812-PRS-15CST
1010	907-282-A065		26	Each	Sprinkler Head, 1812-PRS-R-Van 1724
1020	907-282-A066		93	Each	Sprinkler Head, 5012-PL-FC-R

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
1030	907-282-A067		68	Each	Sprinkler Head, 5012-PL-PC-R
1040	907-282-B001		2,484	Linear Feet	Piping, 1/2" Diameter
1050	907-282-B002		3,264	Linear Feet	Piping, 3/4" Diameter
1060	907-282-B003		3,600	Linear Feet	Piping, 1" Diameter
1070	907-282-B004		1,825	Linear Feet	Piping, 1 1/4" Diameter
1080	907-282-B005		356	Linear Feet	Piping, 1 1/2" Diameter
1090	907-282-B006		334	Linear Feet	Piping, 2" Diameter
1100	907-282-B008		7,137	Linear Feet	Piping, 3" Diameter
1110	907-282-D001		55,517	Linear Feet	Valve Control Wire
1120	907-282-E001		18,450	Linear Feet	Trench Excavation and Backfill
1130	907-282-F001		1	Each	Meter with Meter Box, 2"
1140	907-282-G002		1	Each	Electric Controller, 24 Station
1150	907-282-H001		3	Each	Electric Control Valve, 1"
1160	907-282-H002		10	Each	Electric Control Valve, 1 1/2"
1170	907-282-H003		10	Each	Electric Control Valve, 2"
1180	907-282-I004		1	Each	Backflow Preventer, 3"
1190	907-282-J002		8	Each	Isolation Valve, 3"
1200	907-282-K001		4	Each	Quick Coupler Key with Hose and Swivel
1210	907-304-B005	(GT )	484	Ton	Granular Material, Class 9, Group C
1220	907-304-B007	(GT )	22,649	Ton	Granular Material, Class 5, Group E
1230	907-403-S004		25	Mile	Joint Sealant
1240	907-407-A001	(A2 )	26,500	Gallon	Asphalt for Tack Coat
1250	907-503-A002	(C )	468	Square Yard	8" and Variable Continuously Reinforced Concrete Pavement, Broom Finish
1260	907-512-B001		96,600	Pounds	Portland Cement Pressure Grout Slurry, Type 1
1270	907-619-E3001		4	Each	Changeable Message Sign
1280	907-619-J3001		5	Each	Remove and Reset Impact Attenuator
1290	907-626-A006		80,225	Linear Feet	6" Thermoplastic Double Drop Traffic Stripe, Skip White
1300	907-626-C007		81,327	Linear Feet	6" Thermoplastic Double Drop Edge Stripe, Continuous White
1310	907-626-E005		4,060	Linear Feet	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow
1320	907-626-F005		78,799	Linear Feet	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow
1330	907-626-G006		39,351	Linear Feet	Thermoplastic Double Drop Detail Stripe, White
1340	907-626-G007		363	Linear Feet	Thermoplastic Double Drop Detail Stripe, Yellow
1350	907-626-H009		684	Linear Feet	Thermoplastic Double Drop Legend, White
1360	907-626-H010		608	Square Feet	Thermoplastic Double Drop Legend, White
1370	907-699-A002		1	Lump Sum	Roadway Construction Stakes

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
1380	907-906001		1,040	Hours	Trainees [\$5.00] <b>ALTERNATE GROUP AA NUMBER 1</b>
1390	907-304-F002	(GT )	26,132	Ton	Size 610 Crushed Stone Base <b>ALTERNATE GROUP AA NUMBER 2</b>
1400	907-304-F003	(GT )	26,132	Ton	3/4" and Down Crushed Stone Base <b>ALTERNATE GROUP AA NUMBER 3</b>
1410	907-304-F004	(GT )	26,132	Ton	Size 825B Crushed Stone Base <b>ALTERNATE GROUP BB NUMBER 1</b>
1420	907-403-B007	(BA1 )	5,898	Ton	Hot Mix Asphalt, ST, 12.5-mm mixture, Leveling <b>ALTERNATE GROUP BB NUMBER 2</b>
1430	907-403-N002	(BA1 )	5,898	Ton	Warm Mix Asphalt, ST, 12.5-mm mixture, Leveling <b>ALTERNATE GROUP CC NUMBER 1</b>
1440	907-403-E001	(BA1 )	18,333	Ton	Hot Mix Asphalt, HT, 12.5-mm mixture, Polymer Modified, Leveling <b>ALTERNATE GROUP CC NUMBER 2</b>
1450	907-403-Q002	(BA1 )	18,333	Ton	Warm Mix Asphalt, HT, 12.5-mm mixture, Polymer Modified, Leveling <b>ALTERNATE GROUP DD NUMBER 1</b>
1460	907-403-E002	(BA1 )	206	Ton	Hot Mix Asphalt, HT, 19-mm mixture, Polymer Modified, Leveling <b>ALTERNATE GROUP DD NUMBER 2</b>
1470	907-403-Q003	(BA1 )	206	Ton	Warm Mix Asphalt, HT, 19-mm mixture, Polymer Modified, Leveling <b>ALTERNATE GROUP EE NUMBER 1</b>
1480	907-403-A011	(BA1 )	12,296	Ton	Hot Mix Asphalt, ST, 12.5-mm mixture <b>ALTERNATE GROUP EE NUMBER 2</b>
1490	907-403-M003	(BA1 )	12,296	Ton	Warm Mix Asphalt, ST, 12.5-mm mixture <b>ALTERNATE GROUP FF NUMBER 1</b>
1500	907-403-A012	(BA1 )	2,336	Ton	Hot Mix Asphalt, ST, 19-mm mixture <b>ALTERNATE GROUP FF NUMBER 2</b>
1510	907-403-M004	(BA1 )	2,336	Ton	Warm Mix Asphalt, ST, 19-mm mixture <b>ALTERNATE GROUP GG NUMBER 1</b>
1520	907-403-A015	(BA1 )	6,491	Ton	Hot Mix Asphalt, ST, 9.5-mm mixture <b>ALTERNATE GROUP GG NUMBER 2</b>
1530	907-403-M001	(BA1 )	6,491	Ton	Warm Mix Asphalt, ST, 9.5-mm mixture <b>ALTERNATE GROUP HH NUMBER 1</b>
1540	907-403-D004	(BA1 )	25,335	Ton	Hot Mix Asphalt, HT, 9.5-mm mixture, Polymer Modified <b>ALTERNATE GROUP HH NUMBER 2</b>
1550	907-403-P001	(BA1 )	25,335	Ton	Warm Mix Asphalt, HT, 9.5-mm mixture, Polymer Modified <b>ALTERNATE GROUP II NUMBER 1</b>

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
1560	907-403-D001	(BA1 )	22,640	Ton	Hot Mix Asphalt, HT, 12.5-mm mixture, Polymer Modified
<b>ALTERNATE GROUP II NUMBER 2</b>					
1570	907-403-P002	(BA1 )	22,640	Ton	Warm Mix Asphalt, HT, 12.5-mm mixture, Polymer Modified
<b>Bridge Items</b>					
1580	202-B010		369	Square Yard	Removal of Bridge End Pavement
1590	202-B036		241	Square Yard	Removal of Concrete Slope Paving
1600	202-B307		15	Square Yard	Removal of Bridge Deck
1610	502-A001	(C )	433	Square Yard	Reinforced Cement Concrete Bridge End Pavement
1620	801-A001	(S )	308	Cubic Yard	Foundation Excavation for Bridges
1630	803-B002	(S )	2	Each	Conventional Static Pile Load Test [\$5,000.00]
1640	803-D007	(S )	13,875	Linear Feet	HP 14 x 89 Steel Piling
1650	803-I001	(S )	3	Each	PDA Test Pile
1660	803-J001	(S )	1	Each	Pile Restrike
1670	803-N001	(S )	180	Linear Feet	Exploration
1680	803-O007	(S )	180	Linear Feet	Temporary Casing, 42" Diameter
1690	805-A001	(S )	107,982	Pounds	Reinforcement
1700	813-A002	(S )	290	Linear Feet	Concrete Railing, 32"
1710	815-A009	(S )	2,816	Ton	Loose Riprap, Size 300
1720	815-D001	(S )	17	Cubic Yard	Concrete Slope Paving
1730	907-803-K007	(S )	510	Linear Feet	Drilled Shaft, 42" Diameter
1740	907-803-M006	(S )	85	Linear Feet	Trial Shaft, 42" Diameter
1750	907-804-A001	(S )	578	Cubic Yard	Bridge Concrete, Class AA
1760	907-809-PP001	(S )	1	Lump Sum	Support Wall System
1770	907-813-PP001	(S )	14	Linear Feet	Concrete Railing, 32", Per Plans
1780	907-824-PP038		14	Each	Neoprene Bearing Pads
1790	907-824-PP095		2	Each	Bridge Repair, Emergency Support System Installation
1800	907-824-PP095		2	Each	Bridge Repair, Emergency Support System Materials