

Call 07 Mill & Overlay approximately 7 miles of SR 21 from Steele to Sebastopol, known as State Project No. MP-5021-62(010) / 305111301 in Scott County.

Q1. **1.)** Will additional time be considered, the time given of 47 productive days is inadequate with the schedule constraints such as all failed areas being completed prior to allowing milling to start, traffic not being allowed on milled surfaces, and the areas limited by the Engineer 's judgment on production doesn't allow the contractor to produce at full capacity. Also, a railroad permit, per the instructions on obtaining the permit state very clearly that it will take at least 3 weeks to obtain a permit from the railroad. **2.)** The existing roadway ditch 557+00--561+00 shall be deepened and graded to provide drainage. How is this excavation to be paid for? **3.)** Are temporary erosion control items to be required in this area? **4.)** Will an erosion control plan be required? **5.)** MDOT shall retain up to 10000 tons of milling. Milling quantities of 110890 s.y. milled @ 2" will yield 10,978 tons of material Does MDOT expect the total milling material? Will milled material have to be weighed for MDOT?

A1. **1.)** See the addendum for the project **2.)** It will be paid with Excess Excavation **3.)** Yes, ditch liner and solid sod will be utilized. **4.)** No **5.)** See the addendum for this project.